

**Big Sandy Plant,  
Unit 2  
WFGD Project  
PHASE I REPORT  
Engineering Services**

Report No. AEBS-2-LI-012-0001, Rev. 0

presented to



December 30, 2004

**Table of Contents**

|           | <i>Page</i>  |
|-----------|--|
| Section 1 | Executive Summary ..... 1-1                                      |
| Section 2 | Study Description ..... 2-1                                      |
|           | 2.1 Characteristics of Existing Unit ..... 2-1                   |
|           | 2.2 Proposed Sulfur Emissions Control ..... 2-1                  |
|           | 2.3 Scope of Work ..... 2-1                                      |
|           | 2.4 Deliverables ..... 2-2                                       |
| Section 3 | Conceptual Design Basis ..... 3-1                                |
|           | 3.1 Introduction..... 3-1  |
|           | 3.2 As-Fired Coal Composition..... 3-1                           |
|           | 3.3 Ambient Conditions ..... 3-3                                 |
|           | 3.4 Coal Composition..... 3-3                                    |
|           | 3.5 Limestone Composition..... 3-4                               |
|           | 3.6 WFGD Absorber..... 3-4                                       |
|           | 3.7 Dewatering..... 3-5  |
|           | 3.8 Electrical ..... 3-6   |
|           | 3.9 Control Systems..... 3-6                                     |
| Section 4 | Description of Conceptual Design ..... 4-1                       |
|           | 4.1 Process Flow Diagrams and Material Balance..... 4-1          |
|           | 4.2 Process Equipment List ..... 4-3                             |
|           | 4.3 Conceptual Electric Load List ..... 4-4                      |
|           | 4.4 Conceptual Electrical One Line diagram ..... 4-4             |
| Section 5 | Conceptual Plot Plans and General Arrangement Drawings ..... 5-1 |
|           | 5.1 Summary..... 5-1   |
|           | 5.2 Recommended Plot Plan..... 5-1                               |
|           | 5.3 Plot Plan Development Criteria..... 5-2                      |
|           | 5.4 General Arrangements ..... 5-3                               |
|           | 5.5 Stack Location ..... 5-4                                     |
|           | 5.6 Big Sandy Unit 1 Layout Considerations..... 5-4              |

**Table of Contents**

|                   | <i>Page</i>   |
|-------------------|---|
| <b>Section 6</b>  | <b>Phase IIa Objectives ..... 6-1</b>   |
|                   | 6.1 Introduction..... 6-1   |
|                   | 6.2 Major Issues to be Addressed in Phase IIa ..... 6-2                           |
| <b>Section 7</b>  | <b>Big Sandy Unit 1 Incremental Issues ..... 7-1</b>                              |
|                   | 7.1 Incremental Issues with Adding WFGD to Big Sandy Unit 1 ..... 7-1             |
|                   | 7.2 Incremental Issues with Adding SCR to Big Sandy Unit 1 ..... 7-2              |
|                   | 7.3 Incremental Costs Associated with Adding Unit 1 ..... 7-2                     |
| <b>Section 8</b>  | <b>Summary of Phase I..... 8-1</b>  |
|                   | 8.1 Schedule Basis..... 8-1   |
|                   | 8.2 Project Critical Path..... 8-2  |
|                   | 8.3 Engineering Schedule..... 8-2   |
|                   | 8.4 Division of Work ..... 8.3  |
|                   | Exhibit 8.1 - Schedule  |
|                   | Exhibit 8.2 – Division of Work  |
| <b>Appendix A</b> | <b>WFGD Material Balance Tables and Process Flow Diagrams</b>                     |
| <b>Appendix B</b> | <b>Plot Plans and General Arrangement Drawings</b>                                |
| <b>Appendix C</b> | <b>Process Equipment List</b>   |
| <b>Appendix D</b> | <b>Conceptual Electrical One Line Diagram and Conceptual Electrical Load List</b> |

Parsons E& C was chosen by the American Electric Power Services Corporation (AEPSC) to assist in their efforts to retrofit a Wet Flue Gas Desulfurization System at the Kentucky Power Company's Big Sandy Plant, Coal Fired Electric Generating Unit 2.

The overall project will consist of several different phases as defined below:

- Phase I – Conceptual Engineering and Planning
- Phase II – Scope Definition and Project Planning
- Phase III – Project Execution

These are further defined in AEPSC's Specification PE-BS12-TS-0001.

This report has been prepared at the conclusion of Phase I activity to document the work performed. The work elements developed comprise of the following:

- Conceptual Plot Plans (various alternatives including recommended preliminary layout)
- Conceptual System Descriptions
- Conceptual General Arrangements
- Conceptual Onelines
- Conceptual Process Flow Diagrams and Material Balances
- Proposal for Phase IIa (submitted separately)
- Listing of Outstanding Issues and Studies to be resolved / performed during Phase IIa
- Incremental issues associated with the addition of an SCR on Unit 1
- Incremental issues associated with Unit 1 being added to the Unit 2 absorber (two units into one vessel).
- Phase IIa Conceptual Schedule

Throughout this project, we will continuously review all decisions by measuring them based on their effects on safety, reliability, schedule, and cost.

Since Parsons E&C is currently providing similar services for the Mitchell Plant WFGD System, the AEPSC and Parsons E&C Tier II team has been capitalizing on the experience gained from that effort and will continue to build upon it. Many studies and evaluations were performed and we will build upon acquired knowledge as we move forward on this project. Where site-specific issues are concerned, these will be considered and tailored to the project.

In an effort to mitigate the risks that could potentially impede successful completion of the project, the AEPSC and Parsons E&C Tier II team has identified many actions that need to be addressed in the next Phase of the project. A complete listing of these major open issues is included in Section 6. These issues will be addressed during the early part of the next phase and be scheduled logically to sequence activities that ensure a complete, integrated plan as depicted below.



Following is a partial list of the major Phase IIa studies/evaluations to be completed:

- Boiler upgrade engineering scope definition to be included in Parsons E&C’s scope of work
- Determination of limestone delivery methodology to be implemented at the plant
- Gypsum disposal options
- Service water source determination and treatment method
- System blowdown options and determination of proper treatment method(s)
- Permitting support for various recent options related to dust generation from trucks and materials handling

**Section 1**

**Executive Summary**

- Fixing the stack location once an FGD OEM supplier is determined
- Potential examination of applying an emissions control technology to Big Sandy Unit 1.

## 2.1 Characteristics of Existing Unit

---

Big Sandy Unit #2 is a pulverized coal wall fired unit with a dry bottom pressurized boiler. The nominal unit rating, prior to FGD conversion, is 865 MW gross and 800 MW net. The full load firing rate is 8,180 MM Btu/hr and the minimum load firing rate is 3,017 MM Btu/hr. The unit has a Ljungstrom Rotary Tri-Sector air heater, a cold electrostatic precipitator (ESP), and low NO<sub>x</sub> burners. Ignition fuel is #2 oil. The unit has been retrofitted with an SCR for additional NO<sub>x</sub> control. Booster fans were added as part of the SCR installation. It will be necessary to lower SO<sub>2</sub> emissions to meet the requirements of the AEPSC Fleet SO<sub>2</sub> Compliance Plan.

## 2.2 Proposed Sulfur Emissions Control

---

The proposed method to lower SO<sub>2</sub> emissions at Big Sandy Unit #2 is to retrofit a Wet Flue Gas Desulfurization (WFGD) system that will allow burning of Northern Appalachian Basin or Illinois Basin high sulfur coals with a sulfur content of up to 4.5 lb SO<sub>2</sub>/MM Btu. The WFGD system will be designed to have an SO<sub>2</sub> removal efficiency of 98% and will utilize 92% active calcium carbonate limestone to produce wallboard grade gypsum.

## 2.3 Scope of Work

---

The scope of work includes Phase I conceptual engineering and design for retrofit of a WFGD system at Big Sandy Unit # 2 as part of the AEPSC Fleet SO<sub>2</sub> Compliance Plan. The overall scope is divided into two packages: the current work package and the follow on work proposal package. The deliverables associated with the current work package are as follows:

- Conceptual Plot Plan including Stack Location
- Conceptual General Arrangement Drawings
- Conceptual Process Flow Diagrams
- Conceptual Mass Balance Diagrams
- Phase I Report addressing cost, schedule, benefits and risks
- Summary of Open Items and Issues
- Discussion of Incremental issues associated with addition of a WFGD System on Unit 1, utilizing a single absorber (both Units 1 and 2 into one system)

## Section 2

## Study Description

- Discussion of Incremental issues associated with installing an SCR system on Unit 1, in addition to the WFGD system

In addition, Phase I work includes the preparation of a summary proposal to progress the Project into Phase IIa. This report defines a schedule and engineering/design costs required to progress the work to approximately 15 % completion and develop an estimate of the overall project cost.

Key criteria for performance of the Phase I work are as follows:

- In general, follow the Mitchell project decisions and design criteria and approach.
- Base the recommended layouts on subjective comparisons/estimates.  
The design will assume the absorber is an open spray tower or tray design.

## 2.4 Deliverables

---

The following deliverables have been prepared and issued to fulfill requirements of the scope of work:

- Plot plan drawings 2-5070000A-A, 2-5070000B-A, 2-5070000C-B, 2-5070000D-A, 2-5070000E-A, 2-5070001A-A, 12-5070000A-A, 12-5070000B-A, and 12-5070000D-B
- General Arrangement drawings 2-5070002A-A, and 2-5070003A-A, and 2-5070004A-A.
- Process Flow diagrams 2-51070000-B, 2-51070001-A, 2-51070002-A, 2-51070003-A, and 2-51070004-B
- Boiler and FGD Material Balance Estimate Calculation AEBS-2-DC-042-5-001, Rev. 0 which has process data keyed to nodes on the Process Flow Diagrams
- Big Sandy Unit #2 FGD Process Equipment List AEBS-2-LI-022-0001, Rev. 0.
- Proposal for Big Sandy Unit #2 Phase IIa, dated 11/30/04
- Big Sandy Unit #2 Phase I Report AEBS-2-LI-012-0001, Rev. 0, dated 12/30/04.

In addition, deliverables are included which present the conceptual configuration of the electrical distribution system, and a preliminary list of electrical loads to be served by the system:

**Section 2**

**Study Description**

- Unit 2 FGD Conceptual One Line Diagram AEBS-2-SK-EZ-206-001-A
- Unit 2 FGD Conceptual Electrical Load List AEBS-2-LI-023-0001-B

### 3.1 Introduction

---

Big Sandy Unit 2 is located in Lawrence County, Kentucky, approximately 20 miles north of Louisa. The unit consists of a nominal net 800 MWe coal-fired steam turbine power cycle with an operating selective catalytic reduction (SCR) unit. It is proposed that a WFGD process be applied to the unit to mitigate SO<sub>2</sub> emissions. To that end, Parsons E&C has prepared material balances -- with estimated flow rates and temperatures, plot plans and general arrangement drawings showing stack location and real estate requirements, equipment and electric load lists, as well as an electrical one-line diagram. The drawings and results of these efforts will be presented in subsequent sections of this report. The purpose of this section is to summarize the design input that went into generating the results contained within. All of the values discussed or listed in this section are also summarized in Parsons E&C design calculation AEBS-2-DC-042-5-001.

It is assumed that Big Sandy Unit 2 will undergo a pressurized to balanced-draft conversion and that the currently operating booster fans will be replaced by induced draft (ID) fans. ID fans will be required to operate the boiler and overcome the added ductwork and absorber pressure drop. The WFGD process is assumed to utilize either a tray or spray tower-type absorber and generate wallboard quality gypsum product. The reagent is assumed to be 92 percent "available" calcium carbonate (CaCO<sub>3</sub>).

### 3.2 As-Fired Coal Composition

---

It is proposed that Big Sandy Unit 2 will fire a blend of Northern Appalachian Basin or Illinois Basin high sulfur coal up to 4.5 lbs SO<sub>2</sub>/MMBtu. The expected as-fired coal proposed in AEP's Specification BS-12-AECE-093004 is shown in Table 3-A.

The coal composition in Table 3-A is shown on both a "wet" and "dry" basis. Both bases are shown because AEP Specification BS-12-AECE-093004 shows the coal composition on a "dry" basis and the input to the material balance (shown in Appendix A) shows the coal on a "wet" basis. The table is convenient for immediate side-by-side comparison.

Another feature of the coal composition shown in Table 3-A is that there is a column taken directly from AEP Specification BS-12-AECE-093004 and a second labeled "Parsons E&C". The coal composition shown under column "Parsons E&C" is the actual coal used in the material balance presented in this report. The coal from AEP Specification BS-12-AECE-

**Section 3**

**Conceptual Design Basis**

093004 has a sulfur content that generates 4.31 lb SO<sub>2</sub>/MMBtu. The coal shown in column “Parsons E&C” of Table 3-A has been modified such that a true value of 4.5 lb SO<sub>2</sub>/MM Btu is produced. This was affected by increasing the “wet-basis” sulfur weight percent of coal from 2.69 percent to 2.81 percent. The difference, 0.12, was subtracted out of the coal oxygen content. It should be noted that a similar adjustment was made on chlorine and fluorine. By adjusting the coal to the expected maximum sulfur and chlorine levels a better representation of the WFGD process can be generated.

Table 3-A Big Sandy Design Coal Composition

|                             | AEP BS-12-AECE-093004 |           | Parsons E&C |           |
|-----------------------------|-----------------------|-----------|-------------|-----------|
|                             | Wet Basis             | Dry Basis | Wet Basis   | Dry Basis |
| Fixed Carbon                | 47.33                 |           | 47.33       |           |
| Volatile Matter             | 36.15                 |           | 36.15       |           |
| Moisture                    | 6.63                  |           | 6.63        |           |
| Ash                         | 9.89                  |           | 9.89        |           |
| Total                       | 100.00                |           | 100         |           |
| Sulfur                      | 2.69                  |           | 2.81        |           |
| Heating Value, Btu/lb       | 12,490                |           | 12,490      |           |
| lb SO <sub>2</sub> / MM Btu | 4.31                  |           | 4.5         |           |
| Carbon                      | 69.33                 | 74.25     | 69.33       | 74.25     |
| Hydrogen                    | 4.67                  | 5.00      | 4.67        | 5.00      |
| Nitrogen                    | 1.33                  | 1.43      | 1.33        | 1.43      |
| Chlorine                    | 0.05                  | 0.05      | 0.20        | 0.214     |
| Fluorine                    | 0.00                  | 0.00      | 0.002       | 0.002     |
| Moisture                    | 6.63                  | -         | 6.63        | -         |
| Ash                         | 9.89                  | 10.59     | 9.89        | 10.59     |
| Sulfur                      | 2.69                  | 2.88      | 2.81        | 3.00      |
| Oxygen                      | 5.41                  | 5.8       | 5.138       | 5.514     |
| Total                       | 100.00                | 100.00    | 100.00      | 100.00    |

**Section 3**

**Conceptual Design Basis**

**3.3 Ambient Conditions**

The ambient conditions that were used in the results generated in this report are summarized in Table 3-B. These values are taken directly from AEP Specification BS-12-AECE-093004.

**Table 3-B Big Sandy Ambient Conditions**

|                       |                        |
|-----------------------|------------------------|
| Barometric Pressure   | 29.3 inches Hg         |
| Inlet Air Temperature | 56.1 °F                |
| Relative Humidity     | 70 %                   |
| Vapor Pressure        | 0.223 psia             |
| Elevation             | 568 ft above sea level |

**3.4 Coal Combustion**

Accurate portrayal of the gas flow to the absorber is important for absorber sizing, estimating reagent requirements, purge stream composition, and product generation, as well as estimating large electrical loads such as those associated with the ID and absorber recycle pumps. Parsons E&C completed a combustion calculation based on input from AEP specification BS-12-AECE-093004 in order to characterize the flue gas flow to the absorber and estimate ID fan pressure rise and motor requirements. The primary inputs used in the calculation are summarized in Table 3-C.

**Table 3-C Combustion Calculation Inputs**

|                              |   |
|------------------------------|---|
| MCR Thermal Input            | 8,180 MMBtu/hr  |
| Fuel HHV – Design Basis Coal | 12,490 Btu/lb   |
| Coal Sulfur Content          | 4.5 lb SO <sub>2</sub> /MMBtu                                 |
| Excess Air                   | 21% Furnace Excess Air<br>20% Air Heater Leakage / In-Leakage |
| SCR Pressure Drop            | 8.5 inches H <sub>2</sub> O                                   |
| ID Fan Pressure Increase     | 40.5 inches H <sub>2</sub> O                                  |
| ID Fan Inlet Temperature     | 321 °F  |

**Section 3**

**Conceptual Design Basis**

**3.5 Limestone Composition**

The limestone composition used in this study is shown in Table 3-D. This limestone, with an available CaCO<sub>3</sub> content of 92 percent, is a premium brand capable of generating wallboard-grade gypsum when utilized by an appropriate WFGD technology.

Table 3-D Limestone Composition

| Dry Basis, Percent (%) by weight               | Nominal |
|--|---------|
| Calcium Carbonate available, CaCO <sub>3</sub> | 92.0    |
| Total Magnesium Carbonate, MgCO <sub>3</sub> * | 3.0     |
| Inerts   | 5.0     |
| Total  | 100.0   |
| Free Moisture                                  | <5.0%   |

\* Maximum allowable insoluble MgCO<sub>3</sub> content of 1.5% (Nominal quality)

**3.6 WFGD Absorber**

As an FGD OEM has not been chosen at this point, and giving consideration to the gross unit size of the power station, a generic spray/tray FGD absorber module was modeled and sized for this effort. The arrangement of the absorber and stack provides space for the future installation of a wet electrostatic precipitator (SO<sub>3</sub> mitigation). Table 3-E summarizes the absorber process input parameters used to generate the results presented in this report.

Table 3-E Absorber Parameters

| Parameter                             | Value |
|---------------------------------------|-------|
| SO <sub>2</sub> Removed, %            | 98    |
| SO <sub>3</sub> Removed, %            | 30    |
| L/G                                   | 115   |
| Water Entrainment, grains/SCF         | 0.01  |
| SO <sub>2</sub> Oxidized in System, % | 99.5  |

**Section 3**

**Conceptual Design Basis**

| Parameter                            | Value    |
|--------------------------------------|----------|
| Reaction Tank Type                   | Straight |
| Gas velocity, ft/sec                 | 13       |
| Inlet/Outlet Duct Velocities, ft/sec | 50       |
| Maximum Recycle Pump Flow, gpm       | 75,000   |
| Solids in Reaction Tank, %           | 20       |

**3.7 Dewatering**

Primary dewatering is assumed to be completed by hydroclone clusters. Each cluster is assumed to produce a 50 weight percent solid product. Hydrocyclone overheads flow to a head tank that drains to the reclaim water tank. Blowdown is removed from the hydrocyclone overheads. Secondary dewatering is assumed to be accomplished by vacuum belt filters. The assumed solids recovery for the belt filters is 98 percent. Wallboard grade gypsum, with greater than 93 percent gypsum,  $\text{CaSO}_4 \bullet 2\text{H}_2\text{O}$ , purity and less than 100 ppm (dry) chlorides, will be produced by the belt filter system. Cake wash, cloth wash, and system make-up water is assumed to have the composition shown in Table 3-F.

Table 3-F River Water Analysis

| Parameter              | Value |
|------------------------|-------|
| SO <sub>4</sub> (ppmv) | 53    |
| Ca (ppmv)              | 60    |
| Cl (ppmv)              | 19    |
| Na (ppmv)              | 0     |
| Mg (ppmv)              | 50    |

### 3.8 Electrical

---

The Conceptual Electrical Load List (AEBS-2-LI-023-0001) and the Conceptual One Line Diagram (AEBS-2-SK-EZ-206-001) are based on the following:

- Big Sandy Unit 2 Process Equipment List FPCS-C1-LI-537498-0001.
- Mitchell FGD/SCR Project Electrical Load List AEPM-12-LI-023-0001 – for non-process load identification and magnitude only.
- Mitchell FGD/SCR Project Key One Line Diagram 12-121001 – for general bus arrangement and drawing content.

### 3.9 Control Systems

---

The control system for the FGD and the Balance of Plant (BOP) systems that are required to support the FGD will be an extension of the existing Emerson plant DCS. The I/O output devices will be remote mounted near the source of the inputs in several locations within and near the FGD buildings. The remote I/O will be connected to the existing DCS via redundant fiber optic cables. The logic for the FGD equipment in the FGD vendor's scope will be designed by the FGD vendor with Parsons E&C as the reviewer. Logic for auxiliary BOP systems supporting the FGD will be designed by Parsons E&C.

Equipment such as new I/O racks or cards that will be required to support the boiler balanced draft conversion will be placed in the proximity of existing equipment. Suggested logic for the control of the ID fans will be developed by Parsons E&C however final logic and implementation will be by AEP.

## 4.1 Process Flow Diagrams and Material Balance

Flue gas generated in the coal-fired Big Sandy Unit 2 boiler will be treated in a WFGD process to mitigate SO<sub>2</sub> emissions. The WFGD system will be designed for an overall SO<sub>2</sub> removal efficiency of 98 %. It is proposed that the unit will fire a blend of Northern Appalachian or Illinois Basin high sulfur coal with up to 4.5 lb SO<sub>2</sub>/MMBtu and have a full-load thermal input of 8,180 MMBtu/hr. This section contains a brief system description illustrated by several Process Flow Diagrams (PFDs). The PFDs show a simplified schematic of the principal process system equipment as well as the envisioned equipment redundancy. To support the PFDs, a material balance showing the composition and state points of the primary process streams is presented in Appendix A.

The nominal 800 MW net Unit 2 will be converted from pressurized operation to balanced draft operation. Flue gas will be ducted from the "existing" ESP to "new" induced draft (ID) fans. It is envisioned that two new axial ID fans be used to accommodate the increased furnace gas path pressure drop and overcome the resistance induced by the addition of the WFGD. Provisions have been made, including the consideration of added pressure drop and the allocation of physical space, for a mercury control system that may be added if future conditions warrant. In its present form, the mercury control technology is in the form of in-duct activated carbon injection and baghouse downstream of the existing ESP and prior to the ID fan inlet. The ductwork downstream of each ID fan discharge will converge to a common duct and continue to the WFGD absorber. A schematic illustrating the gas-path ductwork on the suction and discharge of the new ID fans is shown in drawing 2-517001-A.

Big Sandy Unit 2 will be provided with a single WFGD absorber. Flue gas discharged from each of the two ID fans will be ducted together and routed to the absorber inlet duct. The PFD for the absorber is shown on drawing 2-5170003-A. The absorber will use ground limestone slurried in water as the SO<sub>2</sub> removal reagent. The absorber will likely be either a tray or spray tower and will utilize absorber recycle pumps to provide an adequate liquid to gas ratio within the absorber tower. Limestone slurry will be fed to replenish the calcium consumed in the desulfurization reactions. Oxidation air blowers will supply low-pressure air to the absorber reaction tank in order to oxidize the calcium sulfite to calcium sulfate (gypsum). Oxidation air will be distributed evenly throughout the reaction area such that high sulfite conversion levels are attained. Bleed pumps transfer a water slurry of gypsum product, unreacted reagent, captured flyash, and inert solid

Dated January 13, 2012

Attachment No. 2

ISSUES FOR INFORMATION

| NO. | DATE     | BY | REVISION               |
|-----|----------|----|------------------------|
| 1   | 01/13/12 | AW | ISSUED FOR INFORMATION |

**PARSONS E&C**  
KENTUCKY POWER CORPORATION  
BIG SANDS PLANT  
PROCESS FLOW DIAGRAM  
COMBUSTION AIR AND FUEL GASES  
UNIT 2


DESIGNED BY: [ ]  
CHECKED BY: [ ]  
APPROVED BY: [ ]  
DATE: [ ]

PROJECT NO.: [ ]  
DRAWING NO.: 2-517001-A

SCALE: [ ]

REVISIONS:

| NO. | DATE     | DESCRIPTION            |
|-----|----------|------------------------|
| 1   | 01/13/12 | ISSUED FOR INFORMATION |



**PARSONS E&C**  
KENTUCKY POWER CORPORATION  
BIG SANDS PLANT  
PROCESS FLOW DIAGRAM  
COMBUSTION AIR AND FUEL GASES  
UNIT 2


DESIGNED BY: [ ]  
CHECKED BY: [ ]  
APPROVED BY: [ ]  
DATE: [ ]

PROJECT NO.: [ ]  
DRAWING NO.: 2-517001-A

SCALE: [ ]

REVISIONS:

| NO. | DATE     | DESCRIPTION            |
|-----|----------|------------------------|
| 1   | 01/13/12 | ISSUED FOR INFORMATION |



1007001-2-517001



## Section 4

## Description of Conceptual Design

material to dewatering. A sump area will be provided and will be equipped with sump pumps that return the collected drains to the absorber reaction tanks.

Scrubbed flue gas from the absorber will be ducted to a new chimney. The chimney will have a single flue designed for wet operation. The chimney will be of reinforced concrete construction with a fiberglass reinforced plastic (FRP) flue equipped with liquid collection and drainage systems. Space has been allotted in the system arrangement for the future addition of an elevated, horizontal flow, stand-alone wet ESP (WESP) for fine particulate and SO<sub>3</sub> mist removal downstream of the absorber. The chimney and WESP are shown schematically in drawing number 2-5170003-A.

Full load operation of Unit 2 firing the design coal consumes approximately 775 tons of 92 % “active” calcium carbonate (CaCO<sub>3</sub>) limestone per day. Limestone will be fed from a storage pile to silos located within the limestone preparation building. Two wet grinding ball mill systems will be installed. The mill systems will be located in the reagent preparation building. The mills produce limestone ground to 95% passing 325 mesh. The ground limestone will be slurried with water that is either reclaimed from the dewatering process or with make-up water from the service water tank. The reagent slurry feed pumps forward the reagent slurry to the absorbers through a double pipe loop (independent) feed system. The reagent preparation building will be provided with an area sump for collection of slurry from process drains. The sump will be provided with two sump pumps that return the collected slurry to the limestone slurry storage tanks. The reagent preparation system is illustrated in drawing number 2-5170000-B.

Gypsum dewatering will consist of two stages: primary and secondary. Primary dewatering will be achieved by hydrocyclone classification. Secondary dewatering will be accomplished with horizontal belt vacuum filters. A hydrocyclone cluster will be mounted above each vacuum belt filter. Hydrocyclone feed pumps will feed slurry from the feed tanks to the hydrocyclone classifiers. Overflow from the hydrocyclones will discharge through a common manifold to one overflow head tank. The head tank will overflow to a reclaim water tank. The reclaimed water will be returned to the absorber and/or the limestone grinding system to maximize the utilization of water and unreacted limestone contained in the hydroclone overflow. Underflow from each hydrocyclone classifier will be delivered to its associated belt filter. A simplified system arrangement for the

Dated January 18, 2012

Kenestry Process Company  
BIG SANDY PLANT  
REAGENT PREPARATION SYSTEM  
UNIT 2


**PARSONS ESC**

PROJECT NUMBER: 000015-2 ON 2M4  
PROJECT LOCATION: BIG SANDY PLANT, KENTUCKY  
PROJECT DESCRIPTION: REAGENT PREPARATION SYSTEM UNIT 2  
DRAWN BY: [Name]  
CHECKED BY: [Name]  
DATE: [Date]

REVISIONS:

| NO. | DATE | DESCRIPTION            |
|-----|------|------------------------|
| 1   |      | ISSUED FOR INFORMATION |
| 2   |      | ISSUED FOR INFORMATION |
| 3   |      | ISSUED FOR INFORMATION |
| 4   |      | ISSUED FOR INFORMATION |
| 5   |      | ISSUED FOR INFORMATION |
| 6   |      | ISSUED FOR INFORMATION |
| 7   |      | ISSUED FOR INFORMATION |

APPROVED BY: [Signature]  
DATE: [Date]



000015-2 ON 2M4

Kenestry Process Company  
BIG SANDY PLANT  
REAGENT PREPARATION SYSTEM  
UNIT 2

FROM LIMESTONE HANDLING SYSTEM  
DUST  
FROM FILTERATE PUMPS  
TO ABSORBER  
TO ABSORBER

hydrocyclones and overflow tank is shown in Drawing 2-5170003-A along with the absorber configuration.

Vacuum belt filters will be used to dewater hydrocyclone underflow to produce gypsum containing less than 10 percent moisture. The gypsum product will be conveyed to a storage pile at a rate up to 56 tph. Fresh makeup water, filtered and biologically treated river water, will be provided as seal water to the vacuum pumps and for washing the gypsum filter cake. Vacuum filter filtrate will be collected together with hydroclone overflow in the reclaim water tanks, and returned to the absorber reaction tank and/or ball mill grinding system by the two reclaim water pumps. The basic configuration of the vacuum belt filter system is shown on drawing 2-5170004-B. Sump pumps will be provided in the vacuum belt filter area to return collected liquids to the reclaim water tanks.

The concentration of chlorides, and/or solid fines material, in the absorber reaction tank will be controlled by an FGD blowdown or purge stream. The blowdown stream may or may not be treated prior to being routed to its ultimate destination, which may be a dedicated pond or the bottom ash pond. The source of the FGD blowdown stream will be the hydroclone overflow head tanks as shown on drawing 2-5170003-A.

The FGD system requires significant quantities of makeup water to compensate for: water lost through evaporation in the FGD absorber, water lost with the FGD gypsum filter cake, and that purged from the system (blowdown) to control the concentration of chlorides and/or fines in the absorber. Strained, biologically treated, filtered water from the Big Sandy River, will be stored in the makeup service water tank from where it will be pumped to the various fresh water users. A schematic of the service water tank is shown in Figure 2-5170002-A. FGD service water pumps will provide fresh water to the absorber mist eliminator and oxidation air quench. The balance-of-plant service water pumps provide water to limestone grinding, vacuum pump seal water, water for slurry piping system flush out, for makeup (initial fill) of the absorbers, and for make-up to the reclaim tank.

## 4.2 Process Equipment List

---

The process flow diagrams, described above, and conceptual design criteria, presented in Section 3, were used to generate mass balances (Appendix A) of the conceptual combustion and WFGD systems. The process equipment list is shown in Appendix C. The equipment list is for reference only and not the product of detailed design. The equipment list in



Dated January 18, 2012

Attachment 2  
Page 8

ISSUED FOR INFORMATION

| NO. | REV. | DATE | DESCRIPTION            |
|-----|------|------|------------------------|
| 1   | 1.0  |      | ISSUED FOR INFORMATION |

THIS DRAWING IS THE PROPERTY OF PARSONS E&C. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF PARSONS E&C.

**PARSONS E&C**  
 KENTUCKY PROJECT COMPANY  
 BIG SANDY PLANT  
 KENTUCKY  
 PROCESS FLOW DIAGRAM  
 MAKE-UP WATER SYSTEM  
 UNIT 2


FIG. NO. P-517002-A

DATE: 12/10/11  
 DRAWN BY: C. W. DANIELSON  
 CHECKED BY: J. M. HARRIS  
 PROJECT ENGINEER: J. M. HARRIS

PROJECT NUMBER: P-517002  
 PROJECT NAME: BIG SANDY PLANT  
 PROJECT LOCATION: BIG SANDY, KY

SCALE: AS SHOWN

PROJECT MANAGER: J. M. HARRIS  
 PROJECT ENGINEER: J. M. HARRIS  
 PROJECT SUPERVISOR: J. M. HARRIS



200415-2 ON 2046

Appendix C merely shows gross dimensions and equipment sizes and will change with refinements in design, margin application, and FGD OEM technology choice.

### 4.3 Conceptual Electrical Load List

---

The conceptual list of equipment to be powered by the Big Sandy Unit 2 FGD Electrical Distribution System is presented in Appendix D as List AEBS-2-LI-023-0001. Loads to be served by this system include those identified in the Process Equipment List (Appendix C), as well as projected non-process loads associated with FGD facilities lighting and HVAC systems, the new chimney, the new outdoor FGD substation, etc. The Appendix D list assigns process loads to electrical distribution system buses based on anticipated load power ratings, and on the desire to power redundant process loads from separate power sources. This latter approach will minimize process down time in the event of electrical equipment outages. The non-process loads are all envisioned to be 480V and are generally assigned to Common Load motor control centers to be located in load concentration areas.


The Electrical Load List is meant to account for all loads requiring electrical service; it is not the intent of the list to be used for the determination and optimization of bus demand loadings. Those analyses will be performed as part of the Phase II electrical system voltage studies. This Electrical Load List is envisioned to be a living document, to be expanded and updated as the Big Sandy FGD Project evolves.

### 4.4 Conceptual Electrical One Line Diagram

---

The conceptual One Line Diagram of the Big Sandy Unit 2 Electrical Distribution System is included in Appendix D as Sketch AEBS-2-SK-EZ-206-001. The distribution system configuration, which is an abbreviated version of the Mitchell Units 1 and 2 FGD electrical system, provides sufficient redundancy of electrical equipment to allow for full FGD (process) operations under most credible electrical equipment failure scenarios. In addition, a Common Load switchgear lineup is included in the configuration for powering non-process loads. This concept of separating process and non-process load buses evolved in the Mitchell FGD Project due to the high magnitude of the combined process and non-process loads and the resultant adverse impact on the distribution system steady state voltage.

Revised January 18, 2012



NOTES:

| ISSUES FOR INFORMATION |         |                        |
|------------------------|---------|------------------------|
| A                      | DATE    | DESCRIPTION            |
| 1                      | 1/18/12 | ISSUED FOR INFORMATION |

**PARSONS E&C**  
KENTUCKY POWER COMPANY  
BIO SANDY PLANT  
ELECTRICAL  
UNIT 2 FSD  
CONCEPTUAL ONE LINE DIAGRAM  
DRAWN BY: [Name]  
CHECKED BY: [Name]  
DATE: [Date]

| PROJECT INFORMATION |                  |
|---------------------|------------------|
| NO.                 | DESCRIPTION      |
| 1                   | PROJECT NO.      |
| 2                   | PROJECT NAME     |
| 3                   | PROJECT LOCATION |
| 4                   | PROJECT OWNER    |
| 5                   | PROJECT ENGINEER |
| 6                   | PROJECT CHECKER  |
| 7                   | DATE             |
| 8                   | SCALE            |
| 9                   | PROJECT NO.      |
| 10                  | PROJECT NAME     |
| 11                  | PROJECT LOCATION |
| 12                  | PROJECT OWNER    |
| 13                  | PROJECT ENGINEER |
| 14                  | PROJECT CHECKER  |
| 15                  | DATE             |
| 16                  | SCALE            |

**Section 4****Description of Conceptual Design**

The double-ended switchgear lineups depicted are operated with their tie breakers normally open, with each bus section receiving power from its incoming transformer and main breaker. In order to maintain continuity of service to all loads during an outage of any individual transformer supply, all transformers and buses will be rated to allow any single transformer in a double-ended switchgear arrangement to carry all load on a double-ended lineup. This will be achieved via manual or automatic closing of the lineup tie breaker in accordance with the control philosophy to be developed for the project.

Incoming power to the Big Sandy FGD Electrical Distribution System will likely be developed via modifications to the existing Big Sandy main 138kV switchyard – it is this method that is implied on the conceptual one line. Another option of FGD power supply would be to modify the existing Unit 2 SCR electrical distribution system, including 138-13.8kV transformers. This approach will be reviewed at the onset of Phase IIa; if adopted, the one line diagram will be revised accordingly. In any event, this one line will evolve, during Phase II, into the Big Sandy FGD Key One Line Diagram, complete with equipment identifiers and ratings.

The Appendix D conceptual One Line assumes that the new ID fans, intended for connection to 13.8kV Buses A and B, will be able to start and run satisfactorily with this connection without unacceptable degradation of system voltages. Should the horsepowers of the fan motors become too high for this configuration – resulting in unacceptable voltages during motor starting or steady state operation – connection of the motors in a different fashion will need to be investigated.

## 5.1 Summary

---

Two areas at the Big Sandy Site were considered for placement of the WFGD equipment and buildings. These are the areas north and south of Unit #2. In comparison to the north area, the south area is much smaller, has more existing underground utilities, would require relocation of warehouses and the Unit #2 Service Building, and would result in tight access to the south side of the Unit #2 boiler. One plot plan was considered for the south area. This is shown on drawing 2-507001A. Due to the disadvantages identified for the South arrangement, it is the least desirable of the areas considered.

The north area requires minimum utility relocation. The existing warehouse on the north side would not require relocation for the WFGD system. This warehouse may require relocation if a WESP is added in the future for SO<sub>3</sub> control. Extension of the existing 138 kV switchyard will require modification to the two 12" HDPE ash slurry lines that run north/south on the east side of the switchyard to the ash ponds across the highway. This relocation will be required regardless of the location of the WFGD equipment and buildings. It became apparent that the north area had many advantages over the south area, at which point emphasis was placed on the north area. Two plot plans were considered for this area: Option 1 and Option 2 as shown on drawings 2-5070000B and 2-5070000C, respectively. These plot plans were developed based on a tray tower type absorber. Arrangements for North Options 1 and 2, using an open tower type absorber, were also developed. An open tower absorber would increase the number of Absorber Recycle Pumps from five to eight, requiring a larger FGD Building. The drawings for the open spray tower arrangements are titled North Option – 1/8 and North Option – 2/8 and are shown on drawings 2-5070000E and 2-5070000D, respectively.

## 5.2 Recommended Plot Plan

---


The recommended plot plan for the WFGD buildings and equipment at Big Sandy Unit #2 is the North Option 2 arrangement, shown on drawing 2-5070000C for the tray tower type absorber and 2-5070000D for the open tower type absorber. These arrangements are similar to the North Option 1 arrangement with the following exception. The flue gas duct from the SCR outlet through the ID fans to the WFGD absorber inlet is oriented at a 35° angle from the east-west centerline of the existing stack, resulting in a lower pressure drop than the right angle arrangement in the North Option 1 design. Option 2 also moves the FGD buildings further to the east, in











comparison to Option 1, which allows the FGD substation and FGD station service transformers to be located closer to the existing 138 kV Substation. This transformer location is also closer to the FGD Building and the ID Fans, where the largest electrical loads are located. The extension of the existing 138 kV switchyard will be necessary to accommodate switchyard equipment additions for FGD substation bulk power feeds. This arrangement also allows space for efficient location of the field erected tanks so that they are nearest to the primary users, thus minimizing piping runs.

### 5.3 Plot Plan Development Criteria

---

In development of the plot plans, the following arrangement criteria have been considered:

- Minimize length of ductwork and pressure drop from the ESP outlet to the FGD absorber inlet.
- Ensure adequate space for operations and maintainability in and around the FGD Buildings and Equipment.
- Minimize the complexity of power transmission from the existing main 138 kV switchyard to the FGD substation, and from the FGD substation to the FGD electrical distribution equipment in the Absorber Building.
- Ensure adequate space for operations and maintainability of all existing Unit#1 and 2 buildings and equipment.
- Ensure adequate duct runs in and out of equipment to provide good flow distribution and minimal pressure drop.
- Provide conveyor access to minimize transfer points and complexity of the limestone and gypsum handling systems.
- Include gypsum dewatering on site even though pumping the slurry across the road to a dewatering pond will be considered in Phase II as an alternative to onsite dewatering.
- Locate the limestone silo bay in the Reagent Prep Building adjacent to the FGD Absorber Building to allow access to the top of the silos from the FGD Building.
- Minimize duct length between absorber and chimney while allowing sufficient space for large underground foundations.

## 5.4 General Arrangements

General Arrangements for the ground floor of the FGD Building, Reagent Prep Building and the Dewatering Area Building are shown on drawings 2-5070002A, 2-5070003A, and 2-5070004A, respectively. These general arrangements are based on the Mitchell Unit #1 and #2 tray tower design with modifications for single rather than two unit design. Redundancy of equipment is based on the Mitchell Station arrangement and criteria in the AEP Program Buying Guide for Major Process Equipment Sizing.

Mitchell Units #1 and #2 are sister units to Big Sandy Unit #2 with comparable heat input and flue gas flow rate. The Mitchell design is based on burning coal having a maximum sulfur content of 4.5 lb SO<sub>2</sub>/MM Btu for the current design with provision for future conversion to allow burning coal having a maximum sulfur content of 7.5 lb SO<sub>2</sub>/MM Btu. The current Mitchell design, downsized for a single unit and without provision for future higher sulfur coal capability, is a valid basis for the Big Sandy Unit 2 FGD arrangement.

Some of the equipment used in the Mitchell General Arrangements is oversized for the actual required duty. This is based on determining the required size of the equipment component and then picking the standard equipment size from the AEP Program Buying document that is equal to or larger than the required size. The AEP Program Buying document applies to the ball mills, vacuum belt filters, recycle pumps, oxidation air compressors and ID fans. It may be possible to downsize some of these components for Big Sandy Unit 2, if the Program Buying criteria is not applied and the actual required size equipment is purchased rather than a standard size. For the preliminary general arrangements, the equipment sizes shown are conservative.

Regarding redundancy, the major equipment, based on the Mitchell design, but adjusted in size for one unit at Big Sandy #2, is spared as follows:

- Two ball mills, 1 operating and 1 spare
- Two vacuum belt filters, 1 operating and 1 spare
- Five recycle pumps (based on tray tower absorber), 4 operating and 1 spare
- Two oxidation air compressors, 1 operating and 1 spare






|                               |             |
|-------------------------------|-------------|
| ISSUES FOR REVIEW AND COMMENT |             |
| NO.                           | DESCRIPTION |
| 1                             | ...         |
| 2                             | ...         |
| 3                             | ...         |
| 4                             | ...         |
| 5                             | ...         |
| 6                             | ...         |
| 7                             | ...         |
| 8                             | ...         |
| 9                             | ...         |
| 10                            | ...         |
| 11                            | ...         |
| 12                            | ...         |
| 13                            | ...         |
| 14                            | ...         |
| 15                            | ...         |
| 16                            | ...         |
| 17                            | ...         |
| 18                            | ...         |
| 19                            | ...         |
| 20                            | ...         |
| 21                            | ...         |
| 22                            | ...         |
| 23                            | ...         |
| 24                            | ...         |
| 25                            | ...         |
| 26                            | ...         |
| 27                            | ...         |
| 28                            | ...         |
| 29                            | ...         |
| 30                            | ...         |
| 31                            | ...         |
| 32                            | ...         |
| 33                            | ...         |
| 34                            | ...         |
| 35                            | ...         |
| 36                            | ...         |
| 37                            | ...         |
| 38                            | ...         |
| 39                            | ...         |
| 40                            | ...         |
| 41                            | ...         |
| 42                            | ...         |
| 43                            | ...         |
| 44                            | ...         |
| 45                            | ...         |
| 46                            | ...         |
| 47                            | ...         |
| 48                            | ...         |
| 49                            | ...         |
| 50                            | ...         |

**PARSONS E&C**  
 PROFESSIONAL ENGINEERING FIRM  
 1000 WEST 10TH AVENUE, SUITE 100  
 DENVER, COLORADO 80202  
 PHONE: (303) 733-8800  
 FAX: (303) 733-8801  
 WWW: WWW.PARSONSEANDC.COM



**KENTUCKY POWER COMPANY**  
 200 WEST MAIN STREET, SUITE 1000  
 LOUISVILLE, KY 40202  
 PHONE: (502) 582-2000  
 FAX: (502) 582-2001  
 WWW: WWW.KPCORP.COM

**BIG SANDY PLANT**  
 GENERAL ARRANGEMENT  
 DEWATERING AREA  
 GROUND FLOOR

PROJECT NO. 2-507000A-A  
 DRAWN BY: [Name]  
 CHECKED BY: [Name]  
 DATE: [Date]  
 SCALE: AS SHOWN



PLAN - GROUND FLOOR  
DEWATERING AREA



2-507000A-A

## 5.5 Stack Location

---

The plant coordinates of the new FGD stack are shown on Drawing 2-5070000C, the recommended North Option 2 arrangement. This location is based on preliminary equipment and building sizes and can be optimized, as allowed by the permitting schedule, when FGD OEM general arrangements and equipment sizing becomes available.

## 5.6 Big Sandy Unit1 Layout Considerations

---

Drawings 12-5070000A , 12-5070000B , and 12-5070000D are plot plans showing a wet FGD arrangement that includes retrofit to Unit #1 in conjunction with Unit #2. The three drawings show the same combined Unit#1 and 2 FGD absorber, reagent preparation, and dewatering arrangement. The difference in the three drawings is in the arrangement of the Unit#1 ID fans relative to the Unit #2 ID fans. On drawing 12-5070000D, the Unit #1 ID fans are located under the Unit #2 flue gas duct. The FGD system components have been factored in size for the additional flue gas entering the system from Unit #1 (275 MW gross and 2,602 mm Btu/hr full load firing rate). An additional recycle pump, for a total of six, will be required for the open tray tower design. The quantities of the remaining major mechanical equipment components will not change, but the actual sizing criteria for the equipment will be adjusted to account for the approximate 1/3 increase in flue gas flow to the absorber when Unit 1 flow is combined with the Unit #2 flow.

For a two-unit FGD installation, the FGD substation area would be expected to increase to accommodate a total of four FGD Auxiliary Transformers, and the quantity of station service transformers required would also increase to four. These quantities are consistent with those of the two-unit Mitchell FGD electrical system.







## 6.1 Introduction

---

Phase IIa will involve the integration of planning, conceptual studies and economic assessments, design criteria formulation, site layout design, and primary OEM equipment vendor information for the FGD systems. In Phase IIa, detailed engineering and design efforts will begin in earnest. Because of the schedule necessitating the need for a complete project cost estimate, Phase IIa engineering efforts will be geared toward the formulation of complete project definition to allow proper estimation of the current efforts' equipment sizing, quantities, craft labor, and continued engineering. While the current Phase I work is being completed, efforts involving all of the engineering disciplines for detailed planning of facilities locations and systems design will begin. The initial concentration of engineering will focus primarily on the civil, structural, and mechanical work. The civil work is associated with survey locations, subsurface utility investigations, geotechnical assessments, erosion and sedimentation plans, as well as, storm water system and excavation and fill calculations. The early structural engineering efforts in addition to design criteria development will include preparation of technical specifications, preliminary foundation designs for the absorber and chimney, and lasergrammetry for definition of as-built conditions of tie-in locations and planned duct routing. Foundation design for the chimney and absorber will be finalized after receipt of certified vendor load information. The mechanical work will involve development of ID fan sizing calculations and specification, definition of limestone and gypsum handling systems and specifications, development of balance-of-plant flow diagrams, writing of balance-of-plant equipment specifications, development of piping line specifications, and writing of technical specifications for piping, insulation, and mechanical equipment installation.

The process, electrical, and structural engineering disciplines during this initial period will be finalizing process flow diagrams and one-line diagrams, developing system and equipment sizing calculations, formulating new underground utility systems and grounding grids, beginning preparation of demolition drawings, and interfacing heavily with the FGD OEM vendor in order to obtain the critical system and foundation design information that is essential for the design of their respective foundations. During this initial period, the 3-D PDS model will be developed as the project's basic tool for the integration of the various disciplines' detailed design effort. [The FGD OEM vendor will be required to provide their equipment's 3-D models for use by Parsons E&C in the development of the overall integrated plant 3-D model.]

The conclusion of the Phase IIa efforts will be a complete project estimate that will allow AEPSC to understand the capital commitment necessary to complete this project. It is anticipated that the Design Review Board (DRB) approval of the project will be coincident with the completion of the project cost estimate. The Parsons E&C team is committed to support the AEPSC Big Sandy team during the DRB approval process.

## **6.2 Major Issues To Be Addressed in Phase IIa**

---

AEPSC and Parsons E&C have jointly developed studies and evaluations that define the known major issues and open actions that will require further effort to completely define the overall project. Following is a listing of these elements with a short description for each, as well as the work to be performed.

### **Schedule Acceleration Study**

Big Sandy Unit 2 WFGD commission date is currently scheduled for November 22, 2009. Parsons E&C will identify what strategic activities need to be initiated and what project milestones need to be completed in order to accelerate this WFGD commissioning date.

### **Permitting Support**

By this activity Parsons E&C will provide AEP with services required, time-to-time, to support on-going issues associated with the air, water, or site permitting processes. These issues would include, but are not confined to, material balances for alternative coals, limestones, or ambient conditions, review of documented state or local emissions/effluent regulations, revised emission or effluent calculations, trace element emissions, and/or supporting calculations.

### **Design Review Board Support**

AEP may request support from Parsons E&C in preparing and/or presenting material to AEP Senior Management. This support may take the form of, but is not limited to, review of presentation material, generating presentation documents, and travel to Columbus, Ohio to support the AEP project team.

### **Site Safety Study**

Parsons E&C will walk the site to see what potential construction hazards exist. The overall study will take the following form: 1) Review access and egress for safe construction operations and minimal conflict with plant operations. 2) Highlight areas for confined space entry permitting. 3) Review worker pedestrian areas for safe site access. 4) Establish preliminary safe work zone boundaries. 5) Evaluate road crossings and recommend special traffic controls for safe construction operations. 6) Review site for "Overhead Power Line" restrictions and recommend appropriate postings for construction clearances. 7) Review existing structures affected by construction for "Tie Off" requirements. 8) Issue a report on existing conditions, analysis of hazards or potential hazards, and recommend corrective actions or accident prevention measures.

### **Big Sandy Unit 1 Emissions Control Strategy**

Parsons E&C may, if directed by AEP, evaluate the application of several emissions control technologies to Big Sandy Unit 1 for the purposes of reducing mercury emissions. The emission controls will focus on deNOx and deSOx technologies, such as SCR and WFGD, as well as commercial mercury removal systems. WFGD control technologies evaluated may or may not include the same WFGD technology applied to Big Sandy Unit 2. The emissions alternatives evaluated will weigh overall results with risk, cost, schedule, and commercial reliability. A study report would be issued for this work.

### **Big Sandy Unit 1 Alternatives and Risk Assessment**

Parsons E&C may, if directed by AEP, identify and evaluate the risks associated with the application of emissions control technology(s) to both Big Sandy Units 1 and 2. Issues to be evaluated may include: the impact of additional ammonia requirements for Unit 1 on the existing urea-to-ammonia plant, affect of Unit 1 technology to the general arrangements and plot plans already developed by Parsons E&C for Unit 2 WFGD, and additional utility requirements for Unit 1 conversion. If the same WFGD control technology is applied to both Units 1 and 2, additional studies will be required. These additional studies may include, but are not limited to, routing flue gas from both Unit 1 (300 MW) and Unit 2 (800 MW) to the same absorber vessel, evaluating induced draft damper configurations required to isolate off-line unit, evaluating affect of "off-line" Unit 2 on location of wet/dry line when Unit 1 "on-line" at part load, and total unit response to master fuel trip (MFT), or other such plant disruption, on either Big Sandy Unit 1 or 2.

## Section 6

## Phase IIa Objectives

### Limestone and Gypsum Weather protection

Parsons E&C will make an assessment to determine if raw limestone requires measures for freeze protection and dust control. The same evaluation will be made for the gypsum product. A report will be issued for this study.

### Plant Operating Data

Historical plant data summaries will be evaluated by Parsons E&C to determine normal base line and part load operating levels, as well as to determine required turndown requirements and capabilities. Examination of the historical data will also reveal if the unit is a “peaker” or traditional “base loaded” unit. AEP will be interviewed to determine the future disposition of daily operations to make sure they are consistent with historical data. The summarized data will be incorporated into the plant specific design criteria

### Plant Operating Philosophy

Parsons E&C will interview the appropriate AEP personnel to determine the preferred schedule for batch operations such as: raw limestone grinding, limestone slurry preparation, and gypsum dewatering. These operations may be confined to two shifts rather than three. Plant preferences will determine storage/surge tank volumes. The summarized results will be incorporated into the plant specific design criteria.

### Shared Assets

The potential effects of Unit 2 WFGD conversion to Unit 1 will be evaluated by Parsons E&C. This would include changes in coal feedstock necessitating separate coal deliveries, storage, and handling for Unit 1. Other variables will be identified and investigated such as shared electrical tie-ins, flyash disposal options, and the potential for conversion of Unit 1 for SCR and WFGD.

There are also potential effects of adding WFGD to Unit 2 on existing Unit 2 equipment. These effects need to be identified and quantified. One example of this is if ammonia is chosen for in-duct SO<sub>3</sub> mitigation. The existing urea-to-ammonia facility would have to be examined to ensure that it can provide the required ammonia for both the existing Unit 2 SCR as well as the potentially required ammonia for SO<sub>3</sub> mitigation.

A report will be issued for this study.

### Baseline Plant Test

A third party will be contracted by AEP to perform a rigorous and comprehensive survey of plant state points and other data. This data will be reviewed and reconciled by Parsons E&C against historical plant operating data. Plant personnel will be interviewed to assess the accuracy of the baseline test data and to help reconcile any inconsistent information. The results will be reflected in the plant specific design criteria.

### High Sulfur Coals

AEP will perform any evaluations required to determine the effect of burning higher sulfur coal on unit operations, including the boiler, air heater and ESP.

### Redundancy

Before final plot plans and General Arrangement drawings can be developed, a WFGD equipment redundancy policy must be established. In its simplest form, such a policy requires specifying redundant critical equipment as either: (1) two units sized for full load – one unit operating and one spare, or, (2) three units sized for half load – two units operating and one spare. It is anticipated that redundancy requirements will be mutually resolved by AEP and Parsons E&C during design development.

### SO<sub>3</sub> Mitigation Study

SO<sub>3</sub> mitigation method will be determined by AEP. AEP does not want Parsons E&C to perform a study of viable options. Implementation of the mitigation system selected by AEP is in Parsons E&C scope of detailed design.

### Limestone Specification

It is essential that we finalize limestone “design” composition and identify likely alternatives. This requires a review of limestone available by railcar and a definition of the gypsum product as either disposable or wallboard quality. Once the design limestone is identified, the trace element analysis for purposes of permitting the unit needs to be verified. The final limestone specification, decision on disposable vs. wallboard quality gypsum, and trace element analysis of the limestone is in AEP scope of work. Parsons E&C will perform the trace element analysis of byproducts and wastewater.

**Section 6****Phase IIa Objectives****Gypsum Dewatering**

A decision by AEP is required on the ultimate disposition of the solids produced in the WFGD process. It must be agreed upon as to whether a salable gypsum product is to be produced or if the WFGD solids are to be disposed of in either a landfill or pond. The choice will allow assessment of the dewatering method and disposal options. The final dewatering option may affect the size of the plot plan, type/size of oxidation blower required, bulk dewatering equipment required, as well as the quality of limestone required.

**FGD Supplier**

A WFGD OEM must be selected by AEP with input and guidance from Parsons E&C. Choice of technology will affect all other aspects of the plant design and is an important issue that must be evaluated and weighed with cost, risk, reliability, and schedule in mind.

**Chimney Studies**

Parsons E&C will need to finalize the chimney location. AEP will specify the chimney height and complete turbulence and dispersion tests. Parsons E&C will evaluate potential breeching configurations and determine if the use of FRP ductwork from the absorber hood is feasible or if square/rectangular ductwork is required. The work in Parsons E&C scope is part of design development.

**Power Source Study**

There are two options for providing redundant sources of power to the Unit 2 WFGD electrical distribution system. One option involves the use of the existing Unit 2 138-13.8kV SCR transformers and SCR 13.8kV switchgear. Modifications and/or partial replacement of this equipment would likely be necessary for this option to be feasible. The other option involves the addition of 138kV breakers in the existing Big Sandy 138kV switchyard, and the extension of new 138kV transmission circuits to a new 138-13.8kV FGD substation located adjacent to the FGD development area. Parsons E&C will perform an assessment of these alternatives and provide a recommendation for AEP's approval.

**Rail Delivery or Truck Delivery**

A final determination must be made as to whether rail cars or trucks will be used for the delivery of coal, limestone, and perhaps dewatered gypsum.

This decision must be weighed against the risks, cost, and benefits of each alternative. Parsons E&C will perform this study and issue a report.

### **Make-up Water Supply**

Potential water make-up sources will be identified and quantified. Make-up water sources include river water, ash pond run-off, and well water. Make-up water trace element compositions will be evaluated. Pre-treatment alternatives for biological and solids removal will be evaluated. Modifications to the existing river water intakes will be evaluated as necessary. Parsons E&C will perform this study and issue a report.

### **Coal System Upgrades**

Coal feed to Unit 2 will be a blend of high and low sulfur coals. A coal blending system will have to be developed. An approach to maintaining two separate coal piles for Unit 2 will also need to be developed. Parsons E&C will examine rail traffic schedules to determine what impact will be realized through delivery of two separate coal sources. Parsons E&C will perform this study and issue a report.

### **Blow Down**

The ultimate disposition of the WFGD purge stream effluent must be determined and verified. Once the location is determined, a trace element analysis will be required, along with an evaluation of state regulations, as to whether the purge effluent requires additional clarification and/or treatment. This work will be done by Parsons E&C as part of the design development.

### **Topographic Survey**

Parsons E&C will prepare a drawing and specification to procure topographic survey services. The survey will include identification of surface features and will provide existing topographic information for the existing plant necessary for design. The survey will be performed by a professional land surveyor. A Parsons E&C representative will be on site during the surveyor's fieldwork.

### **Geotechnical Investigations and Report**

A subsurface exploration program will be performed at the site. Parsons E&C will review existing geotechnical information, and then propose additional subsurface investigations as warranted. A drawing and

## Section 6

## Phase IIa Objectives

specification will be provided by Parsons E&C for AEP to procure these services. The program will likely include standard penetration test (SPT) borings, rock cores, field resistivity testing, shear wave velocity testing, and laboratory testing of soils. A Parsons E&C representative will be on site during the fieldwork. The results of the geotechnical investigation will be provided to Parsons E&C as a data report and Parsons E&C will use this data to generate geotechnical design recommendations.

### Underground Utility Investigations and Report

Parsons E&C will review existing utility drawings available for the site and then prepare recommendations for a subsurface utility locating program. Parsons E&C will prepare a drawing and specification for AEP to procure these services. This work will be performed in general accordance with American Society of Civil Engineers (ASCE) 38-02, "Standard Guideline for the Collection and Depiction of Existing Subsurface Utility Data." Most likely the services will consist of Quality Level B geophysical methods for designating utilities in accordance with ASCE 38-02 with some Quality Level A locating on an "as-needed" basis. Quality level C services will be provided as part of the topographic survey. A Parsons E&C representative will be on site during this fieldwork.

### River Intake – Bathymetric Study

If required, Parsons E&C will prepare a drawing and specification for AEP to procure bathymetric survey services to obtain river water depths in the area of the proposed river intake. This will only be required if modification to the existing intake is necessary to add pump(s) to meet makeup water requirements of the WFGD system. These services may or may not be performed by the same surveyor who performs the separately listed topographic survey. A professional land surveyor will perform the survey with equipment specifically manufactured to obtain water depth reading or soundings. A Parsons E&C representative will be on site during this fieldwork.

### Transient Analysis

A dynamic (time dependant) model maintaining the integrity of the existing plant geometry while incorporating the new absorber gas-path geometry will be developed. This model will be used to investigate gas-path transient responses in order to estimate peak pressures in the flue gas system to determine design pressure of the gas side ductwork and equipment. AEP will perform this work and provide design pressures to Parsons E&C for the ductwork in the AE's scope of design.

## Construction Approach

Several approaches to construction for this plant can be used. It is the intent of AEP and Parsons E&C to develop an approach that is consistent with the objectives of a safe working environment, acceptable schedule, and cost-effectiveness. Parsons E&C will evaluate the site specific needs, project schedule, complexity of equipment, and make the most appropriate recommendation while considering the project cost and risk profile for the project.

## Noise Study

Parsons E&C will write a specification for use by AEP to procure the services of a noise consultant to perform a survey of existing background noise at the plant boundary lines, determine the allowable noise levels at the boundary lines when the FGD plant is in operation, make recommendations on limits of equipment noise levels and acoustical treatment of outdoor equipment, ductwork, and buildings (louvers, building construction, etc.) to assure that allowable boundary line noise levels are not exceeded, and to perform a noise survey of actual levels at the boundary lines with the FGD plant in operation. Parsons E&C will review the consultant's report and incorporate their recommendations into equipment specifications.

## 7.1 Incremental Issues with Adding WFGD to Big Sandy Unit 1

The issue to add a WFGD technology to Big Sandy Unit 1 has been raised by AEP. The approach is that the flue gas from Units 1 and 2 would be commonly ducted to a single absorber tower and ultimately to a single wet stack. Reagent preparation and product dewatering would be common. The gas paths from the individual units would remain separate through induced draft fans, dedicated to each unit, and combined, where appropriate, prior to the absorber inlet duct. Three conceptual layouts for the combined FGD system can be found in Section 5 of this report.

Prior to adding WFGD to Big Sandy Unit 1, a life-extension program, that may include furnace conversion from pressurized to balanced-draft, would be required. This is due to the decayed state of the existing furnace and ductwork. This necessary program would extend the life of the power generator by twenty years. For the purposes of this discussion, Parsons E&C is assuming that both a life-extension program and a furnace draft conversion program could be completed without much risk to plant availability and at a known cost.

A design challenge lies in ducting the Unit 1 flue gas to the common absorber inlet duct. The difficulty lies in spatially accommodating the ductwork from the ESPs to the common absorber tower, from both Unit 2 and Unit 1. With the two units positioned back-to-back and exhausting into a common stack (existing hot stack), the ductwork egresses from each individual unit will be tight. The existence and/or level of possible interferences will remain unknown until *both* units are evaluated three dimensionally subject to application to a common WFGD tower.

There are other issues that introduce uncertainty and would require evaluation and definition to mitigate risk. These would include but not be limited to: (1) evaluating ID fan damper configurations required to isolate an off-line unit, (2) evaluate effect of "off-line" Unit 2 on location of the absorber wet/dry line when Unit 1 is "on-line" at part load, (3) effect of Unit 1 WFGD on the general arrangements and plot plans already developed by Parsons E&C for Unit 2 WFGD, (4) electrical and other service requirements for additional capacity required to accommodate Unit 1 flue gas flow, and, (5) total unit response to master fuel trip (MFT), or other such plant disruption, on either Big Sandy Unit 1 or 2.

There is a large amount of risk associated with proceeding on Unit 2 WFGD without making a decision over the final disposition of Unit 1. This

## Section 7

## Big Sandy Unit 1 Incremental Issues

risk could adversely affect both cost and schedule for Unit 2 WFGD. Comments from plant personnel received by Parsons E&C during the project kick-off meeting indicated a high level of concern in proceeding with WFGD for Unit 2 without planning for and incorporating modifications to Unit 1.

## 7.2 Incremental Issues with Adding SCR to Big Sandy Unit 1

---

It has been proposed that if WFGD were applied to Big Sandy Unit 1, a selective catalytic reduction (SCR) system would be concurrently added. This would entail ducting the hot flue gas from the economizer exit to the SCR system and then ducting the flue gas back to the air heater. From the air heater, flue gas would flow through the ESP and ultimately be routed to the common absorber tower.

A typical SCR system consists of an ammonia injection grid (AIG), static mixing of the flue gas and ammonia, and a multiple-bed catalytic reactor. The SCR AIG and reactor must be supported above grade in close proximity to the economizer. Grade-level real estate would have to be located to accommodate the steel. Proper planning would be required to configure the Unit 1 SCR along with the ductwork changes required to route the flue gas to the WFGD absorber tower. Discussion with Big Sandy plant personnel has hinted at the possible relocation of the Unit 1 ESPs. Again, as is the case with the WFGD discussed above, both Units 1 and 2 would have to be evaluated in three dimensions to properly assess and refine this combination. Proceeding without addressing these issues would potentially expose the Unit 2 WFGD design to deficiencies and risk that would undermine the overall project.

Other issues that would have to be evaluated include: general assessment of furnace access for SCR, electrical and other service requirements for SCR addition, impact of additional ammonia requirements for Unit 1 on the existing urea-to-ammonia plant, and the effect of Unit 1 SCR and WFGD on the general arrangements and plot plans already developed by Parsons E&C for Unit 2 WFGD.

## 7.3 Incremental Issues with Adding Unit 1

---

One of the possibilities for dealing with mercury control is the installation of an SCR and WFGD for the Big Sandy Unit 1. We have established incremental cost estimates associated with combining the Unit 1 WFGD with the Unit 2 WFGD, vis a vis, Unit 1 and Unit 2 steam generators into

one FGD absorber tower. The incremental costs were evaluated by having unitized draft systems up to the absorber vessel. Thus each unit has its own dedicated duct from the ESP outlet to the WFGD absorber including two axial ID Fans.

The incremental costs were determined by using the Mitchell Units 1 and 2 project cost estimates to determine a relative estimate for the Big Sandy Unit 2 overall cost. This was then factored based upon judgment for the incremental increase of the equipment size to incorporate the processes of the 300 MW Unit 1. Following is a tabulation of these incremental costs:

| <u>WFGD System Description</u>                   | <u>Cost (x 1000)</u> |
|--|----------------------|
| Absorber Island                                  | \$11,400             |
| Flue Gas Draft System                            | \$16,150             |
| Limestone Handling and Slurry Preparation System | \$5,700              |
| Gypsum Dewatering and Handling System            | \$5,700              |
| Electrical and I&C Systems                       | \$5,950              |
| Chimney  | \$4,200              |
| Balance of Plant Equipment                       | \$3,700              |
| Foundation and Site Preparation                  | \$6,400              |
| <b>TOTAL INCREMENTAL COST</b>                    | <b>\$59,200</b>      |

The above estimated incremental cost breakdown relates to approximately \$197/KW and was established by using the same ratio to the total costs as was established for the Mitchell costs. These values include AEPSC's costs, assumed to be in the same proportion as the Mitchell project, but do not include Water Treatment, Coal Blending and SO<sub>3</sub> Mitigation costs.

Regarding the SCR incremental cost, it is Parsons' experience that a ratio of \$100 per KW is a relatively accurate cost estimate. Applying this ratio, incremental costs for a Unit 1 SCR would be approximately \$30 million. This is based upon it having its own dedicated urea to ammonia conversion system.

**Section 8**

**Summary of Phase I**

**8.1 Schedule Basis**

To support AEPSC’s requirements, this schedule is based on the expected initial operation of Big Sandy Unit 2 WFGD on November 22, 2009. The purpose of this work scope is to advance engineering to a point that will allow the development of a valid overall project cost estimate. See Exhibit 8-1 for the summary schedule for this phase of the work.

During this next phase, a Critical Path Schedule for the entire project, including the development of a target installation schedule that will be adjusted once construction contractors are selected, will be developed.

The concept formulated by Parsons E&C to effectively address this next phase of the project is illustrated in the diagram below:



The cycle for this phase of the project is estimated to take approximately nine (9) months. This time period is required to effectively conclude all aspects of Phase IIa. When conclusions and decision are established for key studies and evaluations, engineering of the project can proceed. A critical point to make here is that it is common to move forward with the engineering of a project too early (i.e., before the foundation for the design has been established). It takes restraint to hold engineering from moving too far forward using assumptions and guesswork instead of firmly established design criteria and fact. Conversely, it is essential to integrate the studies and evaluations phase with engineering to allow overlap and the ability to initiate engineering when appropriate key conclusions have been reached.

A schedule will be developed at the beginning of Phase IIa that logically ties the studies and evaluations to successor activities that will allow the project to flow as shown graphically above.

## 8.2 Project Critical Path

---

The critical path through the project lies with the permitting activities. If the permitting activities' schedule can be improved, the critical path in moving forward will then lie with chimney erection and construction of the WFGD absorber. Erection of the chimney shell will essentially prevent other craft activity in the FGD area due to safety requirements. At a minimum, a fifty (50) foot safety exclusion zone (radius) is required around the stack during construction. Therefore, it is important to establish the stack location and mobilize a chimney contractor early in the project. As soon as the chimney shell is erected, construction on the absorber and process buildings can commence.

Related to this string of construction activities at the front end of the schedule is the necessity to complete relocations and foundations in the chimney/FGD island area. Since the chimney erection will impede other FGD area work, the schedule will need to provide for completing the entire FGD island foundations prior to start of the chimney shell. This will permit absorber island building construction immediately after the completion of the chimney shell, which otherwise would be delayed if foundations were not previously installed.

## 8.3 Engineering Schedule

---

The engineering schedule is dependent upon timely completion of the Phase IIa evaluations and studies that need to be finalized prior to the start of detailed engineering. The major deliverable for this next phase is the project cost estimate. Once the cost estimate is completed, and continued detailed engineering is authorized, the construction and commissioning schedules will be the driving factors to meet the required WFGD startup date. The key to success is the timing of engineering information from the OEMs and vendors to support balance-of-plant engineering and construction. Therefore, it is essential that orders to suppliers be released as required to support the overall schedule, thus preventing undue and unnecessary work schedule conflicts and delays.

## 8.4 Division of Work


---

A complete project Division of Work (DOW) was jointly developed by AEPSC and Parsons E&C. The intent of this DOW is to define what company is responsible to perform all the work elements and supply all the materials for the project. This DOW is expected to be a living document, but provides a current baseline for documentation of intended project development. We have included as Exhibit 8.2 this Division of Work.

# Exhibit 8-1



| Activity ID                      | Activity Description                             | Orig Dur | Early Start | Early Finish | Date |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
|----------------------------------|--|----------|-------------|--------------|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|--|--|--|--|
|                                  |  |          |             |              | D    | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV |  |  |  |  |
| 1036                             | FGD OEM General Arrangement Drawings             | 80       | 01FEB05     | 23MAY05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1038                             | BOP Process Flow Diagrams Special Processes      | 40       | 29MAR05     | 23MAY05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1042                             | FGD OEM P&ID's                                   | 40       | 29MAR05     | 23MAY05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1043                             | BOP General Arrangements                         | 30       | 24MAY05     | 04JUL05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1045                             | BOP P&ID's                                       | 80       | 29MAR05     | 18JUL05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| <b>Instruments &amp; Control</b> |  |          |             |              |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1054                             | Valve Process Conditions                         | 10       | 07JUN05     | 20JUN05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1057                             | Instrument Process Conditions                    | 10       | 07JUN05     | 20JUN05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1060                             | DCS I/O Count                                    | 10       | 07JUN05     | 20JUN05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1063                             | DCS Architecture Drawing & Data Sheets           | 10       | 21JUN05     | 04JUL05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1066                             | Budget Quote-DCS                                 | 10       | 05JUL05     | 18JUL05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1068                             | Review Vendor Drawings                           | 20       | 19JUL05     | 15AUG05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1070                             | Estimate Control Valves                          | 20       | 19JUL05     | 15AUG05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1073                             | Estimate Instrument                              | 20       | 19JUL05     | 15AUG05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1076                             | Estimate Instrument Racks                        | 15       | 19JUL05     | 08AUG05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1079                             | Estimate Instrument Tubing                       | 10       | 19JUL05     | 01AUG05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| <b>Electrical</b>                |  |          |             |              |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1107                             | Typical Schematics                               | 30       | 06JUN05     | 15JUL05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1110                             | Electrical One Lines                             | 195      | 03JAN05     | 30SEP05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1113                             | General Arrangements(Switchyard&Electrical Room) | 100      | 28FEB05     | 15JUL05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1116                             | Electrical Package 1-Engineered Electrical Eqpt  | 45       | 18JUL05     | 16SEP05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |
| 1119                             | Electrical Package 2-HV Switchyard Package       | 45       | 18JUL05     | 16SEP05      |      |     |     |     |     |     |     |     |     |     |     |     |  |  |  |  |







**Section 8**

**Summary of Phase I**

**Exhibit 8-2**

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |  | Division of Work (DOW) Legend |   |    |     | Comments |
|---|--|-------------------------------|---|----|-----|----------|
|   |  | FGD                           | AE                                      | EC | O   |          |
| Revision Date: <b>November 17, 2004</b>   |  | FGD                           | AE                                      | EC | O   |          |
| Current Rev #: <b>Rev 0</b>   |  | ESC                           | SGS                                     | C  | TBD |          |
|   |  | N/A                           | Not Applicable for this Project or Task |    |     |          |

| Item | Description   | Functional Design | Detail Design | Supply | Site Erection | Comments   |
|------|---|-------------------|---------------|--------|---------------|--|
| 1    | <b>Special Studies and Investigations</b>                       |                   |               |        |               |  |
| 2    | Fan Study   | N/A               | N/A           | N/A    | N/A           |  |
| 3    | Boiler & Draft System Implosion Study & Transient Analysis      | AE                | AE            | AE     | N/A           |  |
| 4    | Physical or Computer Flue Gas Model Study (FGD Scope of Supply) | FGD               | FGD           | FGD    | N/A           | Flow from Absorber                                       |
| 5    | Physical or Computer Flue Gas Model Study (BOP Scope of Supply) | AE                | AE            | AE     | N/A           | Flow from ESP outlet to new chimney, excluding Absorber. |
| 6    | Geotechnical Study  | AE                | AE            | O      | O             |  |
| 7    | Topographical Surveys   | AE                | AE            | O      | O             |  |
| 8    | Baseline Testing  | N/A               | N/A           | O      | N/A           |  |
| 9    | Traffic Study   | AE                | AE            | AE     | N/A           |  |
| 10   | Underground Utility Survey                                      | AE                | AE            | O      | O             |  |
| 11   | Lasergrammetry of Tie-In Points                                 | AE                | AE            | AE     | AE            |  |
| 12   | Chimney Proximity Effect  | O                 | O             | O      | O             |  |
| 13   | Coal Blending Study   | AE                | AE            | N/A    | N/A           |  |
| 14   | Ammonia Bi-Sulphate condensation study and effects              | O                 | O             | O      | N/A           |  |
| 15   | Sulphuric Acid condensation study and effects                   | O                 | O             | O      | N/A           |  |
| 16   | Preliminary Phase I Studies                                     | N/A               | N/A           | N/A    | N/A           |  |
| 17   | Limestone & Gypsum Supply/ Sales                                | O                 | O             | O      | O             |  |
| 18   | <b>FGD Process</b>  |                   |               |        |               |  |
| 19   | Process Design Basis  | FGD               | FGD           | N/A    | N/A           |  |
| 20   | Process Flow Diagrams   | FGD               | FGD           | N/A    | N/A           |  |
| 21   | Mass Balances   | FGD               | FGD           | N/A    | N/A           |  |
| 22   | Process Control Description                                     | FGD               | FGD           | N/A    | N/A           |  |
| 23   | Performance Guarantees/Curves                                   | FGD               | FGD           | N/A    | N/A           |  |
| 24   | Process Data Sheets   | FGD               | FGD           | N/A    | N/A           |  |
| 25   | FGD Pressure Drop Calculations                                  | FGD               | FGD           | N/A    | N/A           | From absorber inlet to absorber outlet.                  |
| 26   | <b>BOP Process</b>  |                   |               |        |               |  |
| 27   | Process Design Basis  | AE                | AE            | N/A    | N/A           |  |
| 28   | Process Flow Diagrams   | AE                | AE            | N/A    | N/A           |  |
| 29   | Mass Balances   | AE                | AE            | N/A    | N/A           |  |
| 30   | Process Control Description                                     | AE                | AE            | N/A    | N/A           |  |
| 31   | Performance Guarantees/Curves                                   | AE                | AE            | N/A    | N/A           |  |
| 32   | Process Data Sheets   | AE                | AE            | N/A    | N/A           |  |
| 33   | BOP Design Criteria   | AE                | AE            | N/A    | N/A           |  |
| 34   | Pressure Drop Calculations                                      | AE                | AE            | N/A    | N/A           | From ESP outlet to stack, excluding Item 19              |
| 35   | <b>Struct. Engineering &amp; Plant Layout</b>                   |                   |               |        |               |  |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |  | Division of Work (DOW) Legend |                         |                     |   |  |
|---|--|-------------------------------|-------------------------|---------------------|---|--|
|   |  | FGD                           | AE                      | EC                  | O                                       | ESC  |
| Revision Date: <b>November 17, 2004</b>   |  | FGD Supplier                  | Architect Engineer-PE&C | Erection Contractor | Owner-AEP                               | Material & Installation by subcontractor managed by AE or EC   |
| Current Rev #: <b>Rev 0</b>   |  | SGS                           | Chimney Supplier        | To Be Determined    | Not Applicable for this Project or Task |  |
| Item  | Description  | Functional Design             | Detail Design           | Supply              | Site Erection                           | Comments   |
| 36  | Plant General Arrangement Dwgs                                       | AE                            | AE                      | N/A                 | N/A                                     | Input from FGD & BOP Process Suppliers   |
| 37  | General Arrangements for FGD Process Islands                         | FGD                           | FGD                     | N/A                 | N/A                                     |  |
| 38  | Foundations  | AE                            | AE                      | N/A                 | N/A                                     |  |
| 39  | FGD Equipment Loads  | FGD                           | FGD                     | N/A                 | N/A                                     |  |
| 40  | BOP Equipment Loads  | AE                            | AE                      | N/A                 | N/A                                     |  |
| 41  | Site Plan  | AE                            | AE                      | N/A                 | N/A                                     |  |
| 42  | <b>Support Steel</b>   |                               |                         |                     |   |  |
| 43  | FGD Process Building Support Steel                                   | AE                            | AE                      | AE                  | EC                                      | Input from FGD. AE to supply DEA drawings and material takeoffs.   |
| 44  | FGD Process Equipment Support Steel                                  | FGD                           | FGD                     | FGD                 | EC                                      |  |
| 45  | Pipe Hangers (Inside FGD Islands)                                    | FGD                           | FGD                     | FGD                 | EC                                      |  |
| 46  | Pipe Hangers (Outside FGD Islands)                                   | AE                            | AE                      | AE                  | EC                                      | Hangers for FGD-supplied piping to be supplied by FGD. AE to supply DEA drawings and material takeoffs.                        |
| 47  | Pipe Racks / Supports (Inside FGD Islands)                           | AE                            | AE                      | AE                  | EC                                      |  |
| 48  | Pipe Racks / Supports (Outside FGD Islands)                          | AE                            | AE                      | AE                  | EC                                      | AE to supply DEA drawings and material takeoffs.   |
| 49  | Cable Tray Racks / Supports (Inside FGD Islands)                     | AE                            | AE                      | AE                  | EC                                      |  |
| 50  | Cable Tray Racks / Supports (Outside FGD Islands)                    | AE                            | AE                      | AE                  | EC                                      | AE to supply DEA drawings and material takeoffs.   |
| 51  | Fluework Support Steel   | AE                            | AE                      | AE                  | EC                                      |  |
| 52  | Conveyor Support Steel   | AE                            | AE                      | AE                  | EC                                      | AE to supply DEA drawings and material takeoffs.   |
| 53  | <b>Fluework including expansion joints</b>                           |                               |                         |                     |   |  |
| 54  | Absorber Wet/Dry Interface Flue                                      | FGD                           | FGD                     | FGD                 | EC                                      | Begin scope at Alloy Inlet Duct Gooseneck Support Steel, if required, by FGD. AE to supply DEA drawings and material takeoffs. |
| 55  | Absorber Outlet Flue to Chimney                                      | AE                            | AE                      | FGD                 | EC                                      |  |
| 56  | Absorber Inlet Sample Test Ports                                     | FGD                           | FGD                     | FGD                 | EC                                      | AE to supply DEA drawings and material takeoffs.   |
| 57  | Absorber Outlet Moisture Carryover Test Ports                        | FGD                           | FGD                     | FGD                 | EC                                      |  |
| 58  | Stack Test Sample Ports  | O                             | O                       | O                   | O                                       | Chimney Contractor   |
| 59  | Chimney Breaching  | O                             | O                       | O                   | O                                       |  |
| 60  | Modifications to Existing Flue                                       | AE                            | AE                      | AE                  | EC                                      | Chimney Contractor   |
| 61  | FGD Supply Flue (from tie to existing flue downstream of ESP Outlet) | AE                            | AE                      | AE                  | EC                                      |  |
| 62  | FGD Supply Flue (from ESP outlet)                                    | AE                            | AE                      | AE                  | EC                                      | AE to supply DEA drawings and material takeoffs.   |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |  | Division of Work (DOW) Legend |   |        |               | Comments  |
|---|--|-------------------------------|---|--------|---------------|---|
|   |  | FGD                           | AE                                      | EC     | O             |   |
| Revision Date: <b>November 17, 2004</b>   |  | FGD                           | AE                                      | EC     | O             |   |
| Current Rev #: <b>Rev 0</b>   |  | ESC                           | SGS                                     | C      | TBD           |   |
|   |  | N/A                           | Not Applicable for this Project or Task |        |               |   |
| Item  | Description  | Functional Design             | Detail Design                           | Supply | Site Erection | Comments  |
| 63  | Flue located in existing stack                                 | AE                            | AE                                      | AE     | EC            |   |
| 64  | <b>Platforms/Stairs</b>  |                               |   |        |               |   |
| 65  | FGD Process Equipment & Components Platforms and Stairs        | FGD                           | AE                                      | AE     | EC            |   |
| 66  | BOP Process Equipment & Components Platforms and Stairs        | AE                            | AE                                      | AE     | EC            | AE to supply DEA drawings and material takeoffs.  |
| 67  | Chimney Test Platform  | O                             | O                                       | O      | O             | Chimney Contractor  |
| 68  | <b>Limestone Handling System</b>                               |                               |   |        |               |   |
| 69  | Limestone Storage Structure                                    | AE                            | AE                                      | AE     | EC            | Limestone Supply by Owner   |
| 70  | Limestone Reclaim Hopper                                       | AE                            | AE                                      | AE     | EC            |   |
| 71  | Limestone Conveyor System                                      | AE                            | AE                                      | AE     | EC            |   |
| 72  | Limestone Instrumentation & Controls                           | AE                            | AE                                      | AE     | EC            | Conveyor Vendor   |
| 73  | Trucks Unloading Facility                                      | AE                            | AE                                      | AE     | EC            |   |
| 74  | Trucks Unloading Facility                                      | O                             | O                                       | O      | O             |   |
| 75  | Bulldozers   | O                             | O                                       | O      | O             |   |
| 76  | <b>Limestone Preparation Island &amp; associated equipment</b> |                               |   |        |               |   |
|   |  |                               |   |        |               | Minimum of 2 silos. Total useful storage capacity of all silos combined shall be a minimum of 24 hours based on entire site limestone consumption. AE to supply DEA drawings and material takeoffs. |
| 77  | Limestone Day Silo(s)  | FGD                           | FGD                                     | FGD    | EC            |   |
| 78  | Limestone Day Silo Bin Vibrators                               | FGD                           | FGD                                     | FGD    | EC            |   |
| 79  | Limestone Silo Isolation Valves                                | FGD                           | FGD                                     | FGD    | EC            |   |
| 80  | Limestone Silo Dust Collector                                  | FGD                           | FGD                                     | FGD    | EC            |   |
| 81  | Limestone Chutes   | FGD                           | FGD                                     | FGD    | EC            |   |
| 82  | Limestone Silo Instrumentation                                 | FGD                           | FGD                                     | FGD    | EC            |   |
| 83  | Limestone Weighing Feeder                                      | FGD                           | FGD                                     | FGD    | EC            |   |
| 84  | Limestone Ball Mill  | FGD                           | FGD                                     | FGD    | EC            | Minimum of 1 spare ball mill.   |
| 85  | Ball Mill Motor  | FGD                           | FGD                                     | FGD    | EC            |   |
| 86  | Ball Mill Rubber Liners  | FGD                           | FGD                                     | FGD    | EC            |   |
| 87  | Ball Charge  | FGD                           | FGD                                     | FGD    | EC            |   |
|   |  |                               |   |        |               | Minimum of 1 per mill. B&W to supply design on agitator, lining, nozzles, and loads.  |
| 88  | Mill Product Tank  | FGD                           | FGD                                     | FGD    | EC            |   |
| 89  | Mill Product Tank Agitator                                     | FGD                           | FGD                                     | FGD    | EC            |   |
| 90  | Mill Product Recycle Pumps                                     | FGD                           | FGD                                     | FGD    | EC            | Minimum of 1 spare pump per ball mill.  |
| 91  | Mill Jacking System  | FGD                           | FGD                                     | FGD    | EC            |   |
| 92  | Limestone Hydrocyclone Classifiers                             | FGD                           | FGD                                     | FGD    | EC            | Minimum of 1 per mill   |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |  | Division of Work (DOW) Legend                       |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
|---|--|---|--------------|-------------------|-------------------------|--------|---------------------|---|-----------|-----|--|-----|------------------------------|---|------------------|-----|------------------|
|   |  | FGD   | FGD Supplier | AE                | Architect Engineer-PE&C | EC     | Erection Contractor | O   | Owner-AEP | ESC | Material & Installation by subcontractor managed by AE or EC | SGS | Steam Generator Supplier/OEM | C | Chimney Supplier | TBD | To Be Determined |
| Revision Date: <b>November 17, 2004</b><br>Current Rev #: <b>Rev 0</b>                                  |  | Item  | Description  | Functional Design | Detail Design           | Supply | Site Erection       | Comments  |           |     |  |     |                              |   |                  |     |                  |
| 93  |  | Limestone Preparation Instrumentation               |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 94  |  | <b>Reagent Slurry Feed</b>                          |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 95  |  | Reagent Slurry Feed Tanks                           |              | FGD               | FGD                     | FGD    | EC                  | Minimum of 2 tanks. Total usable storage capacity of all tanks combined is 12 hours based on entire site slurry consumption. B&W to supply design on agitator, lining, nozzles, and loads |           |     |  |     |                              |   |                  |     |                  |
| 96  |  | Reagent Slurry Feed Tank Agitators                  |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 97  |  | Reagent Slurry Feed Pumps                           |              | FGD               | FGD                     | FGD    | EC                  | Minimum of one spare pump.  |           |     |  |     |                              |   |                  |     |                  |
| 98  |  | Reagent Slurry Feed Instrumentation                 |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 99  |  | <b>Absorbers Island &amp; associated equipment</b>  |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 100   |  | <b>Absorber Vessel (1 x 100% capacity per unit)</b> |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 101   |  | Inlet Flue, Absorber wet/dry interface              |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 102   |  | Absorber Zone                                       |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 103   |  | Outlet Cone & Hood                                  |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 104   |  | Absorber Internal Supports                          |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 105   |  | ME Vane Support                                     |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 106   |  | Vessel Penetrations, Nozzles, Headers.              |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 107   |  | Integral recycle tank with agitators                |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 108   |  | Mist Eliminators & Wash Nozzles                     |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 109   |  | Quench System                                       |              | FGD/AE            | AE                      | ESC    | ESC                 | FGD to provide quench flow requirements.  |           |     |  |     |                              |   |                  |     |                  |
| 110   |  | Quench Logic  |              | AE                | AE                      | N/A    | N/A                 |   |           |     |  |     |                              |   |                  |     |                  |
| 111   |  | Quench System Pump                                  |              | AE                | AE                      | ESC    | ESC                 |   |           |     |  |     |                              |   |                  |     |                  |
| 112   |  | Mist Eliminator Wash (Absorber Internal)            |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 113   |  | <b>Reaction Tank</b>                                |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 114   |  | Absorber Reaction Tank Shell                        |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 115   |  | Oxidation Air Distribution System                   |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 116   |  | Reaction Tank Agitators                             |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 117   |  | <b>Recycle System</b>                               |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 118   |  | Absorber Recycle Internal Spray Pipe                |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 119   |  | Absorber Recycle External Spray Pipe                |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 120   |  | Recycle Piping Supports (internal)                  |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 121   |  | Recycle Piping Supports (external)                  |              | AE                | AE                      | AE     | EC                  | AE to supply DEA drawings and material takeoffs.  |           |     |  |     |                              |   |                  |     |                  |
| 122   |  | Recycle Pipe Hangers                                |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |
| 123   |  | Recycle Spray Nozzles                               |              | FGD               | FGD                     | FGD    | EC                  |   |           |     |  |     |                              |   |                  |     |                  |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |  | Division of Work (DOW) Legend |                              |                     |   |  |
|---|--|-------------------------------|------------------------------|---------------------|---|--|
|   |  | FGD                           | AE                           | EC                  | O                                       | ESC  |
| Revision Date: <b>November 17, 2004</b>   |  | FGD Supplier                  | Architect Engineer-PE&C      | Erection Contractor | Owner-AEP                               | Material & Installation by subcontractor managed by AE or EC |
| Current Rev #: <b>Rev 0</b>   |  | SGS                           | Steam Generator Supplier/OEM | C                   | Chimney Supplier                        | TBD  |
|   |  | TBD                           | To Be Determined             | N/A                 | Not Applicable for this Project or Task |  |

| Item | Description   | Functional Design | Detail Design | Supply | Site Erection | Comments  |
|------|---|-------------------|---------------|--------|---------------|---|
| 124  | Recycle Pump  | FGD               | FGD           | FGD    | EC            | Minimum of one spare pump per absorber.   |
| 125  | Recycle Pump Gearbox / Accessories                  | FGD               | FGD           | FGD    | EC            |   |
| 126  | Recycle Pump Motor                                  | FGD               | FGD           | FGD    | EC            |   |
| 127  | <b>Oxidation Air Supply</b>                         |                   |               |        |               |   |
| 128  | Oxidation Air Blowers                               | FGD               | FGD           | FGD    | EC            | Minimum of one spare blower.  |
| 129  | Oxidation Air Blower Motors                         | FGD               | FGD           | FGD    | EC            |   |
| 130  | Oxidation Air Blower Noise Enclosure                | FGD               | FGD           | FGD    | EC            |   |
| 131  | Oxidation Air Inlet Filter                          | FGD               | FGD           | FGD    | EC            |   |
| 132  | Oxidation Air Inlet Filter Silencer                 | FGD               | FGD           | FGD    | EC            |   |
| 133  | Oxidation Air Control Panel                         | FGD               | FGD           | FGD    | EC            |   |
| 134  | Oxidation Air Saturation Nozzle                     | FGD               | FGD           | FGD    | EC            |   |
| 135  | Emergency Storage Tank                              | FGD               | AE            | AE     | EC            | Tank storage capacity to hold contents of one absorber reaction tank. FGD vendor to supply design on agitator, lining, nozzles, and loads.  |
| 136  | Emergency Storage Tank Agitator(s)                  | FGD               | FGD           | FGD    | EC            |   |
| 137  | Emergency Storage Tank Return Pumps                 | FGD               | FGD           | FGD    | EC            |   |
| 138  | WFGD/Absorber Instrumentation                       | FGD               | FGD           | FGD    | EC            | One spare per tank.   |
| 139  | <b>Dewatering Island &amp; associated equipment</b> |                   |               |        |               |   |
| 140  | <b>Primary Dewatering</b>                           |                   |               |        |               |   |
| 141  | Absorber Bleed Pump                                 | FGD               | FGD           | FGD    | EC            | Minimum of 1 spare pump per absorber. Bleed rate for each pump will be designed to empty Absorber Reaction Tank in 6 hours.   |
| 142  | Hydrocyclone Classifier Cluster                     | FGD               | FGD           | FGD    | EC            | Located in Dewatering Island. Minimum of 1 cluster per vacuum belt filter.  |
| 143  | <b>Secondary Dewatering</b>                         |                   |               |        |               |   |
| 144  | Hydroclone Feed Tank                                | FGD               | FGD           | FGD    | EC            | Minimum of 2 tanks. Total useful storage capacity of all tanks combined is 8 hours based on entire site absorber bleed rate. FGD vendor to supply design on agitator, lining, nozzles, and loads. |
| 145  | Hydroclone Feed Tank Agitator                       | FGD               | FGD           | FGD    | EC            |   |
| 146  | Hydroclone Feed Pump                                | FGD               | FGD           | FGD    | EC            | Minimum of 1 pump per vacuum belt filter.   |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |   | Division of Work (DOW) Legend |                         |                     |               |  |
|---|---|-------------------------------|-------------------------|---------------------|---------------|--|
|   |   | FGD                           | AE                      | EC                  | O             | ESC  |
| Revision Date: <b>November 17, 2004</b>   |   | FGD Supplier                  | Architect Engineer-PE&C | Erection Contractor | Owner-AEP     | Material & Installation by subcontractor managed by AE or EC   |
| Current Rev #: <b>Rev 0</b>   |   | SGS                           | Chimney Supplier        | To Be Determined    | N/A           | Not Applicable for this Project or Task  |
| Item  | Description                                 | Functional Design             | Detail Design           | Supply              | Site Erection | Comments   |
| 147   | Horizontal Vacuum Belt Filter               | FGD                           | FGD                     | FGD                 | EC            | Minimum of 1 spare vacuum belt filter.   |
| 148   | <b>Vacuum Filter Auxiliaries</b>            |                               |                         |                     |               |  |
| 149   | Liquid Ring Vacuum Pump                     | FGD                           | FGD                     | FGD                 | EC            | Minimum of 1 per vacuum belt filter.   |
| 150   | Filtrate Pump                               | FGD                           | FGD                     | FGD                 | EC            | Minimum of 1 per vacuum belt filter.   |
| 151   | Seal Water Separator                        | FGD                           | FGD                     | FGD                 | EC            | Minimum of 1 per vacuum belt filter.   |
| 152   | Seal Water Tank                             | FGD                           | FGD                     | FGD                 | EC            | Minimum of 1 per vacuum belt filter.   |
| 153   | Cake Wash Pump                              | FGD                           | FGD                     | FGD                 | EC            | Minimum of 1 per vacuum belt filter.   |
| 154   | Cloth Wash Tank                             | FGD                           | FGD                     | FGD                 | EC            | Minimum of 1 per vacuum belt filter.   |
| 155   | Cloth Wash Pump                             | FGD                           | FGD                     | FGD                 | EC            | Minimum of 1 per vacuum belt filter.   |
| 156   | <b>Reclaim Water Storage &amp; Return</b>   |                               |                         |                     |               | Minimum of 2 tanks. Total useful storage capacity of all tanks combined is 8 hours based on entire site reclaim water rate. FGD vendor to supply design of agitator, lining, nozzles, and loads. |
| 157   | Reclaim Water Tank                          | FGD                           | AE                      | AE                  | EC            |  |
| 158   | Reclaim Water Tank Agitator                 | FGD                           | AE                      | AE                  | EC            |  |
| 159   | Reclaim Water Pump                          | FGD                           | FGD                     | FGD                 | EC            | Minimum of 1 spare pump.   |
| 160   | Dewatering System Instrumentation           | FGD                           | FGD                     | FGD                 | EC            |  |
| 161   | <b>Gypsum Handling</b>                      |                               |                         |                     |               |  |
| 162   | Belt Filter Discharge Conveyor              | AE                            | AE                      | AE                  | EC            |  |
| 163   | Cake Transfer Conveyor                      | AE                            | AE                      | AE                  | EC            |  |
| 164   | <b>Product Cake Stackout &amp; Storage</b>  |                               |                         |                     |               |  |
| 165   | Gypsum Storage Structure                    | AE                            | AE                      | AE                  | EC            |  |
| 166   | Gypsum Stacker                              | AE                            | AE                      | AE                  | EC            |  |
| 167   | Gypsum Reclaimer                            | AE                            | AE                      | AE                  | EC            |  |
| 168   | Gypsum Emergency stackout conveyor          | AE                            | AE                      | AE                  | EC            |  |
| 169   | Gypsum Reclaim Conveyor                     | AE                            | AE                      | AE                  | EC            |  |
| 170   | Truck Loading Facility                      | AE                            | AE                      | AE                  | EC            |  |
| 171   | Trucks                                      | O                             | O                       | O                   | O             |  |
| 172   | Gypsum Handling Instrumentation             | AE                            | AE                      | AE                  | EC            |  |
| 173   | Bulldozers                                  | O                             | O                       | O                   | O             |  |
| 174   | <b>Water Distribution</b>                   |                               |                         |                     |               |  |
| 175   | <b>Make Up Water Storage &amp; Transfer</b> |                               |                         |                     |               |  |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |  | Division of Work (DOW) Legend |                         |                     |           |  |
|---|--|-------------------------------|-------------------------|---------------------|-----------|--|
|   |  | FGD                           | AE                      | EC                  | O         | ESC  |
| Revision Date: <b>November 17, 2004</b>   |  | FGD Supplier                  | Architect Engineer-PE&C | Erection Contractor | Owner-AEP | Material & Installation by subcontractor managed by AE or EC |
| Current Rev #: <b>Rev 0</b>   |  | SGS                           | Chimney Supplier        | To Be Determined    |           | Not Applicable for this Project or Task                      |
|   |  | TBD                           |                         |                     |           |  |
|   |  | N/A                           |                         |                     |           |  |

| Item | Description   | Functional Design | Detail Design | Supply | Site Erection | Comments  |
|------|---|-------------------|---------------|--------|---------------|---|
| 176  | Service Water Tank  | FGD               | AE            | EC     | EC            | Minimum of one tank per unit. Useful storage capacity for tank shall be a minimum of 1 hour for associated unit + 30 minute emergency quench capacity required for unit. FGD vendor to supply design of agitator, lining, nozzles, and loads. |
| 177  | Make Up Water Pump  | FGD               | FGD           | FGD    | EC            | Single tie point. Minimum of 1 spare pump per Make Up Water Tank.   |
| 178  | Make Up Water Instrumentation                                   | FGD               | FGD           | FGD    | EC            |   |
| 179  | <b>Mist Eliminator Wash</b>                                     |                   |               |        |               |   |
| 180  | Mist Eliminator Wash Pumps                                      | FGD               | FGD           | FGD    | EC            | Single tie point. Minimum of 1 spare pump per Absorber.   |
| 181  | Mist Eliminator Wash Pump Instrumentation                       | FGD               | FGD           | FGD    | EC            |   |
| 182  | <b>Sumps</b>  |                   |               |        |               |   |
| 183  | <b>Reagent Preparation Area Sump System</b>                     |                   |               |        |               |   |
| 184  | Reagent Preparation Area Sump                                   | FGD               | AE            | ESC    | ESC           |   |
| 185  | Reagent Preparation Area Trench                                 | FGD               | AE            | ESC    | ESC           |   |
| 186  | Reagent Preparation Area Grating                                | FGD               | AE            | ESC    | EC            |   |
| 187  | Reagent Preparation Area Sump Agitator                          | FGD               | AE            | ESC    | EC            |   |
| 188  | Reagent Preparation Area Sump Pump                              | FGD               | AE            | ESC    | EC            | Minimum of 1 spare pump.  |
| 189  | Reagent Preparation Area Sump Agitator & Pump Supports          | FGD               | AE            | ESC    | EC            | AE to supply DEA drawings and material takeoffs.  |
| 190  | Reagent Preparation Area Sump System Instrumentation            | FGD               | AE            | ESC    | EC            |   |
| 191  | <b>Absorber Area Sump System (Absorbers share common sump.)</b> |                   |               |        |               |   |
| 192  | Absorber Area Sump  | FGD               | AE            | ESC    | ESC           |   |
| 193  | Absorber Area Trench  | FGD               | AE            | ESC    | ESC           |   |
| 194  | Absorber Area Grating   | FGD               | AE            | ESC    | EC            |   |
| 195  | Absorber Area Sump Agitator                                     | FGD               | AE            | ESC    | EC            |   |
| 196  | Absorber Area Sump Pump   | FGD               | AE            | ESC    | EC            | Minimum of 1 spare pump.  |
| 197  | Absorber Area Sump Agitator & Pumps Supports                    | FGD               | AE            | ESC    | EC            | AE to supply DEA drawings and material takeoffs.  |
| 198  | Absorber Area Sump System Instrumentation                       | FGD               | AE            | ESC    | EC            |   |
| 199  | <b>Dewatering Area Sump System</b>                              |                   |               |        |               |   |
| 200  | Dewatering Area Sump  | FGD               | AE            | ESC    | ESC           |   |
| 201  | Dewatering Area Trench  | FGD               | AE            | ESC    | ESC           |   |
| 202  | Dewatering Area Grating   | FGD               | AE            | ESC    | EC            |   |
| 203  | Dewatering Area Sump Agitator                                   | FGD               | AE            | ESC    | EC            |   |
| 204  | Dewatering Area Sump Pump                                       | FGD               | AE            | ESC    | EC            | Minimum of 1 spare pump.  |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |  | Division of Work (DOW) Legend |                              |                     |   |  |
|---|--|-------------------------------|------------------------------|---------------------|---|--|
|   |  | FGD                           | AE                           | EC                  | O                                       | ESC  |
| Revision Date: <b>November 17, 2004</b>   |  | FGD Supplier                  | Architect Engineer-PE&C      | Erection Contractor | Owner-AEP                               | Material & Installation by subcontractor managed by AE or EC |
| Current Rev #: <b>Rev 0</b>   |  | SGS                           | Steam Generator Supplier/OEM | C                   | Chimney Supplier                        | TBD  |
|   |  | TBD                           | To Be Determined             | N/A                 | Not Applicable for this Project or Task |  |

| Item | Description   | Functional Design | Detail Design | Supply | Site Erection | Comments   |
|------|---|-------------------|---------------|--------|---------------|--|
| 205  | Dewatering Area Sump Agitator & Pumps Supports  | FGD               | AE            | ESC    | EC            | AE to supply DEA drawings and material takeoffs.                             |
| 206  | Dewatering Area Sump System Instrumentation   | FGD               | FGD           | FGD    | EC            |  |
| 207  | <b>Maintenance Tank Area Sump System</b>  |                   |               |        |               |  |
| 208  | Maintenance Tank Area Sump  | FGD               | AE            | ESC    | ESC           |  |
| 209  | Maintenance Tank Area Trench  | FGD               | AE            | ESC    | ESC           |  |
| 210  | Maintenance Tank Area Grating   | FGD               | AE            | ESC    | EC            |  |
| 211  | Maintenance Tank Area Sump Agitator   | FGD               | AE            | ESC    | EC            |  |
| 212  | Maintenance Tank Area Sump Pump   | FGD               | AE            | ESC    | EC            | Minimum of 1 spare pump.<br>AE to supply DEA drawings and material takeoffs. |
| 213  | Maintenance Tank Area Sump Agitator & Pumps Supports  | FGD               | AE            | ESC    | EC            |  |
| 214  | Maintenance Tank Area Sump System Instrumentation   | FGD               | FGD           | FGD    | EC            |  |
| 215  | <b>Air &amp; Flue Gas Equipment</b>   |                   |               |        |               |  |
| 216  | ID Fans   | AE                | AE            | AE     | EC            |  |
| 217  | ID Fans Motors  | AE                | AE            | AE     | EC            |  |
| 218  | Fan Isolation Dampers   | AE                | AE            | AE     | EC            |  |
| 219  | Instrumentation   | AE                | AE            | AE     | EC            |  |
| 220  | <b>WFGD Waste Water</b>   |                   |               |        |               |  |
| 221  | WFGD Waste Water Treatment System   | AE                | AE            | AE     | EC            |  |
| 222  | <b>Heating, Ventilation and Air Conditioning (HVAC)</b>                                       |                   |               |        |               |  |
| 223  | FGD Process Equipment   | FGD               | FGD           | FGD    | EC            | For FGD-Supplied Enclosures  |
| 224  | FGD Process Island Buildings  | AE                | AE            | ESC    | ESC           |  |
| 225  | BOP Process Equipment   | AE                | AE            | AE     | EC            |  |
| 226  | <b>Dust Collection</b>  |                   |               |        |               |  |
| 227  | FGD Process Equipment   | FGD               | FGD           | FGD    | EC            |  |
| 228  | BOP Process Equipment   | AE                | AE            | AE     | EC            |  |
| 229  | <b>Lifting &amp; Handling Equipment</b>   |                   |               |        |               |  |
| 230  | Monorail (for FGD Process Equipment)  | FGD               | AE            | AE     | EC            | AE to supply DEA drawings and material takeoffs.                             |
| 231  | Hoists / Trolleys (for FGD Process Equipment)   | FGD               | AE            | AE     | EC            | AE to supply DEA drawings and material takeoffs.                             |
| 232  | Monorail (for ID fans)  | AE                | AE            | AE     | EC            |  |
| 233  | Hoists / Trolleys (for ID fans)   | AE                | AE            | AE     | EC            |  |
| 234  | Monorail (for BOP Process Equipment)  | AE                | AE            | AE     | EC            |  |
| 235  | Hoists / Trolleys (for BOP Process Equipment)   | AE                | AE            | AE     | EC            |  |
| 236  | <b>Stacks</b>   |                   |               |        |               |  |
| 237  | Stacks  | O                 | O             | O      | O             |  |
| 238  | Continuous Emissions Monitoring System (CEMS)   | O                 | O             | O      | EC            |  |
| 239  | <b>Piping, Valves &amp; Operators, Paint &amp; Insul, Lagging, Supports, Expansion Joints</b> |                   |               |        |               |  |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |  | Division of Work (DOW) Legend                                |               |        |               |   |
|---|--|--|---------------|--------|---------------|---|
|   |  | FGD  | AE            | EC     | O             | ESC   |
| Revision Date: <b>November 17, 2004</b>   |  | FGD Supplier   |               |        |               |   |
| Current Rev #: <b>Rev 0</b>   |  | Architect Engineer-PE&C                                      |               |        |               |   |
|   |  | Erection Contractor  |               |        |               |   |
|   |  | Owner-AEP  |               |        |               |   |
|   |  | Material & Installation by subcontractor managed by AE or EC |               |        |               |   |
|   |  | Steam Generator Supplier/OEM                                 |               |        |               |   |
|   |  | Chimney Supplier   |               |        |               |   |
|   |  | To Be Determined   |               |        |               |   |
|   |  | Not Applicable for this Project or Task                      |               |        |               |   |
|   |  | TBD  |               |        |               |   |
|   |  | N/A  |               |        |               |   |
| Item  | Description  | Functional Design  | Detail Design | Supply | Site Erection | Comments  |
| 240   | <b>Interconnecting piping &amp; accessories (Within FGD Islands)</b> |  |               |        |               |   |
| 241   | FGD Process Piping   | FGD  | FGD           | FGD    | EC            | Small bore (2" & under) field run piping supplied by FGD. Site erection by EC.                            |
| 242   | Seal Water   | FGD  | FGD           | FGD    | EC            | Single Supply Point by AE. Small bore (2" & under) field run piping supplied by FGD. Site erection by EC. |
| 243   | Limestone Prep Area Sump Transfer                                    | FGD  | FGD           | FGD    | EC            |   |
| 244   | Absorber Area Sump Transfer  | FGD  | FGD           | FGD    | EC            |   |
| 245   | Dewatering Area Sump Transfer  | FGD  | FGD           | FGD    | EC            |   |
| 246   | Flush Water  | FGD  | FGD           | FGD    | EC            | Single Supply Point by AE   |
| 247   | Firewater loop mods, hydrants, hose stations                         | AE   | AE            | ESC    | ESC           | AE to supply DEA drawings and material takeoffs.  |
| 248   | Potable Water  | AE   | AE            | ESC    | ESC           | AE to supply DEA drawings and material takeoffs.  |
| 249   | Sanitary Water   | AE   | AE            | ESC    | ESC           | AE to supply DEA drawings and material takeoffs.  |
| 250   | Process Drain and Vents (in FGD Island)                              | FGD  | FGD           | FGD    | EC            | Small bore (2" & under) field run piping supplied by FGD. Site erection by EC.                            |
| 251   | Process Drain and Vents (in BOP)                                     | AE   | ESC           | ESC    | ESC           | Single Supply Point by AE. Small bore (2" & under) field run piping supplied by FGD. Site erection by EC. |
| 252   | Service & Instrument Air (Within Islands)                            | FGD  | FGD           | FGD    | EC            |   |
| 253   | Closed Cycle Cooling Water (Within Island)                           | N/A  | N/A           | N/A    | N/A           |   |
| 254   | FGD Process Piping (Outside of Island)                               | FGD  | AE            | AE     | EC            | Small bore (2" & under) field run piping supplied by FGD. Site erection by EC.                            |
| 255   | BOP Process Piping (Outside of Island)                               | AE   | AE            | ESC    | ESC           | AE to supply DEA drawings and material takeoffs.  |
| 256   | Stack Water Collection Piping to Absorber Island                     | AE   | AE            | ESC    | ESC           | FGD OEM responsible for piping to Absorber located inside island.   |
| 257   | <b>Mech. Eng. Technical Data</b>                                     |  |               |        |               |   |
| 258   | FGD Coating/Paint Spec   | FGD  | FGD           | N/A    | N/A           |   |
| 259   | FGD Piping and Instrument Diagrams                                   | FGD  | FGD           | N/A    | N/A           |   |
| 260   | FGD Piping Isometric Drawings  | FGD  | FGD           | N/A    | N/A           |   |
| 261   | FGD Equipment List   | FGD  | FGD           | N/A    | N/A           |   |
| 262   | FGD Piping Line List   | FGD  | FGD           | N/A    | N/A           |   |
| 263   | FGD Valve List   | FGD  | FGD           | N/A    | N/A           |   |



| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |   | Division of Work (DOW) Legend |  |        |               | Comments   |
|---|---|-------------------------------|--|--------|---------------|--|
|   |   | FGD                           | AE   | EC     | O             |  |
| Revision Date: <b>November 17, 2004</b>   |   | FGD                           | FGD Supplier   |        |               |  |
| Current Rev #: <b>Rev 0</b>   |   | AE                            | Architect Engineer-PE&C                                      |        |               |  |
|   |   | EC                            | Erection Contractor  |        |               |  |
|   |   | O                             | Owner-AEP  |        |               |  |
|   |   | ESC                           | Material & Installation by subcontractor managed by AE or EC |        |               |  |
|   |   | SGS                           | Steam Generator Supplier/OEM                                 |        |               |  |
|   |   | C                             | Chimney Supplier   |        |               |  |
|   |   | TBD                           | To Be Determined   |        |               |  |
|   |   | N/A                           | Not Applicable for this Project or Task                      |        |               |  |
| Item  | Description   | Functional Design             | Detail Design  | Supply | Site Erection | Comments   |
| 301   | FGD System Descriptions   | FGD                           | FGD  | N/A    | N/A           |  |
| 302   | BOP System Descriptions   | AE                            | AE   | N/A    | N/A           |  |
| 303   | DCS System Hardware   | AE/O                          | AE/O   | O      | EC            |  |
| 304   | DCS (Logics)  | AE/O                          | AE/O   | O      | N/A           |  |
| 305   | DCS Factory Acceptance Testing  | O                             | O  | O      | N/A           | Require FGD OEM to be present                        |
| 306   | Instrument Installation Materials   | FGD/AE                        | FGD/AE   | ESC    | ESC           |  |
| 307   | <b>Electrical Design Drawings &amp; Documents</b>                               |                               |  |        |               |  |
| 308   | Single Line Diagrams  | AE                            | AE   | N/A    | N/A           |  |
| 309   | Elementary Diagrams   | AE                            | AE   | N/A    | N/A           |  |
| 310   | Interconnection Diagrams  | AE                            | AE   | N/A    | N/A           |  |
| 311   | Electrical/Electronics Room Layout  | AE                            | AE   | N/A    | N/A           |  |
| 312   | Electrical Load List  | AE                            | AE   | N/A    | N/A           | Input from FGD OEM.                                  |
| 313   | Power System Studies (SKM)  | AE                            | AE   | N/A    | N/A           |  |
| 314   | <b>Power Distribution Equipment</b>   |                               |  |        |               |  |
| 315   | Unit Aux Transformer  | AE                            | AE   | AE     | EC            |  |
| 316   | Iso-Phase Bus & Modifications   | AE                            | AE   | AE     | EC            |  |
| 317   | Non-Seg Bus and Modifications   | AE                            | AE   | AE     | EC            |  |
| 318   | Medium Voltage Cable Bus  | AE                            | AE   | AE     | EC            |  |
| 319   | Substation / Load Center  | AE                            | AE   | AE     | EC            |  |
| 320   | Transformers  | AE                            | AE   | AE     | EC            |  |
| 321   | Switchgear  | AE                            | AE   | AE     | EC            |  |
| 322   | Motor Control Centers (MCC)   | AE                            | AE   | AE     | EC            |  |
| 323   | Bus Ducts   | AE                            | AE   | AE     | EC            |  |
| 324   | Power Distribution Panels   | AE                            | AE   | ESC    | ESC           |  |
| 325   | FGD Process Equipment Variable Frequency Drives (480V)                          | FGD                           | FGD  | FGD    | EC            | Supplied with Equipment                              |
| 326   | BOP Process Equipment Variable Frequency Drives (480V)                          | AE                            | AE   | AE     | EC            | Supplied with Equipment                              |
| 327   | <b>Transmission of Bulk Power to FGD Substation</b>                             |                               |  |        |               |  |
| 328   | Existing substation modifications   | AE                            | AE   | O      | O             |  |
| 329   | New Transmission Line   | AE                            | AE   | AE/O   | EC/O          | If overhead: owner responsible for supply & erection |
| 330   | New FGD Substation HV   | AE                            | EC   | EC     | EC            |  |
| 331   | <b>Power Sources Equipment</b>  |                               |  |        |               |  |
| 332   | U P S   | AE                            | AE   | AE     | EC            |  |
| 333   | Batteries   | AE                            | AE   | AE     | EC            |  |
| 334   | <b>Motors (Provided with Equipment)</b>   |                               |  |        |               |  |
| 335   | FGD Process Equipment Motors <5 HP (Use Industry Standard Voltage)              | FGD                           | FGD  | FGD    | EC            | Supplied with Equipment                              |
| 336   | FGD Process Equipment Low Voltage Motors 5 to 250 HP (480V)                     | FGD                           | FGD  | FGD    | EC            | Supplied with Equipment                              |
| 337   | FGD Process Equipment Medium Voltage Motors from > 250 HP to < 5000 HP (4.16kV) | FGD                           | FGD  | FGD    | EC            | Supplied with Equipment                              |
| 338   | FGD Process Equipment Motors >5000 HP   | FGD                           | FGD  | FGD    | EC            |  |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |   | Division of Work (DOW) Legend                                |               |        |               |  |
|---|---|--|---------------|--------|---------------|--|
|   |   | FGD  | AE            | EC     | O             | ESC  |
| Revision Date: <b>November 17, 2004</b>   |   | FGD Supplier   |               |        |               |  |
| Current Rev #: <b>Rev 0</b>   |   | Architect Engineer-PE&C                                      |               |        |               |  |
|   |   | Erection Contractor  |               |        |               |  |
|   |   | Owner-AEP  |               |        |               |  |
|   |   | Material & Installation by subcontractor managed by AE or EC |               |        |               |  |
|   |   | Steam Generator Supplier/OEM                                 |               |        |               |  |
|   |   | Chimney Supplier   |               |        |               |  |
|   |   | To Be Determined   |               |        |               |  |
|   |   | Not Applicable for this Project or Task                      |               |        |               |  |
|   |   | TBD  |               |        |               |  |
|   |   | N/A  |               |        |               |  |
| Item  | Description   | Functional Design  | Detail Design | Supply | Site Erection | Comments   |
| 339   | BOP Process Equipment Motors <5 HP (Use Industry Standard Voltage)              | AE   | AE            | AE     | EC            | Supplied with Equipment  |
| 340   | BOP Process Equipment Low Voltage Motors 5 to 250 HP (480V)                     | AE   | AE            | AE     | EC            | Supplied with Equipment  |
| 341   | BOP Process Equipment Medium Voltage Motors > 250 HP to 5000 HP (4.16kV)        | AE   | AE            | AE     | EC            | Supplied with Equipment  |
| 342   | BOP Equipment Motors >5000 HP   | AE   | AE            | AE     | EC            |  |
| 343   | <b>Electrical Miscellaneous</b>   |  |               |        |               |  |
| 344   | Junction Boxes integral to FGD Skid Mounted Equipment                           | FGD  | FGD           | FGD    | N/A           |  |
| 345   | Junction Boxes integral to BOP Skid Mounted Equipment                           | AE   | AE            | AE     | N/A           |  |
| 346   | Junction Boxes (Balance of Plant)   | AE   | AE            | ESC    | ESC           |  |
| 347   | Local Control Stations (FGD Process)  | FGD  | FGD           | FGD    | EC            | Requirements need to be defined                                |
| 348   | Local Control Stations (BOP Process)  | AE   | AE            | ESC    | ESC           | Requirements need to be defined                                |
| 349   | <b>Electrical Installation (within Absorber/Limestone Prep Areas)</b>           |  |               |        |               |  |
| 350   | Electrical Install Spec/Scope of Work Doc.                                      | AE   | AE            | AE     | N/A           |  |
| 351   | Lighting  | AE   | AE            | ESC    | ESC           |  |
| 352   | Communications  | AE   | AE            | ESC    | ESC           |  |
| 353   | Fire Detection  | AE   | AE            | ESC    | ESC           |  |
| 354   | Heat Tracing (FGD Process)  | FGD  | AE            | ESC    | ESC           |  |
| 355   | Heat Tracing (BOP Process)  | AE   | AE            | ESC    | ESC           |  |
| 356   | Raceways to Junction Boxes integral to FGD Process Equipment Skid Mounted       | FGD  | FGD           | FGD    | N/A           |  |
| 357   | Raceways to Junction Boxes integral to BOP Process Equipment Skid Mounted       | AE   | AE            | AE     | N/A           |  |
| 358   | Raceways  | AE   | AE            | ESC    | ESC           |  |
| 359   | Cable / Wiring to Junction Boxes integral to FGD Process Equipment Skid Mounted | FGD  | FGD           | FGD    | N/A           |  |
| 360   | Cable / Wiring to Junction Boxes integral to BOP Process Equipment Skid Mounted | AE   | AE            | AE     | N/A           |  |
| 361   | Cable / Wiring  | AE   | AE            | ESC    | ESC           |  |
| 362   | Grounding   | AE   | AE            | ESC    | ESC           |  |
| 363   | Lightning Protection  | AE   | AE            | ESC    | ESC           |  |
| 364   | Cathodic Protection   | AE   | AE            | ESC    | ESC           |  |
| 365   | Welding / Maint Recept  | AE   | AE            | ESC    | ESC           |  |
| 366   | <b>Permits</b>  |  |               |        |               | Reference to insurance removed                                 |
| 367   | Environmental (Air, Water, Disposal)  | O  | O             | O      | O             |  |
| 368   | Corp of Engineers   | O  | O             | O      | O             |  |
| 369   | Building Permit   | N/A  | N/A           | EC/O   | N/A           |  |
| 370   | <b>Civil</b>  |  |               |        |               |  |
| 371   | Excavation  | AE/ESC   | AE/ESC        | ESC    | ESC           | Excavation by ESC typically. But, if required excavation by AE |
| 372   | Foundations   | AE   | AE            | ESC    | ESC           |  |
| 373   | Piping and Electrical Underground   | AE   | AE            | ESC    | ESC           |  |
| 374   | Slabs & Pads, Elevated (Within FGD Islands)                                     | FGD/AE   | AE            | ESC    | ESC           |  |
| 375   | Slabs & Pads, Elevated (Outside FGD Islands)                                    | AE   | AE            | ESC    | ESC           |  |
| 376   | Grading & Drainage  | AE   | AE            | ESC    | ESC           |  |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |  | Division of Work (DOW) Legend |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
|---|--|-------------------------------|--------------|-------------------|-------------------------|--------|---------------------|---|-----------|-----|--|-----|------------------------------|---|------------------|-----|------------------|
|   |  | FGD                           | FGD Supplier | AE                | Architect Engineer-PE&C | EC     | Erection Contractor | O   | Owner-AEP | ESC | Material & Installation by subcontractor managed by AE or EC | SGS | Steam Generator Supplier/OEM | C | Chimney Supplier | TBD | To Be Determined |
| Revision Date: <b>November 17, 2004</b><br>Current Rev #: <b>Rev 0</b>                                  |  | Item                          | Description  | Functional Design | Detail Design           | Supply | Site Erection       | Comments  |           |     |  |     |                              |   |                  |     |                  |
| 377   | Paving                                       | AE                            | AE           | ESC               | ESC                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 378   | Fencing                                      | AE                            | AE           | ESC               | ESC                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 379   | <b>Site Construction Services</b>            |                               |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 380   | Site Supervision                             | N/A                           | N/A          | EC                | N/A                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 381   | Site Technical Supervision                   | N/A                           | N/A          | EC                | N/A                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 382   | Construction Advisor (Site)                  | N/A                           | N/A          | FGD/AE            | N/A                     |        |                     | Each his own  |           |     |  |     |                              |   |                  |     |                  |
| 383   | Safety Supervision (Site)                    | N/A                           | N/A          | O/EC              | N/A                     |        |                     | Each his own  |           |     |  |     |                              |   |                  |     |                  |
| 384   | Construction Coordination (HO)               | N/A                           | N/A          | EC                | N/A                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 385   | Engineering Support (HO)                     | N/A                           | N/A          | FGD/AE            | N/A                     |        |                     | Each his own  |           |     |  |     |                              |   |                  |     |                  |
| 386   | Site Support Services (Site)                 | N/A                           | N/A          | FGD/AE            | N/A                     |        |                     | Each his own  |           |     |  |     |                              |   |                  |     |                  |
| 387   | Temporary Utilities & Services               | AE                            | AE           | O                 | O                       |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 388   | Unloading and Site Storage                   | AE                            | AE           | EC/ESC            | EC/ESC                  |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 389   | Craneage / Lifting Equipment                 | AE/EC                         | AE/EC        | EC                | EC                      |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 390   | Office Trailers                              | N/A                           | N/A          | EC                | EC                      |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 391   | Office Equipment                             | N/A                           | N/A          | EC                | EC                      |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 392   | Vehicles                                     | N/A                           | N/A          | FGD/AE/EC         | N/A                     |        |                     | Each his own  |           |     |  |     |                              |   |                  |     |                  |
| 393   | Safety Equipment                             | N/A                           | N/A          | FGD/AE/EC         | N/A                     |        |                     | Each his own  |           |     |  |     |                              |   |                  |     |                  |
| 394   | Site Computer Services                       | N/A                           | N/A          | FGD/O/EC          | FGD/O/EC                |        |                     | Each his own  |           |     |  |     |                              |   |                  |     |                  |
| 395   | Mobilization/Demobilization Costs            | N/A                           | N/A          | EC                | N/A                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 396   | Site Construction Services Subcontractor     | N/A                           | N/A          | AE/EC/O           | N/A                     |        |                     | Each his own  |           |     |  |     |                              |   |                  |     |                  |
| 397   | <b>Buildings &amp; Structures</b>            |                               |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
|   | FGD Process Island Buildings (Architectural) |                               |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 398   |  | AE                            | AE           | ESC               | ESC                     |        |                     | GA & Equip loading data from suppliers  |           |     |  |     |                              |   |                  |     |                  |
| 399   | Miscellaneous Buildings (Pre-engineered)     | AE                            | AE           | ESC               | ESC                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 400   | Warehouse/shops                              | AE                            | AE           | ESC               | ESC                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 401   | <b>Commissioning/Startup</b>                 |                               |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 402   | Commissioning FGD Technical Support          | N/A                           | N/A          | FGD               | N/A                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 403   | Commissioning BOP Technical Support          | N/A                           | N/A          | AE                | N/A                     |        |                     | Quoted as an option.  |           |     |  |     |                              |   |                  |     |                  |
| 404   | Commissioning & Startup Standby Labor        | N/A                           | N/A          | EC/O              | N/A                     |        |                     | Each his own.   |           |     |  |     |                              |   |                  |     |                  |
| 405   | Commissioning Coordination                   | N/A                           | N/A          | FGD/AE/O          | N/A                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 406   | <b>Training</b>                              |                               |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
|   |  |                               |              |                   |                         |        |                     | Based on providing training including FGD subvendors to 4 groups. Each group will be trained for a minimum of 10 days. The training will be provided in 4 separate calendar periods (1 group per period). |           |     |  |     |                              |   |                  |     |                  |
| 407   | FGD System Training Program Delivery         | N/A                           | N/A          | FGD               | N/A                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 408   | BOP System Training Program                  | N/A                           | N/A          | O                 | N/A                     |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 409   | <b>Performance Testing</b>                   |                               |              |                   |                         |        |                     |   |           |     |  |     |                              |   |                  |     |                  |
| 410   | Performance Testing Site Support             | N/A                           | N/A          | FGD/AE            | N/A                     |        |                     | Each his own  |           |     |  |     |                              |   |                  |     |                  |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |   | Division of Work (DOW) Legend |   |           |               | Comments   |
|---|---|-------------------------------|---|-----------|---------------|--|
|   |   | FGD                           | AE                                      | EC        | O             |  |
| Revision Date: <b>November 17, 2004</b>   |   | FGD                           | AE                                      | EC        | O             |  |
| Current Rev #: <b>Rev 0</b>   |   | ESC                           | SGS                                     | C         | TBD           |  |
|   |   | N/A                           | Not Applicable for this Project or Task |           |               |  |
| Item  | Description   | Functional Design             | Detail Design                           | Supply    | Site Erection | Comments   |
| 411   | Performance Testing   | N/A                           | N/A                                     | O         | N/A           |  |
| 412   | <b>Warranty</b>   |                               |   |           |               |  |
| 413   | Performance Guarantees for FGD Process Equipment            | N/A                           | N/A                                     | FGD       | N/A           | As expressly stated in the proposal.                       |
| 414   | Extended  | N/A                           | N/A                                     | N/A       | N/A           |  |
| 415   | Material & Workmanship                                      | N/A                           | N/A                                     | FGD/AE/EC | N/A           | Warranty on BOP equipment will be a pass through to Owner. |
| 416   | <b>Freight</b>  |                               |   |           |               |  |
| 417   | Freight   | N/A                           | N/A                                     | FGD/AE    | N/A           | By BOP equipment supplier.                                 |
| 418   | Postage/Express Delivery                                    | N/A                           | N/A                                     | FGD/AE    | N/A           |  |
| 419   | Customs Fees / Duties                                       | N/A                           | N/A                                     | FGD/AE    | N/A           | If required. By BOP equipment supplier.                    |
| 420   | Packing   | N/A                           | N/A                                     | FGD/AE    | N/A           | By BOP equipment supplier.                                 |
| 421   | <b>Travel &amp; Relocation Associated with Construction</b> |                               |   |           |               |  |
| 422   | Project Related Travel                                      | N/A                           | N/A                                     | FGD/AE    | N/A           |  |
| 423   | Personnel Relocation  | N/A                           | N/A                                     | FGD/AE    | N/A           |  |
| 424   | Interim Living Expenses                                     | N/A                           | N/A                                     | FGD/AE    | N/A           |  |
| 425   | <b>Turnover Documentation</b>                               |                               |   |           |               |  |
| 426   | O&M Manual  | FGD/AE                        | FGD/AE                                  | FGD/AE    | N/A           | Each his own.  |
| 427   | Lubrication Manuals   | FGD/AE                        | FGD/AE                                  | FGD/AE    | N/A           | Each his own.  |
| 428   | As-Built Dwgs   | FGD/AE                        | FGD/AE                                  | FGD/AE    | N/A           | Each his own.  |
| 429   | Training Manual for FGD Process Equipment                   | FGD                           | FGD                                     | FGD       | N/A           |  |
| 430   | Spare Parts List  | FGD/AE                        | FGD/AE                                  | FGD/AE    | N/A           | Each his own.  |
| 431   | Commissioning Manual  | FGD/AE                        | FGD/AE                                  | FGD/AE    | N/A           | Each his own. Quoted as an option for BOP.                 |
| 432   | <b>Taxes</b>  |                               |   |           |               |  |
| 433   | Sales Taxes   | N/A                           | N/A                                     | O         | EC/ESC        | Owner to pay sales tax & other taxes.                      |
| 434   | Other Taxes (Example: Payroll Taxes)                        | N/A                           | N/A                                     | FGD/AE/O  | N/A           | Each his own   |
| 435   | <b>Schedule</b>   |                               |   |           |               |  |
| 436   | Top Level/Milestones Schedule                               | O                             | O/AE                                    | O         | N/A           |  |
| 437   | Detailed Schedule   | O/AE                          | O/AE                                    | AE        | N/A           |  |
| 438   |   |                               |   |           |               |  |
| 439   | <b>Coal Handling System Modifications for Coal Blending</b> |                               |   |           |               |  |
| 440   | TBD   | TBD                           | TBD                                     | TBD       | TBD           |  |
| 441   | TBD   | TBD                           | TBD                                     | TBD       | TBD           |  |
| 442   | TBD   | TBD                           | TBD                                     | TBD       | TBD           |  |
| 443   | TBD   | TBD                           | TBD                                     | TBD       | TBD           |  |
| 444   | TBD   | TBD                           | TBD                                     | TBD       | TBD           |  |
| 445   | TBD   | TBD                           | TBD                                     | TBD       | TBD           |  |

| Project Name: <b>Big Sandy Plant - Unit 2 WFGD<br/>Total Project Scope Split<br/>Target Cost Option</b> |  | Division of Work (DOW) Legend |  |        |               |          |
|---|--|-------------------------------|--|--------|---------------|----------|
| Revision Date: <b>November 17, 2004</b>   |  | FGD                           | FGD Supplier   |        |               |          |
| Current Rev #: <b>Rev 0</b>   |  | AE                            | Architect Engineer-PE&C                                      |        |               |          |
|   |  | EC                            | Erection Contractor  |        |               |          |
|   |  | O                             | Owner-AEP  |        |               |          |
|   |  | ESC                           | Material & Installation by subcontractor managed by AE or EC |        |               |          |
|   |  | SGS                           | Steam Generator Supplier/OEM                                 |        |               |          |
|   |  | C                             | Chimney Supplier   |        |               |          |
|   |  | TBD                           | To Be Determined   |        |               |          |
|   |  | N/A                           | Not Applicable for this Project or Task                      |        |               |          |
| Item  | Description  | Functional Design             | Detail Design  | Supply | Site Erection | Comments |
| 446   |  |                               |  |        |               |          |
| 447   | <b>BALANCED DRAFT CONVERSION (BDC)</b>                         |                               |  |        |               |          |
| 448   | Steam Generator Reinforcement                                  | O                             | O  | O      | EC            |          |
| 449   | Air Pre-Heater reinforcement                                   | O                             | O  | O      | EC            |          |
| 450   | Flues Between Air Pre-Heater Outlet to ESP Inlet Reinforcement | O                             | O  | O      | EC            |          |
| 451   | Electrostatic Precipitator (ESP) Reinforcement                 | O                             | O  | O      | EC            |          |
| 452   | Insulation & Lagging   | O                             | O  | EC     | EC            |          |
| 453   | Induced Draft Fan  | AE                            | AE   | TBD    | EC            |          |
| 454   | Induced Draft Fan Motors                                       | AE                            | AE   | TBD    | EC            |          |
| 455   | FD Fan Modifications   | AE                            | AE   | TBD    | EC            |          |
| 456   | Electrical upgrades for ID Fans                                | AE                            | AE   | TBD    | EC            |          |
| 457   |  |                               |  |        |               |          |
| 458   | <b>COAL BURNING FLEXIBILITY (CBF)</b>                          |                               |  |        |               |          |
| 459   | Install "Nose" on Furnace Rear Wall                            | O                             | O  | O      | EC            |          |
| 460   | Water Cannons and Water Lances                                 | AE                            | AE   | AE     | EC            |          |
| 461   | Sootblowers  | AE                            | AE   | AE     | EC            |          |
| 462   | Thermal Imaging Systems  | AE                            | AE   | AE     | EC            |          |
| 463   | Piping Systems   | AE                            | AE   | AE     | EC            |          |
| 464   | Electrical Systems   | AE                            | AE   | AE     | EC            |          |
| 465   | Furnace Wall Tubing Overlay                                    | O/AE                          | AE   | EC     | EC            |          |

## Appendix A

# WFGD Material Balance Tables and Process Flow Diagrams

## Big Sandy Unit 2

|                        |               |  |             |            |            |   |   |   |  |
|------------------------|---------------|--|-------------|------------|------------|---|---|---|--|
| <b>PARSONS E&amp;C</b> | CLIENT NAME:  | AEP                                      | Revision:   | A          | 0          | 1 | 2 | 3 | JOB NUMBER:<br>53762301                    |
|                        | PROJECT NAME: | Big Sandy Unit 2                         | Originator: | Jay White  | Jay White  |   |   |   |  |
|                        | SUBJECT:      | Boiler and FGD Material Balance Estimate | Reviewer:   | B. Graeffe | B. Graeffe |   |   |   | CALCULATION NUMBER:<br>AEBS-2-DC-042-5-001 |
|                        | WORKSHEET:    | Material Balance Report Sheets           | Date:       | 10/19/2004 | 12/16/2004 |   |   |   |  |

KPSC Case No. 2011-00401  
 Sierra Club First Set of Data Requests  
 Dated January 13, 2012  
 Item No. 27(a)  
 Attachment 1  
 Page 79 of 113

**Big Sandy Unit 2 - WFGD Gas Path Material Balance - 100% MCR Load Condition**

| Stream                 | 1          |                | 2       |                  | 3       |                          | 4       |                        | 5       |                         | 6       |                     | 7       |                             | 8       |                                 | 9       |                            | 10      |      |
|------------------------|------------|----------------|---------|------------------|---------|--------------------------|---------|------------------------|---------|-------------------------|---------|---------------------|---------|-----------------------------|---------|---------------------------------|---------|----------------------------|---------|------|
|                        | Coal Input | ID Fan Suction |         | ID Fan Discharge |         | Flue Gas to FGD Absorber |         | Flue Gas Entering WESP |         | Flue Gas Entering Stack |         | Oxidation Air Inlet |         | Oxidation Air Blower Outlet |         | Sat'd Ox. Air with Quench Water |         | Oxidation Air Quench Water |         |      |
|                        |            | Mass           | Mass    | Mole             | Mass    | Mole                     | Mass    | Mole                   | Mass    | Mole                    | Mass    | Mole                | Mass    | Mole                        | Mass    | Mole                            | Mass    | Mole                       | Mass    | Mole |
| Ar                     |            | 58,747         | 1,471   | 58,747           | 1,471   | 117,493                  | 2,941   | 118,487                | 2,966   | 118,487                 | 2,966   | 994                 | 25      | 994                         | 25      | 994                             | 25      | 0                          | 0       |      |
| CO2                    |            | 826,412        | 18,778  | 826,412          | 18,778  | 1,652,824                | 37,556  | 1,678,098              | 38,130  | 1,678,098               | 38,130  | 0                   | 0       | 0                           | 0       | 0                               | 0       | 0                          | 0       |      |
| HCL                    |            | 674            | 18      | 674              | 18      | 1,347                    | 37      | 0                      | 0       | 0                       | 0       | 0                   | 0       | 0                           | 0       | 0                               | 0       | 0                          | 0       |      |
| HF                     |            | 7              | 0       | 7                | 0       | 14                       | 1       | 0                      | 0       | 0                       | 0       | 0                   | 0       | 0                           | 0       | 0                               | 0       | 0                          | 0       |      |
| H2O                    |            | 191,426        | 10,626  | 191,426          | 10,626  | 382,853                  | 21,251  | 961,672                | 53,381  | 961,672                 | 53,381  | 523                 | 29      | 523                         | 29      | 2,918                           | 162     | 2,395                      | 133     |      |
| N2                     |            | 3,426,208      | 122,306 | 3,426,208        | 122,306 | 6,852,417                | 244,612 | 6,910,291              | 246,678 | 6,910,291               | 246,678 | 57,874              | 2,066   | 57,874                      | 2,066   | 57,874                          | 2,066   | 0                          | 0       |      |
| NH3                    |            | 4              | 0       | 4                | 0       | 9                        | 1       | 9                      | 1       | 9                       | 1       | 0                   | 0       | 0                           | 0       | 0                               | 0       | 0                          | 0       |      |
| NO                     |            | 228            | 8       | 228              | 8       | 456                      | 15      | 456                    | 15      | 456                     | 15      | 0                   | 0       | 0                           | 0       | 0                               | 0       | 0                          | 0       |      |
| NO2                    |            | 18             | 0       | 18               | 0       | 37                       | 1       | 37                     | 1       | 37                      | 1       | 0                   | 0       | 0                           | 0       | 0                               | 0       | 0                          | 0       |      |
| O2                     |            | 335,798        | 10,494  | 335,798          | 10,494  | 671,596                  | 20,988  | 680,576                | 21,269  | 680,576                 | 21,269  | 17,774              | 555     | 17,774                      | 555     | 17,774                          | 555     | 0                          | 0       |      |
| SO2                    |            | 18,054         | 282     | 18,054           | 282     | 36,107                   | 564     | 722                    | 11      | 722                     | 11      | 0                   | 0       | 0                           | 0       | 0                               | 0       | 0                          | 0       |      |
| SO3                    |            | 414            | 5       | 414              | 5       | 827                      | 10      | 579                    | 7       | 579                     | 7       | 0                   | 0       | 0                           | 0       | 0                               | 0       | 0                          | 0       |      |
| Total Gas Flow, Wet    |            | 4,857,990      | 163,988 | 4,857,990        | 163,988 | 9,715,981                | 327,977 | 10,350,927             | 362,459 | 10,350,927              | 362,459 | 77,164              | 2,675   | 77,164                      | 2,675   | 79,560                          | 2,808   | 2,395                      | 133     |      |
| Total Gas Flow, Dry    |            | 4,686,564      | 153,363 | 4,686,564        | 153,363 | 9,333,128                | 306,725 | 9,389,255              | 309,078 | 9,389,255               | 309,078 | 76,642              | 2,646   | 76,642                      | 2,646   | 76,642                          | 2,646   | 0                          | 0       |      |
| Coal                   | 654,924    | 0              |         | 0                |         | 0                        |         | 0                      |         | 0                       |         |                     |         |                             |         |                                 |         |                            |         |      |
| Ash                    | 0          | 965            |         | 965              |         | 1,930                    |         | 0                      |         | 0                       |         |                     |         |                             |         |                                 |         |                            |         |      |
| Total Solids Flow      | 654,924    | 965            |         | 965              |         | 1,930                    |         | 488                    |         | 488                     |         |                     |         |                             |         |                                 |         |                            |         |      |
| Total Stream Mass Flow | 654,924    | 4,858,956      |         | 4,858,956        |         | 9,717,911                |         | 10,351,414             |         | 10,351,414              |         | 77,164              |         | 77,164                      |         | 79,560                          |         | 2,395                      |         |      |
| Gas Flow, ACFM         |            | 1,706,092      |         | 1,592,796        |         | 3,189,465                |         | 2,644,704              |         | 2,648,024               |         | 17,602              |         | 11,135                      |         | 9,592                           |         | n/a                        |         |      |
| Mol. Wt.               |            |                | 29.6240 |                  | 29.6240 |                          | 29.6240 |                        | 28.5575 |                         | 28.5575 |                     | 28.8434 |                             | 28.8434 |                                 | 28.3307 |                            | 18.0153 |      |
| Temp, deg F            |            | 321            |         | 349              |         | 349                      |         | 128                    |         | 128                     |         | 70                  |         | 251                         |         | 121                             |         | 70                         |         |      |
| Pressure, psia         |            | 13.42          |         | 14.88            |         | 14.88                    |         | 14.41                  |         | 14.39                   |         | 14.39               |         | 30.54                       |         | 30.39                           |         | 50                         |         |      |

**Big Sandy Unit 2 - WFGD Primary Dewatering and Reagent Preparation Material Balance - 100% MCR Load Condition**


| Stream                 | 20                | 21                    | 22                     | 23       | 24                           | 25                   | 26                        | 30                         | 31                                | 32                           |
|------------------------|-------------------|-----------------------|------------------------|----------|------------------------------|----------------------|---------------------------|----------------------------|-----------------------------------|------------------------------|
| Component lb/hr        | Hydrocyclone Feed | Hydrocyclone Overflow | Hydrocyclone Underflow | Blowdown | Limestone Slurry to Absorber | Filtrate to Absorber | Overheads to Reclaim Tank | Raw Limestone to Ball Mill | Classified Slurry to Storage Tank | Make-Up Water to Slurry Prep |
|                        | lb/hr             | lb/hr                 | lb/hr                  | lb/hr    | lb/hr                        | lb/hr                | lb/hr                     | lb/hr                      | lb/hr                             | lb/hr                        |
| CaCO3                  | 2,172             | 651                   | 1,520                  | 192      | 58,037                       | 489                  | 459                       | 58,037                     | 58,037                            | 0                            |
| CaSO3:1/2H2O           | 554               | 277                   | 277                    | 82       | 0                            | 201                  | 195                       | 0                          | 0                                 | 0                            |
| CaSO4:2H2O             | 103,338           | 10,334                | 93,004                 | 3,053    | 0                            | 9,141                | 7,281                     | 0                          | 0                                 | 0                            |
| H2O                    | 456,706           | 361,000               | 95,705                 | 106,646  | 147,170                      | 696,952              | 254,354                   | 3,154                      | 147,170                           | 144,016                      |
| MgCO3                  | 1,769             | 1,150                 | 619                    | 340      | 1,893                        | 822                  | 810                       | 1,893                      | 1,893                             | 0                            |
| Alkali Inerts          | 5,946             | 3,865                 | 2,081                  | 1,142    | 3,154                        | 2,765                | 2,723                     | 3,154                      | 3,154                             | 0                            |
| Flyash                 | 3,337             | 2,670                 | 667                    | 789      | 0                            | 1,894                | 1,881                     | 0                          | 0                                 | 0                            |
| TDS                    | 11,754            | 9,291                 | 2,463                  | 2,745    | 26                           | 9,052                | 6,546                     | 0                          | 26                                | 26                           |
| Total Flow             | 585,575           | 389,237               | 196,337                | 114,988  | 210,280                      | 721,317              | 274,250                   | 66,238                     | 210,280                           | 144,042                      |
| Flow, gpm              | 1031              | 751                   | 280                    | 222      | 347                          | 1,429                | 529                       | n/a                        | 347                               | 291                          |
| Specific Gravity       | 1.13              | 1.03                  | 1.40                   | 1.03     | 1.21                         | 1.01                 | 1.03                      | n/a                        | 1.21                              | 0.99                         |
| Cl <sup>-</sup> , ppmw | 12,000            | 12,000                | 12,000                 | 12,000   | 19                           | 2638                 | 12,000                    | n/a                        | 19                                | 19                           |
| TSS, %                 | 20.00             | 4.87                  | 50.00                  | 4.87     | 30.00                        | 0.44                 | 4.87                      | 95.24                      | 30.00                             | 0.00                         |
| TDS, %                 | 2.51              | 2.51                  | 2.51                   | 2.51     | 0.02                         | 0.56                 | 2.51                      | n/a                        | 0.02                              | 0.02                         |

|   |               |  |             |            |            |   |   |   |                     |
|---|---------------|--|-------------|------------|------------|---|---|---|---------------------|
| <b>PARSONS E&amp;C</b><br><br>CALCULATION SHEET | CLIENT NAME:  | AEP                                      | Revision:   | A          | 0          | 1 | 2 | 3 | JOB NUMBER:         |
|   | PROJECT NAME: | Big Sandy Unit 2                         | Originator: | Jay White  | Jay White  |   |   |   | 53762301            |
|   | SUBJECT:      | Boiler and FGD Material Balance Estimate | Reviewer:   | B. Graeffe | B. Graeffe |   |   |   | CALCULATION NUMBER: |
|   | WORKSHEET:    | Material Balance Report Sheets           | Date:       | 10/19/2004 | 12/6/2004  |   |   |   | AEBS-2-DC-042-5-001 |

KPSC Case No. 2011-00401  
 Sierra Club First Set of Data Requests  
 Dated January 13, 2012  
 Item No. 27(a)  
 Attachment 1  
 Page 80 of 113

**Big Sandy Unit 2 - WFGD Secondary Dewatering Material Balance - 100% MCR Load Condition**

| Stream                 | 41                      | 42                                | 43                        | 44                          | 45                     | 46                            | 50                                    | 51                       |
|------------------------|-------------------------|-----------------------------------|---------------------------|-----------------------------|------------------------|-------------------------------|---------------------------------------|--------------------------|
| Component lb/hr        | Vacuum Belt Filter Feed | Vacuum Belt Filter Cake Discharge | Cake to Stackout Conveyor | Vacuum Belt Filter Filtrate | Filter Cake Wash Water | Make-Up Water To Reclaim Tank | General Make-Up Water to Make-Up Tank | Water to Mist Eliminator |
|                        | lb/hr                   | lb/hr                             | lb/hr                     | lb/hr                       | lb/hr                  | lb/hr                         | lb/hr                                 | lb/hr                    |
| CaCO3                  | 1,520                   | 1,490                             | 1,490                     | 30                          | 0                      | 0                             | 0                                     | 0                        |
| CaSO3:1/2H2O           | 277                     | 271                               | 271                       | 6                           | 0                      | 0                             | 0                                     | 0                        |
| CaSO4:2H2O             | 93,004                  | 91,144                            | 91,144                    | 1,860                       | 0                      | 0                             | 0                                     | 0                        |
| H2O                    | 95,705                  | 10,667                            | 10,667                    | 107,162                     | 22,123                 | 335,436                       | 711,853                               | 207,883                  |
| MgCO3                  | 619                     | 607                               | 607                       | 12                          | 0                      | 0                             | 0                                     | 0                        |
| Alkali Inerts          | 2,081                   | 2,039                             | 2,039                     | 42                          | 0                      | 0                             | 0                                     | 0                        |
| Flyash                 | 667                     | 654                               | 654                       | 13                          | 0                      | 0                             | 0                                     | 0                        |
| TDS                    | 2,463                   | 22                                | 22                        | 2,445                       | 4                      | 61                            | 130                                   | 38                       |
| <b>Total Flow</b>      | <b>196,337</b>          | <b>106,895</b>                    | <b>106,895</b>            | <b>111,570</b>              | <b>22,127</b>          | <b>335,497</b>                | <b>711,983</b>                        | <b>207,921</b>           |
| Flow, gpm              | 280                     | n/a                               | n/a                       | 899                         | 45                     | 670                           | 1437                                  | 420                      |
| Specific Gravity       | 1.40                    | 2.03                              | 2.03                      | 0.99                        | 0.99                   | 0.99                          | 0.99                                  | 0.99                     |
| Cl <sup>-</sup> , ppmw | 12,000                  | 1,000                             | 1,000                     | 2,638                       | 19                     | 19                            | 19                                    | 19                       |
| TSS, %                 | 50.00                   | 90.00                             | 90.00                     | 0.44                        | 0.00                   | 0.00                          | 0.00                                  | 0.00                     |
| TDS, %                 | 2.51                    | 0.21                              | 0.21                      | 0.56                        | 0.02                   | 0.02                          | 0.02                                  | 0.02                     |



| REVISED PUMP DISCHARGE FROM LIMESTONE SLURRY STORAGE TANK |          |     |      |      |     |     |
|---|----------|-----|------|------|-----|-----|
| REV   | DATE     | BY  | CHKD | APPD | ELB | CWS |
| B   | 12/17/04 | RAK |      |      |     |     |

ISSUED FOR INFORMATION

| A   |          |     |      |      |     |     |
|-----|----------|-----|------|------|-----|-----|
| REV | DATE     | BY  | CHKD | APPD | ELB | CWS |
| A   | 10/26/04 | RAK |      |      |     |     |

| DATE      | NO. | DESCRIPTION | APPRO. |
|-----------|-----|-------------|--------|
| REVISIONS |     |             |        |

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

**PARSONS E&C**

|                             |                              |  |
|-----------------------------|------------------------------|--|
| PRELIMINARY STATUS          | DATE                         | REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS. REVIEWED NOT CHECKED.                 |
| APPROVED STATUS             | DATE                         | REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS. |
| ORIGINATING PERSONNEL       | PROFESSIONAL ENGINEER'S SEAL |  |
| DRAWN BY                    | RAK                          |  |
| CHECKED BY                  |                              |  |
| LEAD DESIGNER               |                              |  |
| ENGINEER/TECH SPECIALIST    |                              |  |
| PROJECT ENGINEERING MANAGER |                              |  |
| PROJECT MANAGER             | C. W. SAMUELSON              |  |

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
 BIG SANDY KENTUCKY

**PROCESS FLOW DIAGRAM**  
 REAGENT PREPARATION SYSTEM  
 UNIT 2


DWG. NO. 2-5170000-B

SCALE: NONE  
 MECHANICAL ENGINEERING DIVISION

DATE: \_\_\_\_\_  
 APPROVED BY: \_\_\_\_\_  
 DOCUMENT PREPARED BY: PARSONS E&C

AEP SERVICE CORP.  
 1 RIVERSIDE PLAZA  
 COLUMBUS, OH 43215

DWG. NO. 2-5170001



| ISSUED FOR INFORMATION |          |     |      |      |     |     |
|------------------------|----------|-----|------|------|-----|-----|
| REV                    | DATE     | BY  | CHKD | APPD | ELB | CWS |
| A                      | 10/26/04 | RAK |      |      |     |     |

| REVISIONS |     |             |        |      |     |             |
|-----------|-----|-------------|--------|------|-----|-------------|
| DATE      | NO. | DESCRIPTION | APPRO. | DATE | NO. | DESCRIPTION |
|           |     |             |        |      |     |             |

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTERESTS, AND IS TO BE RETURNED UPON REQUEST."

**PARSONS E&C**

PRELIMINARY STATUS DATE REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS. REVIEWED NOT CHECKED.  
 EBL E.BLANKENBILLER 10-11-04

APPROVED STATUS DATE REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.

ORIGINATING PERSONNEL PROFESSIONAL ENGINEER'S SEAL

DRAWN BY RAK

CHECKED BY

LEAD DESIGNER

ENGINEER/TECH SPECIALIST


PROJECT ENGINEERING MANAGER

PROJECT MANAGER C. W. SAMUELSON

DESIGNED AND PREPARED UNDER THE RESPONSIBLE SUPERVISION OF PER. NO. STATE DATE

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
 BIG SANDY KENTUCKY  
**PROCESS FLOW DIAGRAM**  
 COMBUSTION AIR AND FUEL GAS  
 UNIT 2  
 DWG. NO. 2-5170001-A  
 SCALE: NONE MECHANICAL ENGINEERING DIVISION  
 DR: \_\_\_\_\_  
 CH: \_\_\_\_\_  
 DES: \_\_\_\_\_  
 SUP: \_\_\_\_\_  
 DATE: \_\_\_\_\_  
 APPROVED BY \_\_\_\_\_  
 DOCUMENT PREPARED BY PARSONS E&C  
 AEP AMERICAN ELECTRIC POWER AEP SERVICE CORP. RIVERSIDE PLAZA COLUMBUS, OH 43215





| ISSUED FOR INFORMATION |          |     |             |       |      |
|------------------------|----------|-----|-------------|-------|------|
| REV                    | DATE     | BY  | DESCRIPTION | APPD. | DATE |
| A                      | 10/26/04 | RAK |             | ELB   | CNS  |

THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST.

**PARSONS E&C**

PRELIMINARY STATUS DATE REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS. REVIEWED NOT CHECKED.  
 LOE E.BLANKENBILLER 10-11-04

APPROVED STATUS DATE REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.

ORIGINATING PERSONNEL PROFESSIONAL ENGINEER'S SEAL

DRAWN BY RAK  
 CHECKED BY  
 LEAD DESIGNER  
 ENGINEER/TECH SPECIALIST  
 PROJECT ENGINEERING MANAGER  
 PROJECT MANAGER C. W. SAMUELSON


MECHANICAL ENGINEERING DIVISION  
 DOCUMENT PREPARED BY PARSONS EMC

APPROVED BY

AMERICAN ELECTRIC POWER AEP SERVICE CORP. 1 RIVERSIDE PLAZA COLUMBUS, OH 43215

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
 BIG SANDY KENTUCKY  
**PROCESS FLOW DIAGRAM**  
 ABSORBER ISLAND  
 UNIT 2

DWG. NO. 2-5170003-A  
 SCALE: NONE  
 MECHANICAL ENGINEERING DIVISION  
 DATE: \_\_\_\_\_  
 APPROVED BY: \_\_\_\_\_



| REV | DATE     | BY  | CHKD | ENGR | LEAD ENGR | APP'D | DESCRIPTION                |
|-----|----------|-----|------|------|-----------|-------|----------------------------|
| B   | 10/22/04 | RAK |      |      | ELB       | CWS   | ADDED DEWATERING AREA SUMP |
| A   | 10/28/04 | RAK |      |      | ELB       | CWS   | ISSUED FOR INFORMATION     |

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

**PARSONS E&C**

PRELIMINARY STATUS DATE REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS. REVIEWED NOT CHECKED.  
 LDE E.BLANKENBILLER 10-11-04

APPROVED STATUS DATE REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.

DRAWN BY: RAK  
 CHECKED BY:  
 LEAD DESIGNER:  
 ENGINEER/TECH SPECIALIST:  
 PROJECT ENGINEERING MANAGER:  
 PROJECT MANAGER: C. W. SAMUELSON

PROFESSIONAL ENGINEER'S SEAL

APPROVED BY:

DOCUMENT PREPARED BY PARSONS E&C

APPROVED BY:

AMERICAN ELECTRIC POWER SERVICE CORP. RIVERSIDE PLAZA COLUMBUS, OH 43215

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
 BIG SANDY KENTUCKY


**PROCESS FLOW DIAGRAM**  
 DEWATERING SYSTEM  
 UNIT 2

DWG. NO. 2-5170004-B

SCALE: NONE  
 MECHANICAL ENGINEERING DIVISION

DATE: \_\_\_\_\_


SYSTEM DATE: 10-11-04  
 SYSTEM TIME: 10:41:00 AM



## Appendix B

# Plot Plans and General Arrangement Drawings

## Big Sandy Unit 2



| PRELIMINARY |          |     |      |             |       |
|-------------|----------|-----|------|-------------|-------|
| REV         | DATE     | BY  | CHKD | DESCRIPTION | APP'D |
| A           | 12/20/11 | RAK |      |             |       |

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
 BIG SANDY KENTUCKY  
**SITE LAYOUT**  
**FGD PROJECT**  
**PRESENTATION**


DWG. NO. **2-5070005-A**  
 SCALE: 1"=40'  
 DOCUMENT PREPARED BY PARSONS E&C

**PARSONS E&C**

PRELIMINARY STATUS DATE REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS. REVISIONS NOT CHECKED.  
 APPROVED STATUS DATE REPRESENTS REVISED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.

DESIGNED BY: RAK  
 CHECKED BY:  
 LEAD DESIGNER:  
 ENGINEER/TECH SPECIALIST:  
 PROJECT ENGINEERING NUMBER: N/A  
 PROJECT MANAGER: C. V. SAMUELSON

PROFESSIONAL ENGINEER'S SEAL



- LEGEND:**
1. FGD ABSORBER
  2. FGD ABSORBER BUILDING
  3. GYPSUM DEWATERING BUILDING
  4. REAGENT PREP BUILDING
  5. STACK
  6. ID FANS
  7. FGD SUBSTATION
  8. FGD STATION SERVICE TRANSFORMERS
  9. HYDROCLONE FEED TANK
  10. ABSORBER MAINTENANCE STORAGE TANK
  11. LIMESTONE SLURRY TANK
  12. RECLAIM WATER TANK
  13. SERVICE WATER TANK
  14. LIMESTONE SILO
  15. ID FAN ELECTRICAL BUILDING
  16. IN-DUCT SORBENT UNLOADING & STORAGE SILOS
  17. GYPSUM EMERGENCY STOCKOUT FILE
  18. GYPSUM CONVEYOR
  19. LIMESTONE CONVEYOR
  20. MERCURY REMOVAL BAGHOUSE (FUTURE)
  21. WET ESP (FUTURE)
  22. GYPSUM PILE

| ISSUED FOR REVIEW AND COMMENT |          |     |             |          |
|-------------------------------|----------|-----|-------------|----------|
| REV                           | DATE     | BY  | DESCRIPTION | APPROVED |
| A                             | 10/26/11 | RAK |             |          |

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTERESTS, AND IS TO BE RETURNED UPON REQUEST"

**PARSONS E&C**


PRELIMINARY STATUS DATE REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS. REVIEWED NOT CHECKED.  
 LOC E. BLANKENBILLER10-04-04  
 APPROVED STATUS DATE REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.  
 LIDE  
 ORIGINATING PERSONNEL PROFESSIONAL ENGINEER'S SEAL  
 DRAWN BY RAK  
 CHECKED BY  
 LEAD DESIGNER  
 ENGINEER/TECH SPECIALIST  
 PROJECT ENGINEERING MANAGER N/A  
 PROJECT MANAGER C. W. SAMUELSON

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
BIG SANDY KENTUCKY

**SITE LAYOUT**  
FGD PROJECT  
NORTH OPTION - 1

DWG. NO. 2-5070000B-A  
 SCALE: 1"=40'  
 DATE: 10/26/11  
 DOCUMENT PREPARED BY PARSONS E&C  
 APPROVED BY  
 DATE: 10/26/11  
 AEP SERVICE CORP.  
1 RIVERSIDE PLAZA  
COLUMBUS, OH 43215





- LEGEND:**
1. FGD ABSORBER
  2. FGD ABSORBER BUILDING
  3. GYPSUM DEWATERING BUILDING
  4. REAGENT PREP BUILDING
  5. STACK
  6. ID FANS
  7. FGD SUBSTATION
  8. FGD STATION SERVICE TRANSFORMERS
  9. HYDROCLONE FEED TANK
  10. ABSORBER MAINTENANCE STORAGE TANK
  11. LIMESTONE SLURRY TANK
  12. RECLAIM WATER TANK
  13. SERVICE WATER TANK
  14. LIMESTONE SILO
  15. ID FAN ELECTRICAL BUILDING & STORAGE SILOS
  16. IN-DUCT SORBENT UNLOADING & STORAGE SILOS
  17. GYPSUM EMERGENCY STOCKOUT PILE
  18. GYPSUM CONVEYOR
  19. LIMESTONE CONVEYOR
  20. MERCURY REMOVAL BAGHOUSE (FUTURE)
  21. WET ESP (FUTURE)
  22. GYPSUM PILE

ISSUED FOR REVIEW AND COMMENT

| REV | DATE     | CHKD | BY | DESCRIPTION | APPROV. |
|-----|----------|------|----|-------------|---------|
| A   | 11/23/04 | RAK  |    |             |         |

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
BIG SANDY KENTUCKY  
**SITE LAYOUT**  
FGD PROJECT  
NORTH OPTION - 2/8

DWG. NO. 2-5070000-A  
SCALE: 1"=50'  
DATE: \_\_\_\_\_  
DRAWN BY: \_\_\_\_\_  
CHECKED BY: \_\_\_\_\_  
LEAD DESIGNER: \_\_\_\_\_  
ENGINEER/TECH SPECIALIST: \_\_\_\_\_  
PROJECT ENGINEERING MANAGER: \_\_\_\_\_  
PROJECT MANAGER: \_\_\_\_\_

**PARSONS E&C**

REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS. REVIEWED NOT CHECKED.  
DATE: \_\_\_\_\_

REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "N/A" RETAINS PRELIMINARY STATUS.  
DATE: \_\_\_\_\_


PROFESSIONAL ENGINEER'S SEAL

DATE: \_\_\_\_\_

APPROVED BY: \_\_\_\_\_


DOCUMENT PREPARED BY PARSONS E&C

AMERICAN ELECTRIC POWER SERVICE CORP.  
1 RIVERSIDE PLAZA  
COLUMBUS, OH 43215



LEGEND:

1. FGD ABSORBER
2. FGD ABSORBER BUILDING
3. GYPSUM DEWATERING BUILDING
4. REAGENT PREP BUILDING
5. STACK
6. ID FANS
7. FGD SUBSTATION
8. FGD STATION SERVICE TRANSFORMERS
9. HYDROCLONE FEED TANK
10. ABSORBER MAINTENANCE STORAGE TANK
11. LIMESTONE SLURRY TANK
12. RECLAIM WATER TANK
13. SERVICE WATER TANK
14. LIMESTONE SILO
15. ID FAN ELECTRICAL BUILDING
16. IN-DUCT SORBENT UNLOADING & STORAGE SILOS
17. GYPSUM EMERGENCY STOCKOUT PILE
18. GYPSUM CONVEYOR
19. LIMESTONE CONVEYOR
20. MERCURY REMOVAL BACHOUSE (FUTURE)
21. WET ESP (FUTURE)
22. GYPSUM PILE



| ISSUED FOR INFORMATION |          |     |      |      |             |
|------------------------|----------|-----|------|------|-------------|
| REV                    | DATE     | BY  | CHKD | APPD | DESCRIPTION |
| A                      | 11/03/04 | RAK |      |      |             |

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
 BIG SANDY KENTUCKY  
**SITE LAYOUT**  
 FGD PROJECT  
 NORTH OPTION - 1/8

**PARSONS E&C**

PRELIMINARY STATUS DATE REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS.  
 APPROVED STATUS DATE REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.

ORIGINATING PERSONNEL PROFESSIONAL ENGINEER'S SEAL

DRAWN BY RAK

CHECKED BY

LEAD DESIGNER

ENGINEER/TECH SPECIALIST

PROJECT ENGINEERING MANAGER N/A

PROJECT MANAGER C. W. SAMUELSON

DATE: 01-13-12

DWG. NO. 2-5070000E-A

SCALE: 1"=50'


DOCUMENT PREPARED BY PARSONS E&C

DATE: 01-13-12

APPROVED BY: [Signature]

AMERICAN ELECTRIC POWER

AEP SERVICE CORP.  
 1 RIVERSIDE PLAZA  
 COLUMBUS, OH 43215



- LEGEND:**
1. FGD ABSORBER
  2. FGD ABSORBER BUILDING
  3. GYPSUM DEWATERING BUILDING
  4. REAGENT PREP BUILDING
  5. STACK
  6. ID FANS
  7. FGD SUBSTATION
  8. FGD STATION SERVICE TRANSFORMERS
  9. HYDROCLONE FEED TANK
  10. ABSORBER MAINTENANCE STORAGE TANK
  11. LIMESTONE SLURRY TANK
  12. RECLAIM WATER TANK
  13. SERVICE WATER TANK
  14. LIMESTONE SILO
  15. ID FAN ELECTRICAL BUILDING
  16. IN-DUCT SORBENT UNLOADING & STORAGE SILOS
  17. GYPSUM EMERGENCY STOCKOUT PILE
  18. GYPSUM CONVEYOR
  19. LIMESTONE CONVEYOR
  20. MERCURY REMOVAL BAGHOUSE (FUTURE)
  21. WET ESP (FUTURE)
  22. LIMESTONE PILE

| ISSUED FOR REVIEW AND COMMENT |          |     |      |      |
|-------------------------------|----------|-----|------|------|
| REV                           | DATE     | BY  | CHKD | APPD |
| A                             | 09/29/04 | RAK |      |      |

THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST.

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
BIG SANDY KENTUCKY

**SITE LAYOUT  
FGD PROJECT  
SOUTH OPTION**

DWG. NO. **2-507001A-A**

SCALE: 1" = 30'

DATE: \_\_\_\_\_

APPROVED BY: \_\_\_\_\_

DOCUMENT PREPARED BY: PARSONS E&C

AEP AMERICAN ELECTRIC POWER  
AEP SERVICE CORP.  
1 RIVERSIDE PLAZA  
COLUMBUS, OH 43215

**PARSONS E&C**

PRELIMINARY STATUS DATE: REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS.  
APPROVED STATUS DATE: REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.

ORIGINATING PERSONNEL: PROFESSIONAL ENGINEER'S SEAL

DRAWN BY: RAK

CHECKED BY:


LEAD DESIGNER:

ENGINEER/TECH SPECIALIST:

PROJECT ENGINEERING MANAGER: N/A

PROJECT MANAGER: C. W. SAMUELSON

STATE: OHIO DATE: 11-01-04



- LEGEND:**
1. FGD ABSORBER
  2. FGD ABSORBER BUILDING
  3. GYPSUM DEWATERING BUILDING
  4. REAGENT PREP BUILDING
  5. STACK
  6. ID FANS - UNIT 2
  7. FGD SUBSTATION
  8. FGD STATION SERVICE TRANSFORMERS
  9. HYDROCLONE FEED TANK
  10. ABSORBER MAINTENANCE STORAGE TANK
  11. LIMESTONE SLURRY TANK
  12. RECLAIM WATER TANK
  13. SERVICE WATER TANK
  14. LIMESTONE SILO
  15. ID FAN ELECTRICAL BUILDING & STORAGE SILOS
  16. IN-DUCT SORBENT UNLOADING & STORAGE SILOS
  17. GYPSUM EMERGENCY STOCKOUT PILE
  18. GYPSUM CONVEYOR
  19. LIMESTONE CONVEYOR
  20. MERCURY REMOVAL BAGHOUSE (FUTURE)
  21. WET ESP (FUTURE)
  22. GYPSUM PILE
  23. ID FANS - UNIT 1

| ISSUED FOR REVIEW AND COMMENT |          |     |        |          |
|-------------------------------|----------|-----|--------|----------|
| REV                           | DATE     | BY  | REASON | APPROVED |
| A                             | 12/21/04 | RAK |        |          |

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
BIG SANDY KENTUCKY

**SITE LAYOUT**  
FGD PROJECT  
UNITS 1 & 2

DWG. NO. 12-5070000A-A

SCALE: 1"=50'  
DATE: 12/21/04  
DRAWN BY: RAK  
CHECKED BY:  
LEAD DESIGNER:  
ENGINEER/TECH SPECIALIST:  
PROJECT ENGINEERING MANAGER:  
N/A  
PROJECT MANAGER:  
C. W. SAMUELSON

**PARSONS E&C**

PRELIMINARY STATUS DATE REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS.  
APPROVED STATUS DATE REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "N/C" RETAINS PRELIMINARY STATUS.

ORIGINATING PERSONNEL PROFESSIONAL ENGINEER'S SEAL


DRAWN BY: RAK  
CHECKED BY:  
LEAD DESIGNER:  
ENGINEER/TECH SPECIALIST:  
PROJECT ENGINEERING MANAGER:  
N/A  
PROJECT MANAGER:  
C. W. SAMUELSON

DATE: 12/21/04

APPROVED BY: [Signature]

DOCUMENT PREPARED BY: PARSONS E&C

AMERICAN ELECTRIC POWER SERVICE CORP.  
1 RIVERSIDE PLAZA  
COLUMBUS, OH 43215



- LEGEND:
1. FGD ABSORBER
  2. FGD ABSORBER BUILDING
  3. GYPSUM DEWATERING BUILDING
  4. REAGENT PREP BUILDING
  5. STACK
  6. ID FANS - UNIT 2
  7. FGD SUBSTATION
  8. FGD STATION SERVICE TRANSFORMERS
  9. HYDROCLONE FEED TANK
  10. ABSORBER MAINTENANCE STORAGE TANK
  11. LIMESTONE SLURRY TANK
  12. RECLAIM WATER TANK
  13. SERVICE WATER TANK
  14. LIMESTONE SILO
  15. ID FAN ELECTRICAL BUILDING & STORAGE SILOS
  16. IN-DUCT SORBENT UNLOADING & STORAGE SILOS
  17. GYPSUM EMERGENCY STOCKOUT PILE
  18. GYPSUM CONVEYOR
  19. LIMESTONE CONVEYOR
  20. MERCURY REMOVAL BAGHOUSE (FUTURE)
  21. WET ESP (FUTURE)
  22. GYPSUM PILE
  23. UNIT 23

| ISSUED FOR REVIEW AND COMMENT |          |      |         |     |     |
|-------------------------------|----------|------|---------|-----|-----|
| REV                           | DATE     | CHKD | CHKD BY | ELB | CWS |
| A                             | 12/13/11 | RAK  |         |     |     |

THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETERMINAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST.

**PARSONS E&C**

PRELIMINARY STATUS DATE REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS.  
APPROVED STATUS DATE REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "N/A" RETAINS PRELIMINARY STATUS.

DRAWN BY: RAK  
CHECKED BY: [Blank]  
LEAD DESIGNER: [Blank]  
ENGINEER/TECH SPECIALIST: [Blank]  
PROJECT ENGINEERING MANAGER: N/A  
PROJECT MANAGER: C. V. SAMUELSON

PROFESSIONAL ENGINEER'S SEAL: [Blank]

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
BIG SANDY KENTUCKY


**SITE LAYOUT**  
FGD PROJECT  
UNITS 1 & 2

DWG. NO. 12-507000B-A

SCALE: 1"=50'

DOCUMENT PREPARED BY PARSONS E&C

AMERICAN ELECTRIC POWER  
AEP SERVICE CORP.  
1 RIVERSIDE PLAZA  
COLUMBUS, OH 43215



- LEGEND:
1. FGD ABSORBER
  2. FGD ABSORBER BUILDING
  3. GYPSUM DEWATERING BUILDING
  4. REAGENT PREP BUILDING
  5. STACK
  6. ID FANS - UNIT 2
  7. FGD SUBSTATION
  8. FGD STATION SERVICE TRANSFORMERS
  9. HYDROCLONE FEED TANK
  10. ABSORBER MAINTENANCE STORAGE TANK
  11. LIMESTONE SLURRY TANK
  12. RECLAIM WATER TANK
  13. SERVICE WATER TANK
  14. LIMESTONE SILO
  15. ID FAN ELECTRICAL BUILDING
  16. IN-DUCT SORBENT UNLOADING & STORAGE SILOS
  17. GYPSUM EMERGENCY STOCKOUT PILE
  18. GYPSUM CONVEYOR
  19. LIMESTONE CONVEYOR
  20. MERCURY REMOVAL BAGHOUSE (FUTURE)
  21. WET ESP (FUTURE)
  22. GYPSUM PILE
  23. ID FANS - UNIT 1

CORRECTED NEW FGD TRANSFORMER AREA

|   |          |     |  |     |     |
|---|----------|-----|--|-----|-----|
| B | 12/27/11 | RAK |  | ELB | CWS |
|---|----------|-----|--|-----|-----|

ISSUED FOR REVIEW AND COMMENT

|   |          |     |  |     |     |
|---|----------|-----|--|-----|-----|
| A | 12/21/11 | RAK |  | ELB | CWS |
|---|----------|-----|--|-----|-----|

| REV | DATE | BY | CHECKED | DATE | DESCRIPTION | APPROVED |
|-----|------|----|---------|------|-------------|----------|
|     |      |    |         |      |             |          |

REVISIONS

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED FROM CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST"

**PARSONS E&C**

DESIGN STATUS: PRELIMINARY  
 DATE: 12-07-11  
 REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS.

APPROVED STATUS: REVIEWED  
 DATE: 12-07-11  
 REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.

DRAWN BY: RAK  
 CHECKED BY: [ ]  
 LEAD DESIGNER: [ ]  
 ENGINEER/TECH SPECIALIST: [ ]  
 PROJECT ENGINEERING MANAGER: N/A  
 PROJECT MANAGER: C. W. SAMUELSON

PROFESSIONAL ENGINEER'S SEAL

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
 BIG SANDY KENTUCKY

**SITE LAYOUT  
 FGD PROJECT  
 UNITS 1 & 2**

DWG. NO. 12-5070000-B  
 SCALE: 1"=50'  
 DATE: [ ]


DOCUMENT PREPARED BY PARSONS E&C

AEP SERVICE CORP.  
 1 RIVERSIDE PLAZA  
 COVINGTON, KY 40305


Dated January 13, 2012

Item No. 27(a)  
Attachment 1

- Page 16 of 113
- LEGEND:
- 1 ABSORBER
  - 2 ABSORBER RECYCLE PUMP
  - 3 ABSORBER RECYCLE PUMP DISCHARGE RISER
  - 4 ABSORBER BLEED PUMP
  - 5 ABSORBER AREA SUMP
  - 6 OXIDATION AIR COMPRESSOR
  - 7 HYDROCLONE FEED PUMP
  - 8 AIR COMPRESSOR
  - 9 AIR RECEIVER
  - 10 INSTRUMENT AIR DRYER
  - 11 FLOOR TRENCH
  - 12 STAIRTOWER
  - 13 ELEVATOR
  - 14 EMERGENCY EYE & FACE WASH



PLAN - GROUND FLOOR



| ISSUED FOR REVIEW AND COMMENT |      |    |      |       |       |         |
|-------------------------------|------|----|------|-------|-------|---------|
| REV                           | DATE | BY | CHKD | DESCR | APPD. | PROJECT |
|                               |      |    |      |       |       |         |

REVISIONS

THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST.

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
BIG SANDY KENTUCKY

GENERAL ARRANGEMENT  
FGD BUILDING  
GROUND FLOOR

DWG. NO. 2-5070002A-A

SCALE: 1/8"=1'-0"

OR:

OR:

APPROVED BY:

DOCUMENT PREPARED BY PARSONS E&C

**PARSONS E&C**

PRELIMINARY STATUS DATE REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS.  
APPROVED STATUS DATE REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.

ORIGINATING PERSONNEL PROFESSIONAL ENGINEER'S SEAL

DRAWN BY RAK

CHECKED BY

LEAD DESIGNER

ENGINEER/TECH SPECIALIST

PROJECT ENGINEERING MANAGER N/A

PROJECT MANAGER C. W. SAMUELSON


APPROVED BY: [Signature]

DATE: [Date]


AMERICAN ELECTRIC POWER

AEP SERVICE CORP.  
1 RIVERSIDE PLAZA  
COLUMBUS, OH 43215

DWG NO. 2-507003A



PLAN - GROUND FLOOR  
 REAGENT PREPARATION AREA



| ISSUED FOR REVIEW AND COMMENT |          |     |      |      |             |
|-------------------------------|----------|-----|------|------|-------------|
| REV                           | DATE     | BY  | CHKD | APPD | DESCRIPTION |
| A                             | 09/28/04 | RAK |      | ELB  | CMS         |

REVISIONS

\*THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST.\*

**PARSONS E&C**

PRELIMINARY STATUS DATE REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS.  
 LDE E. BLANKENBILLER 9-28-04 REVIEWED NOT CHECKED.

APPROVED STATUS DATE REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.

LDE

ORIGINATING PERSONNEL PROFESSIONAL ENGINEER'S SEAL

DRAWN BY  
 RAK

CHECKED BY

LEAD DESIGNER

ENGINEER/TECH SPECIALIST

PROJECT ENGINEERING MANAGER

N/A

PROJECT MANAGER  
 C. W. SAMUELSON

PERMITS: PERMITS UNDER THE RESPONSIBLE SUPERVISION OF  
 P.E. NO. 10411 STATE: OH DATE: 10/13/04

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
 BIG SANDY KENTUCKY

GENERAL ARRANGEMENT  
 REAGENT PREP AREA  
 GROUND FLOOR

DWG. NO. 2-507003A-A

SCALE: 1/8"=1'-0"

OR: \_\_\_\_\_

CHK: \_\_\_\_\_


APPROVED BY: \_\_\_\_\_

DATE: \_\_\_\_\_


DOCUMENT PREPARED BY  
 PARSONS E&C

AEP SERVICE CORP.  
 1 RIVERSIDE PLAZA  
 COLUMBUS, OH 43215

DWG. NO. 2-5070004A



PLAN - GROUND FLOOR  
 DEWATERING AREA



| ISSUED FOR REVIEW AND COMMENT |          |     |          |     |     |
|-------------------------------|----------|-----|----------|-----|-----|
| KEY                           | DATE     | BY  | REVISION | ELB | CWS |
| A                             | 09/28/04 | RAK |          |     |     |

| REVISIONS |     |             |       |      |     |
|-----------|-----|-------------|-------|------|-----|
| DATE      | NO. | DESCRIPTION | APPD. | DATE | NO. |
|           |     |             |       |      |     |

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

|                             |  |  |  |
|-----------------------------|--|--|--|
| <b>PARSONS E&amp;C</b>      |  | KENTUCKY POWER COMPANY                                 |  |
| BIG SANDY PLANT             |  | BIG SANDY KENTUCKY                                     |  |
| GENERAL ARRANGEMENT         |  | DEWATERING AREA  |  |
| GROUND FLOOR                |  | DWG. NO. 2-5070004A-A                                  |  |
| SCALE: 1/8" = 1'-0"         |  | DOCUMENT PREPARED BY PARSONS E&C                       |  |
| DRAWN BY RAK                |  | APPROVED BY  |  |
| CHECKED BY                  |  | DATE   |  |
| LEAD DESIGNER               |  | PROJECT ENGINEERING MANAGER                            |  |
| ENGINEER/TECH SPECIALIST    |  | PROJECT MANAGER  |  |
| PROJECT ENGINEERING MANAGER |  | PROJECT MANAGER  |  |
| N/A                         |  | C. W. SAMUELSON  |  |
| PROJECT MANAGER             |  | AEP SERVICE CORP. 1 RIVERSIDE PLAZA COLUMBUS, OH 43216 |  |

# Appendix C

## Process Equipment List

### Big Sandy Unit 2

## Big Sandy Unit 2 Process Equipment List

| Description            |                           |                                     |
|------------------------|---------------------------|-------------------------------------|
| Unit Rating            | MW                        | 800                                 |
| Annual Capacity Factor |                           | 90                                  |
| Chimneys               |                           |                                     |
| No of Shells           |                           | 1                                   |
| Type                   |                           | Reinforced Concrete                 |
| No of Flues per Unit   |                           | 1                                   |
| Design Velocity        | ft/sec                    | 49                                  |
| Flue Diameter          | ft                        | 34                                  |
| Height                 | ft                        | 750 - 1,000                         |
| Shell Base Diameter    | ft                        | ~ 90                                |
| ID Fans                |                           |                                     |
| Type                   |                           | Axial                               |
| No Per Unit            |                           | 2                                   |
| Capacity per fan (TB)  | acfm                      | 1,879,000                           |
| Fan Static (TB)        | In WG                     | 43.6                                |
| Fan Motor Size         | HP                        | 20,000                              |
| Motor Type             |                           |                                     |
| FGD Absorber           |                           |                                     |
| Type                   |                           | TBD                                 |
| Quantity               |                           | 1                                   |
| Design SO2 Removal     | %                         | 98                                  |
| L:G ratio              | gal/1,000 ft <sup>3</sup> | 115                                 |
| Diameter - Spray       | Ft                        | 65                                  |
| Diameter - Rxn Tank    | Ft                        | 65                                  |
| Height - Rxn Tank      | Ft                        | 50                                  |
| Height - Overall       | Ft                        | 155                                 |
| FGD Recycle Pumps      |                           |                                     |
| Quantity               |                           | 6 (5 op, 1 sp)                      |
| Capacity per Pump      | gpm                       | 65,000                              |
| Active Spray Levels    |                           | 5                                   |
| Pumps Per Level        |                           | 1                                   |
| Pump motor size        | hp                        | 2,100/2,350/2,510/2,660/2,820/3,100 |

|  |              |                |
|--|--------------|----------------|
| FGD Bleed Pumps                        |              |                |
| Quantity                               |              | 2 (1 op, 1 sp) |
| Capacity per Pump                      | gpm          | 2,130          |
| Pump motor size                        | hp           | 60             |
| Absorber Agitators                     |              |                |
| Quantity                               |              | 8              |
| Size                                   | hp           | 75             |
| Oxidation Air Blowers                  |              |                |
| Quantity                               |              | 2 (1 op, 1 sp) |
| Capacity per Blower                    | Acfm         | 19,600         |
| Blower motor size                      | hp           | 2,100          |
| Absorber Maintenance Tank              |              |                |
| Quantity                               |              | 1              |
| Capacity                               | gal          | 1,400,000      |
| Diameter x height                      | ft           | 56 x 73        |
| Tank Mixer                             | hp           | 40             |
| Absorber Maintenance Tank Return Pumps |              |                |
| Quantity                               |              | 2 (1 op, 1 sp) |
| Capacity per Pump                      | gpm          | 3,000          |
| Pump motor size                        | hp           | 110            |
| Sump Pit                               |              |                |
| Quantity                               |              | 1              |
| Capacity                               | ft x ft x ft | 10 x 10 x 10   |
| Sump Pump                              |              |                |
| Quantity                               |              | 2 (1 op, 1 sp) |
| Capacity                               | gpm          | 500            |
| Pump motor size                        | hp           | 75             |
| Sump Agitator                          |              |                |
| Quantity                               |              | 1              |
| Motor size                             | hp           | 20             |
| Service Air Compressors                |              |                |
| Quantity                               |              | 2 (1 op, 1 sp) |
| Capacity                               | scfm         | 300            |
| Motor size                             | hp           | 100            |
| Instrument Air Dryer                   |              |                |
| Quantity                               |              | 2 (1 op, 1 sp) |
| Capacity                               | scfm         | 300            |
| Service Air Receiver                   |              |                |
|  |              | 1              |
| Instrument Air Receiver                |              |                |
|  |              | 1              |

|                                   |        |     |
|-----------------------------------|--------|-----|
| <b>Limestone Handling</b>         |        |     |
| Stacking Conveyor                 |        |     |
| Quantity                          |        | 1   |
| Capacity                          | Ton/hr | 300 |
| Motor size                        | hp     | 100 |
| Reclaim Hopper / Hopper Activator |        |     |
| Quantity                          |        | 1   |
| Capacity                          | Ton/hr | 300 |
| Motor size                        | hp     | 20  |
| Reclaim Belt Feeder               |        |     |
| Quantity                          |        | 1   |
| Capacity                          | Ton/hr | 300 |
| Motor size                        | hp     | 20  |
| Reclaim Belt Conveyor             |        |     |
| Quantity                          |        | 1   |
| Capacity                          | Ton/hr | 300 |
| Motor size                        | hp     | 120 |
| Conveyor to Day Bin               |        |     |
| Quantity                          |        | 1   |
| Capacity                          | Ton/hr | 300 |
| Motor size                        | hp     | 20  |

|                                    |         |                |
|------------------------------------|---------|----------------|
| <b>Limestone Preparation</b>       |         |                |
| <b>Limestone Ball Mills</b>        |         |                |
| Quantity                           |         | 2 (1 op, 1 sp) |
| Capacity per Mill                  | Tons/hr | 40             |
| Mill motor size                    | hp      | 2,000          |
| <b>Limestone Day Silos</b>         |         |                |
| Quantity                           |         | 2              |
| Capacity per silo                  | hours   | 8              |
| Height Top Cone                    | ft      | 6              |
| Height Bottom Cone                 | ft      | 11             |
| Total Height                       | ft      | 42             |
| Diameter                           | ft      | 14             |
| <b>Day Silo Bin Vent Filter</b>    |         |                |
| Quantity                           |         | 2 (1 op, 1sp)  |
| Filter Fan Size                    | hp      | 5              |
| <b>Day Silo Bin Activator</b>      |         |                |
| Quantity                           |         | 2 (1 op, 1sp)  |
| Diameter                           | ft      | 12             |
| Motor size                         | hp      | 6              |
| <b>LS Weigh Belt Feeder</b>        |         |                |
| Quantity                           |         | 2 (1 op, 1sp)  |
| Capacity per mill                  | Tons/hr | 40             |
| Motor size                         | hp      | 10             |
| <b>Mill Slurry Tanks</b>           |         |                |
| Quantity                           |         | 2 (1 op, 1sp)  |
| Capacity / Tank                    | minutes | 5              |
| Diameter x height                  | ft      | 9 x 12         |
| Tank Mixer                         | hp      | 8              |
| <b>Mill Slurry Pumps</b>           |         |                |
| Quantity                           |         | 2 (1 op, 1sp)  |
| Capacity per Pump                  | gpm     | 900            |
| Pump motor size                    | hp      | 100            |
| <b>Limestone Slurry Classifier</b> |         |                |
| Quantity                           |         | 2 (1 op, 1sp)  |
| Capacity                           | gpm     | 900            |
| <b>LS Slurry Storage Tanks</b>     |         |                |
| Quantity                           |         | 1              |
| Capacity / Tank                    | hours   | 4              |
| Diameter x height                  | ft      | 25 x 32        |
| Tank Mixer                         | hp      | 40             |

| <b>Limestone Preparation<br/>(continued)</b> |              |                |
|--|--------------|----------------|
| <b>LS Slurry Feed Pumps</b>                  |              |                |
| Quantity                                     |              | 2 (1 op, 1 sp) |
| Capacity per Pump                            | gpm          | 790            |
| Pump motor size                              | hp           | 50             |
| <b>Sump Pit</b>                              |              |                |
| Quantity                                     |              | 1              |
| Capacity                                     | ft x ft x ft | 10 x 10 x 10   |
| <b>Sump Pump</b>                             |              |                |
| Quantity                                     |              | 2 (1 op, 1 sp) |
| Capacity                                     | gpm          | 150            |
| Pump motor size                              | Hp           | 50             |
| <b>Sump Agitator</b>                         |              |                |
| Quantity                                     |              | 1              |
| Motor size                                   | Hp           | 20             |

|  |         |                |
|--|---------|----------------|
| <b>Gypsum Dewatering</b>               |         |                |
| <b>Hydrocyclone Feed Pumps</b>         |         |                |
| Quantity                               |         | 2 (1 op, 1 sp) |
| Capacity per Pump                      |         | 1,200          |
| Pump motor size                        |         | 120            |
| <b>Hydrocyclones</b>                   |         |                |
| Quantity                               |         | 2 (1 op, 1 sp) |
| Capacity per HC                        | gpm     | 1,200          |
| <b>Hydrocyclone Overflow Head Tank</b> |         |                |
| Quantity                               |         | 1              |
| Diameter x height                      | ft      | 9 x 10         |
| Tank Mixer Size                        | hp      | 5              |
| <b>Purge Pumps</b>                     |         |                |
| Quantity                               |         | 2 (1 op, 1 sp) |
| Capacity per Pump                      | gpm     | 250            |
| Pump motor size                        | hp      | 30             |
| <b>Filtrate Tanks</b>                  |         |                |
| Quantity                               |         | 1              |
| Capacity per Tank                      | hours   | 8              |
| Diameter x height                      | ft      | 43 x 56        |
| Tank Mixer Size                        | hp      | 30             |
| <b>Filtrate Return Pumps</b>           |         |                |
| Quantity                               |         | 2 (1 op, 1 sp) |
| Capacity per Pump                      | gpm     | 2,000          |
| Pump motor size                        | hp      | 150            |
| <b>Gypsum Belt Filters</b>             |         |                |
| Quantity                               |         | 2 (1 op, 1 sp) |
| Capacity per Filter                    | Tons/hr | 55             |
| Belt Drive motor size                  | hp      | 10             |
| <b>Vacuum Pumps</b>                    |         |                |
| Quantity                               |         | 2 (1 op, 1 sp) |
| Pump Motor size                        | hp      | 600            |


|                                   |              |                |
|-----------------------------------|--------------|----------------|
| <b>Gypsum Handling</b>            |              |                |
| <b>Gypsum Collecting Conveyor</b> |              |                |
| Quantity                          |              | 1              |
| Capacity                          | Ton/hr       | 55             |
| Motor size                        | hp           | 30             |
| <b>Gypsum Conveyor</b>            |              |                |
| Quantity                          |              | 1              |
| Capacity                          | Ton/hr       | 150            |
| Motor size                        | hp           | 60             |
| <b>Gypsum Transfer Conveyor</b>   |              |                |
| Quantity                          |              | 1              |
| Capacity                          | Ton/hr       | 150            |
| Motor size                        | hp           | 35             |
| <b>Sump Pit</b>                   |              |                |
| Quantity                          |              | 1              |
| Capacity                          | ft x ft x ft | 10 x 10 x 10   |
| <b>Sump Pump</b>                  |              |                |
| Quantity                          |              | 2 (1 op, 1 sp) |
| Capacity                          | gpm          | 150            |
| Pump motor size                   | hp           | 50             |
| <b>Sump Agitator</b>              |              |                |
| Quantity                          |              | 1              |
| Motor size                        | hp           | 20             |

|                         |       |                |
|-------------------------|-------|----------------|
| <b>Makeup Water</b>     |       |                |
| Makeup Water Tank       |       |                |
| Quantity                |       | 1              |
| Capacity per Tank       | hours | 1              |
| Diameter x height       | ft    | 25 x 32        |
| FGD Service Water Pumps |       |                |
| Quantity                |       | 2 (1 op, 1 sp) |
| Capacity per Pump       | gpm   | 500            |
| Pump motor size         | hp    | 70             |
| BOP Service Water Pumps |       |                |
| Quantity                |       | 2 (1 op, 1 sp) |
| Capacity per Pump       | gpm   | 1,500          |
| Pump motor size         | hp    | 150            |

## Appendix D

# Conceptual Electrical One Line Diagram and Conceptual Electrical Load List

## Big Sandy Unit 2



| ISSUED FOR INFORMATION |          |     |      |      |             |          |
|------------------------|----------|-----|------|------|-------------|----------|
| REV                    | DATE     | BY  | CHKD | APPD | DESCRIPTION | APPROVED |
| A                      | 12/17/04 | AJM |      |      |             |          |

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

**PARSONS E&C**

PRELIMINARY STATUS DATE 12/07/04 REPRESENTS GENERAL DESIGN CONCEPTS BASED ON ASSUMPTIONS. REVIEWED NOT CHECKED.

APPROVED STATUS DATE REPRESENTS REVIEWED AND APPROVED DESIGN. ANY PORTION MARKED "HOLD" RETAINS PRELIMINARY STATUS.

ORIGINATING PERSONNEL PROFESSIONAL ENGINEER'S SEAL

DRAWN BY  
 CHECKED BY  
 LEAD DESIGNER  
 ENGINEER/TECH SPECIALIST  
 PROJECT ENGINEERING MANAGER  
 PROJECT MANAGER  
 CW SAMUELSON

APPROVED BY

PROJECT MANAGER  
 CW SAMUELSON

PROJECT MANAGER  
 CW SAMUELSON

KENTUCKY POWER COMPANY  
**BIG SANDY PLANT**  
 BIG SANDY KENTUCKY

ELECTRICAL  
 UNIT 2 FGD  
 CONCEPTUAL ONE LINE DIAGRAM

DWG. NO. AEBS-2-SK-EZ-206-001-A

SCALE: ELECTRICAL & CONTROLS ENGINEERING DIV.

DOCUMENT PREPARED BY PARSONS E&C

AEP SERVICE CORP.  
 1 RIVERSIDE PLAZA  
 COLUMBUS, OH 43215

**BIG SANDY UNIT 2 FGD  
 CONCEPTUAL ELECTRICAL LOAD LIST  
 CONNECTED LOADS**

| BUS                           | LOAD                                | HP     | KVA | KW  | AMPS | COMMENTS  |
|-------------------------------|-------------------------------------|--------|-----|-----|------|---|
| <b>13.8KV FGD BUS A</b>       | ID FAN A                            | 20,000 |     |     |      |   |
| <b>4.16KV FGD BUS A</b>       | RECYCLE PP A                        | 2,600  |     |     |      |   |
|                               | RECYCLE PP B                        | 2,600  |     |     |      |   |
|                               | RECYCLE PP C                        | 2,600  |     |     |      |   |
|                               | OXIDATION AIR BLOWER A              | 2,100  |     |     |      |   |
|                               | BALL MILL A                         | 2,000  |     |     |      |   |
|                               | DEWATERING VACUUM PP A              | 600    |     |     |      |   |
| <b>480V FGD BUS A</b>         | ABSORBER MAINT TANK RETURN PP A     | 110    |     |     |      |   |
|                               | GYP DEWATERING FILTRATE RETURN PP A | 150    |     |     |      |   |
|                               | RAW WATER PP A                      | 150    |     |     |      | Assumed possible load   |
|                               | BOP SERVICE WATER PP A              | 150    |     |     |      |   |
|                               | HYDROCYCLONE FEED PP A              | 120    |     |     |      |   |
| <b>480V FGD COMMON BUS A</b>  |                                     |        |     |     |      | No directly connected end loads   |
| <b>480V COMMON LOAD MCC 1</b> | FGD BLDG EXHAUST FANS               |        |     |     | 47   | Mitchell = 10@10HP (14FLA ea); demand factor: 0.5. 70A total<br>Big Sandy - use 2/3 of Mitchell value due to smaller FGD Building size. 47A total               |
|                               | FGD BLDG ELEVATOR RM EXHAUST FAN    | 0.5    |     |     |      | Value based on Mitchell   |
|                               | DCS/BATT ROOM A/C UNIT FEED #1      |        |     | 75  |      | Based on Mitchell. Assume this unit running; Common Load MCC 2 unit idle.   |
|                               | FGD BLDG UNIT HEATERS               |        |     |     | 177  | Mitchell PP1/PP2 = 14@10kW plus 26@15kW; demand factor: 0.5. 265kW total<br>Big Sandy - use 2/3 of Mitchell value due to smaller FGD Building size. 177kW total |
|                               | SUBSTA XFMR PP FEED #1              |        | 125 |     |      | Alternate to Common Load MCC 2 Feed #2  |
|                               | SUBSTA UTILITIES FEED               |        | 150 |     |      | Value based on Mitchell assumption  |
|                               | CHIMNEY AOL                         |        | 8   |     |      | Value based on Mitchell   |
|                               | CEMS FEED #1                        |        |     |     | 100  | Alternate to Common Load MCC 2 Feed #2  |
|                               | CHIMNEY ELEVATOR                    |        | 50  |     |      | Value based on Mitchell   |
|                               | FGD POTABLE WATER BOOSTER PP 1      | 5      |     |     |      | Assumed load and value; based on Mitchell   |
|                               | FGD BLDG INSTANT HOT WATER HTR      |        |     | 130 |      | Assumed Battery Room eyewash/shower; based on Mitchell  |
|                               | 120/208V DISTRIBUTION PANEL XFMR    |        | 45  |     |      |   |
| <b>480V COMMON LOAD MCC 3</b> | LIMESTONE PREP BLDG UNIT HEATERS    |        |     | 140 |      | Mitchell = 5@40kW; demand factor: 0.7. 140kW total. Big Sandy - use same as Mitchell  |
|                               | LIMESTONE PREP BLDG ROOF EXH FANS   |        |     |     | 42   | Mitchell = 6@10HP(14FLA ea); demand factor: 0.5. 42A total. Big Sandy - use same as Mitchell  |
|                               | 120/208V DISTRIBUTION PANEL XFMR    |        | 45  |     |      |   |
| <b>480V ABSORBER MCC A</b>    | FGD BLEED PP A                      | 60     |     |     |      |   |
|                               | ABSORBER REACTION TK AGITATOR A     | 75     |     |     |      |   |
|                               | ABSORBER REACTION TK AGITATOR B     | 75     |     |     |      |   |
|                               | ABSORBER REACTION TK AGITATOR C     | 75     |     |     |      |   |
|                               | ABSORBER REACTION TK AGITATOR D     | 75     |     |     |      |   |
|                               | ABSORBER AREA SUMP PP A             | 75     |     |     |      |   |
|                               | ABSORBER AREA SUMP AGITATOR         | 20     |     |     |      |   |

**BIG SANDY UNIT 2 FGD  
 CONCEPTUAL ELECTRICAL LOAD LIST  
 CONNECTED LOADS**

|                                  |                                     |        |    |     |  |
|----------------------------------|-------------------------------------|--------|----|-----|--|
|                                  | SERVICE AIR COMPRESSOR A            | 100    |    |     |  |
|                                  | FGD SERVICE WATER PP A              | 70     |    |     |  |
|                                  | INSTRUMENT AIR DRYER SKID (HEATER)  |        |    | 50  |  |
|                                  | BATTERY CHARGER 1                   |        | 40 |     |  |
|                                  | UPS MAIN FEED                       |        | 30 |     |  |
|                                  | 120/208V DISTRIBUTION PANEL XFMR    |        | 45 |     |  |
|                                  |                                     |        |    |     |  |
| <b>480V LIMESTONE PREP MCC A</b> | DAY BIN A VENT FILTER               | 5      |    |     |  |
|                                  | DAY BIN A ACTIVATOR                 | 6      |    |     |  |
|                                  | ACTIVATOR A OUTPUT BELT FEEDER      | 10     |    |     | Assumed name and HP rating               |
|                                  | LIMESTONE WEIGH BELT FEEDER A       | 10     |    |     |  |
|                                  | MILL SLURRY TANK A MIXER            | 8      |    |     |  |
|                                  | MILL SLURRY PUMP A                  | 100    |    |     |  |
|                                  | LIMESTONE SLURRY STORAGE TANK MIXER | 40     |    |     |  |
|                                  | LIMESTONE SLURRY FEED PP A          | 50     |    |     |  |
|                                  | LIMESTONE PREP SUMP PUMP A          | 50     |    |     |  |
|                                  | LIMESTONE PREP SUMP AGITATOR        | 20     |    |     |  |
|                                  | 120/208V DISTRIBUTION PANEL XFMR    |        | 45 |     |  |
|                                  |                                     |        |    |     |  |
| <b>480V GYPSUM DEWATER MCC A</b> | HYDROCYCLONE FEED TANK AGITATOR     | 10     |    |     |  |
|                                  | HYDROCYC OVERFLOW HEAD TANK MIXER   | 5      |    |     |  |
|                                  | HEAD TANK PURGE PP A                | 30     |    |     |  |
|                                  | VACUUM BELT FILTER A                | 10     |    |     |  |
|                                  | GYPSUM DEWATERING SUMP PP A         | 50     |    |     |  |
|                                  | CAKE WASH PP A                      | 3      |    |     |  |
|                                  | VACUUM RECEIVER PP A                | ?      |    |     |  |
|                                  | 120/208V DISTRIBUTION PANEL XFMR    |        | 45 |     |  |
|                                  |                                     |        |    |     |  |
| <b>480V ID FAN MCC A</b>         | ID FAN A AUXILIARIES                |        |    | 200 | Assumption, based on Mitchell assumption |
|                                  | ID FAN A INLET ISOL DAMPER          | 75     |    |     |  |
|                                  | ID FAN A OUTLET ISOL DAMPER         | 60     |    |     |  |
|                                  | ID FAN A INLT ISO DMPR SEAL AIR FAN | 100    |    |     |  |
|                                  | 120/208V DISTRIBUTION PANEL XFMR    |        | 45 |     |  |
|                                  |                                     |        |    |     |  |
| <b>13.8KV FGD BUS B</b>          | ID FAN B                            | 20,000 |    |     |  |
|                                  |                                     |        |    |     |  |
| <b>4.16KV FGD BUS B</b>          | RECYCLE PP D                        | 2,600  |    |     |  |
|                                  | RECYCLE PP E                        | 2,600  |    |     |  |
|                                  | RECYCLE PP F                        | 2,600  |    |     |  |
|                                  | OXIDATION AIR BLOWER B              | 2,100  |    |     |  |
|                                  | BALL MILL B                         | 2,000  |    |     |  |
|                                  | DEWATERING VACUUM PP B              | 600    |    |     |  |
|                                  |                                     |        |    |     |  |

**BIG SANDY UNIT 2 FGD  
 CONCEPTUAL ELECTRICAL LOAD LIST  
 CONNECTED LOADS**

|                                  |                                     |     |     |     |  |
|----------------------------------|-------------------------------------|-----|-----|-----|--|
| <b>480V FGD BUS B</b>            | ABSORBER MAINT TANK RETURN PP B     | 110 |     |     |  |
|                                  | GYP DEWATERING FILTRATE RETURN PP B | 150 |     |     |  |
|                                  | RAW WATER PP B                      | 150 |     |     |  |
|                                  | BOP SERVICE WATER PP B              | 150 |     |     |  |
|                                  | HYDROCYCLONE FEED PP B              | 120 |     |     |  |
|                                  |                                     |     |     |     |  |
| <b>480V FGD COMMON BUS B</b>     |                                     |     |     |     | No directly connected end loads  |
|                                  |                                     |     |     |     |  |
| <b>480V COMMON LOAD MCC 2</b>    | OX AIR COMP & ELEC EQ RM FANS       |     |     |     | Mitchell = 7@15HP (21FLA ea); demand factor: 0.5. 74A total                        |
|                                  |                                     |     |     | 49  | Big Sandy - use 2/3 of Mitchell value due to smaller FGD Building size. 49A total  |
|                                  | DCS/BATT ROOM A/C UNIT FEED #2      |     | 75  |     | Based on Mitchell. Assume this unit idle; Common Load MCC 1 unit running.          |
|                                  | FGD BLDG UNIT HTRS                  |     |     |     | Mitchell PP3/PP4 = 21@10kW plus 1@5kW; demand factor: 0.5. 108kW total             |
|                                  |                                     |     | 72  |     | Big Sandy - use 2/3 of Mitchell value due to smaller FGD Building size. 72kW total |
|                                  | FGD BLDG LOUVERS                    |     |     |     | Mitchell = 39@50W = 1.95kW intermittent; demand factor: 0.2 <1kW; ignore           |
|                                  | FGD BLDG ELEVATOR                   | 20  |     |     | Assumed load and value; based on Mitchell  |
|                                  | SUBSTA XFMR PP FEED #2              |     | 125 |     | Alternate to Common Load MCC 1 Feed #1   |
|                                  | CHIMNEY GENERAL SERVICE PWR FEED    |     | 237 |     | Value based on Mitchell  |
|                                  | CEMS FEED #2                        |     |     | 100 | Alternate to Common Load MCC 1 Feed #1   |
|                                  | FGD POTABLE WATER BOOSTER PP 2      | 5   |     |     |  |
|                                  | 120/208V DISTRIBUTION PANEL XFMR    |     | 45  |     |  |
|                                  |                                     |     |     |     |  |
| <b>480V COMMON LOAD MCC 4</b>    | GYP SUM DEWATER BLDG UNIT HEATERS   |     |     |     | Mitchell = 7@40kW; demand factor: 0.7. 196kW total.                                |
|                                  |                                     |     | 147 |     | Big Sandy - use 3/4 of Mitchell value due to smaller GD Building size. 147kW total |
|                                  | GYP SUM DEWATER BLDG ROOF EXH FANS  |     |     |     | Mitchell = 4@10HP(14FLA ea); demand factor: 0.5. 28A total.                        |
|                                  |                                     |     |     | 21  | Big Sandy - use 3/4 of Mitchell value due to smaller GD Building size. 21A total   |
|                                  | 120/208V DISTRIBUTION PANEL XFMR    |     | 45  |     |  |
|                                  |                                     |     |     |     |  |
| <b>480V ABSORBER MCC B</b>       | FGD BLEED PP B                      | 60  |     |     |  |
|                                  | ABSORBER REACTION TK AGITATOR E     | 75  |     |     |  |
|                                  | ABSORBER REACTION TK AGITATOR F     | 75  |     |     |  |
|                                  | ABSORBER REACTION TK AGITATOR G     | 75  |     |     |  |
|                                  | ABSORBER REACTION TK AGITATOR H     | 75  |     |     |  |
|                                  | ABSORBER MAINT TANK MIXER           | 40  |     |     |  |
|                                  | ABSORBER AREA SUMP PP B             | 75  |     |     |  |
|                                  | SERVICE AIR COMPRESSOR B            | 100 |     |     |  |
|                                  | FGD SERVICE WATER PP B              | 70  |     |     |  |
|                                  | INSTRUMENT AIR DRYER SKID (HEATER)  |     |     | 50  |  |
|                                  | BATTERY CHARGER 2                   |     | 40  |     |  |
|                                  | UPS ALTERNATE FEED                  |     | 30  |     |  |
|                                  | 120/208V DISTRIBUTION PANEL XFMR    |     | 45  |     |  |
|                                  |                                     |     |     |     |  |
| <b>480V LIMESTONE PREP MCC B</b> | DAY BIN B VENT FILTER               | 5   |     |     |  |
|                                  | DAY BIN B ACTIVATOR                 | 6   |     |     |  |
|                                  | ACTIVATOR B OUTPUT BELT FEEDER      | 10  |     |     | Assumed name and HP rating   |

**BIG SANDY UNIT 2 FGD  
 CONCEPTUAL ELECTRICAL LOAD LIST  
 CONNECTED LOADS**

|                                  |                                      |     |    |     |  |
|----------------------------------|--------------------------------------|-----|----|-----|--|
|                                  | LIMESTONE WEIGH BELT FEEDER B        | 10  |    |     |  |
|                                  | MILL SLURRY TANK B MIXER             | 8   |    |     |  |
|                                  | MILL SLURRY PUMP B                   | 100 |    |     |  |
|                                  | LIMESTONE SLURRY FEED PP B           | 50  |    |     |  |
|                                  | LIMESTONE PREP SUMP PUMP B           | 50  |    |     |  |
|                                  | 120/208V DISTRIBUTION PANEL XFMR     |     | 45 |     |  |
|                                  |                                      |     |    |     |  |
| <b>480V GYPSUM DEWATER MCC B</b> | HEAD TANK PURGE PP B                 | 30  |    |     |  |
|                                  | FILTRATE TANK MIXER                  | 30  |    |     |  |
|                                  | VACUUM BELT FILTER B                 | 10  |    |     |  |
|                                  | GYPSUM DEWATERING SUMP PP B          | 50  |    |     |  |
|                                  | GYPSUM DEWATERING SUMP AGITATOR      | 20  |    |     |  |
|                                  | CAKE WASH PP B                       | 3   |    |     |  |
|                                  | VACUUM RECEIVER PP B                 | ?   |    |     |  |
|                                  | 120/208V DISTRIBUTION PANEL XFMR     |     | 45 |     |  |
|                                  |                                      |     |    |     |  |
| <b>480V ID FAN MCC B</b>         | ID FAN B AUXILIARIES                 |     |    | 200 | Assumption, based on Mitchell assumption |
|                                  | ID FAN B INLET ISOL DAMPER           | 75  |    |     |  |
|                                  | ID FAN B OUTLET ISOL DAMPER          | 60  |    |     |  |
|                                  | ID FAN B INLT ISOL DMPR SEAL AIR FAN | 100 |    |     |  |
|                                  | 120/208V DISTRIBUTION PANEL XFMR     |     | 45 |     |  |
|                                  |                                      |     |    |     |  |
| <b>LIMESTONE HANDLING (480V)</b> | STACKING CONVEYOR                    | 100 |    |     |  |
|                                  | STACKER TELESCOPIC SPOUT             | 10  |    |     | Possible load, HP based on Mitchell      |
|                                  | RECLAIM HOPPER/HOPPER ACTIVATOR      | 20  |    |     |  |
|                                  | RECLAIM BELT FEEDER                  | 20  |    |     |  |
|                                  | RECLAIM BELT CONVEYOR                | 120 |    |     |  |
|                                  | MAGNETIC SEPARATOR RECTIFIER         |     | 5  |     | Possible load, KW based on Mitchell      |
|                                  | MAGNETIC SEPARATOR BELT DRIVE        | 3   |    |     | Possible load, HP based on Mitchell      |
|                                  | DIVERTER GATE                        | 2   |    |     | Possible load, HP based on Mitchell      |
|                                  | CONVEYOR TO DAY BINS                 | 20  |    |     |  |
|                                  | CONVEYOR TO SILO                     | 40  |    |     | Possible load, HP based on Mitchell      |
|                                  | 120/208V DISTRIBUTION PANEL XFMR     |     | 45 |     |  |
|                                  |                                      |     |    |     |  |
| <b>GYPSUM HANDLING (480V)</b>    | GYPSUM COLLECTING CONVEYOR           | 30  |    |     |  |
|                                  | GYPSUM CONVEYOR                      | 60  |    |     |  |
|                                  | GYPSUM TRANSFER CONVEYOR             | 35  |    |     |  |
|                                  | 120/208V DISTRIBUTION PANEL XFMR     |     | 45 |     |  |